Ventsim Software

Ventsim Visual™

Standard, Advanced and Premium Versions

(Version 3.8)

Ventsim Visual™ User Guide



Ventsim Visual™ User Guide



Volume 1: Version 3.8

The author and distributors have no liability to the licensee or any other person or entity for any damage or loss, including special, incidental or consequential damages caused by this product directly or indirectly.

The software is supplied as is without warranty of any kind, either expressed or implied. Warranties of merchantability or of fitness for any purpose are specifically disclaimed.

© Ventsim Software

By Chasm Consulting

PO BOX 1457

CAPALABA QLD AUSTRALIA 4157

admin@ventsim.com

Preface

This manual presents a guide to the effective use of Ventsim Visual™ ventilation software for mine ventilation simulation and design. It does not profess to be a ventilation engineering guide and as such should not be used as a substitute for existing ventilation texts on underground ventilation and environmental engineering.

The manual may contain simplifications and does not attempt to explain many of the complex concepts and methods used in mine environmental engineering. It is highly recommended that users of Ventsim Visual™ have at least a basic understanding of ventilation and simulation theory in order to correctly input and interpret the program functions and results.

The solutions and methods presented in Ventsim are based on the published work of many talented individuals and research organisation over many decades. Many excellent texts and papers exist for mine ventilation, not the least which is the late Malcolm J McPherson's 'Subsurface Ventilation and Environmental Engineering', from which Ventsim Visual™ draws much of the methodology for thermodynamic and other simulation.

Finally, special thanks to Dr Rick Brake for his continued assistance in the development of Ventsim Visual.

Table of Contents

SECTION 1 : PROGRAM FUNCTIONS

1	VENTSIM VISUAL™ – VERSION 3 – WHAT'S NEW?	16
2	VENTSIM VISUAL™ – AN INTRODUCTION	17
3	VENTSIM CLASSIC™ TO VISUAL GUIDE	21
4	THE VIEW WINDOW	25
5	THE MENU BAR	36
6	THE VIEW TOOLBAR	75
7	THE ACTION TOOLBAR	78
8	THE DATA TOOLBAR	93
9	THE EDIT BOX	97
10	THE POPUP CONTEXT MENU	125
11	PRESETS	128
12	SETTINGS	133
13	HEAT ASSISTANT	160
14	FANS	165

SECTION 2 : PROGRAM USE

15	BUILDING A VENTILATION MODEL	171
16	AUXILLIARY VENTILATION AND DUCTS	184
17	CONTAMINANT SIMULATION (STEADY STATE)	189
18	DYNAMIC SIMULATION (ADVANCED)	193
19	MULTI GAS SIMULATION (ADVANCED)	200
20	THERMODYNAMIC SIMULATION (ADVANCED)	205
21	DIESEL PARTICULATE SIMULATION (DPM)	213
22	STAGING – (ALL VERSIONS)	217
23	VENTFIRE™ –SCENARIO SIMULATION (PREMIUM)	224
24	LIVEVIEW™ (PREMIUM)	238
25	RADON SIMULATION (PREMIUM)	250
26	FINANCIAL OPTIMISATION (ADVANCED)	253
27	TUTORIAL - MODEL EXAMPLES	261
28	APPENDIX A – GLOSSARY OF TERMS	277
29	APPENDIX B – SUMMARY OF DATA TYPES	279
30	APPENDIX C – ICON PICTURE GUIDE	286
31	APPENDIX D – DISPLAY PROBLEMS	292
32	APPENDIX E – SIMULATION ERRORS	295
33	APPENDIX F – SHORTCUT KEYS	300
34	APPENDIX TABLE OF FIGURES	301

Table of Contents Detailed

1 VENTSIM VISUAL™ – VERSION 3 – WHAT'S NEW? 16
2 VENTSIM VISUAL™ – AN INTRODUCTION 17
2.1. About Ventsim Visual™ 18
2.2. Computer Hardware Requirements 19
3 VENTSIM CLASSIC™ TO VISUAL GUIDE 21
3.1. Display 21
3.2. Animation 22
3.3. Elevation Database (Levels) 22
3.4. Airways 22
3.5. Data 23
3.5.1. Colour and Data Manager 23
3.6. Coordinates 23
3.7. Editing and Information 23
3.7.1. The Edit Box 23
3.7.2. The Information Tab 23
3.7.3. Modifying Data 23
3.8. Referenced Graphics 23
3.9. Experiment! 24
4 THE VIEW WINDOW 25
4.1. Point of Focus 26
4.1.1. Moving the point of focus. 26
4.2. Multiple Windows 27
4.2.1. Docked Windows 27
4.2.2. Undocked Windows 27
4.2.3. The Active Window 27
4.2.4. Drawing between windows. 28
4.3. User Control Summary 29
4.4. The Edit Plane 30
4.5. Drawing in the Third Dimension 31
4.5.1. The True Vertical Guide 31
4.5.2. Drawing Airways 31
4.5.3. Manual Coordinate Entry 32
4.5.4. Moving Airways 33
4.5.1. Moving / Copying Icons 34
4.5.1. Copying Airways 35
5 THE MENU BAR 36
5.1. File Menu 36
5.1.1. New / Close 36
5.1.2. Open 36
5.1.3. Merge 37
5.1.4. Save 37
5.1.5. Save As 37
5.1.6. Master Link 37
5.1.7. Defaults 38
5.1.8. Inherit 39
5.1.9. Icons 39
5.1.10. File Tools 40
5.1.11. Save Picture 41
5.1.12. Import 41
5.1.13. Export DXF 45
5.1.14. Manage References 45
5.1.15. Title Note 46

5.1.16. File Memo *46*
5.1.17. Page Setup / Print / Print Preview *46*
5.1.18. Previous File Listing *46*
5.1.19. Load Demonstration *46*
5.1.20. License Manager *46*
5.1.21. Exit *48*
5.2. EDIT MENU 49
5.2.1. Undo *49*
5.2.2. Redo *49*
5.2.3. Copy and Paste Airways *49*
5.2.4. Clone and Apply Attributes *49*
5.2.5. New Airways *50*
5.2.6. Find / Find Next / Find ALL *51*
5.2.7. Highlight or Select All *51*
5.3. VIEW MENU 51
5.3.1. Fit All *51*
5.3.2. Show All *51*
5.3.3. Reset Display *52*
5.3.4. Quick View *52*
5.3.5. Copy to clipboard *52*
5.3.6. Copy to clipboard (all) *52*
5.3.7. Copy to clipboard HI-RES *52*
5.3.8. Snapshot *52*
5.3.9. Set Edit Centre *53*
5.3.10. Show All Elevations *53*
5.3.11. Show All Layers *53*
5.3.12. Hide Zero Flow *53*
5.3.13. Hide Excluded *53*
5.4. SAVED VIEW MENU 53
5.4.1. Save View *53*
5.4.2. Delete View *53*
5.4.3. Saved Views *53*
5.5. RUN MENU 55
5.5.1. Airflows [ALL] *55*
5.5.2. Thermo-dynamics [ADVANCED] *55*
5.5.3. Diesel particulates [ADVANCED] *56*
5.5.4. Dynamic Simulations [ADVANCED] *56*
5.5.5. VentFIRE™ [PREMIUM] *56*
5.5.6. Recirculation [ADVANCED] *56*
5.5.7. Financial Simulation *57*
[ADVANCED] *57*
5.5.8. Contaminant Simulations *57*
5.5.9. Summary *57*
5.6. CONNECT MENU 61
5.6.1. LiveVIEW™ *61*
5.6.2. Ventlog™ *61*
5.7. TOOLS MENU 62
5.7.1. Fans *62*
5.7.1. Levels *62*
5.7.2. Stages *62*
5.7.3. Spreadsheet *63*
5.7.4. Filter *64*
5.7.5. Binding *66*
5.7.6. Duplicates *67*
5.7.7. Convert To 3D *68*

5.7.1. Utilities ... *69*
5.7.2. Airways ... *70*
5.7.3. Auto Name ... *70*
5.7.4. Troubleshoot ... *71*
5.7.5. Reset Model ... *71*
5.8. SETTINGS ... 71
5.8.1. Presets ... *71*
5.8.2. Units ... *72*
5.8.3. Natural Ventilation ... *73*
5.8.4. Compressible Flows ... *73*
5.8.5. Simulation Accuracy ... *73*
5.8.6. Settings ... *73*
5.9. WINDOWS MENU ... 74
5.9.1. Fit All ... *74*
5.9.2. New Window ... *74*
5.9.3. Zoom Out ... *74*
5.9.4. Tile ... *74*
5.9.5. Auto Arrange ... *74*
6 THE VIEW TOOLBAR ... 75
6.1.1. Fit All ... *75*
6.1.2. Solid / Wireframe ... *75*
6.1.3. Grid ... *75*
6.1.4. Nodes ... *75*
6.1.5. Icons ... *75*
6.1.6. Arrows ... *75*
6.1.7. References ... *75*
6.1.8. Limit Data ... *75*
6.1.9. Text ... *76*
6.1.1. Transparency ... *76*
6.1.2. Move Toolbar ... *76*
6.1.3. Hide Toolbar ... *77*
6.1.1. Scale Toolbar ... *77*
7 THE ACTION TOOLBAR ... 78
7.1. FILE INPUT AND OUTPUT FUNCTIONS ... 78
7.1.1. New File ... *78*
7.1.2. Open File ... *78*
7.1.3. Save File ... *78*
7.2. UTILITY FUNCTIONS ... 78
7.2.1. Reset Display ... *78*
7.2.2. Undo ... *78*
7.2.3. Redo ... *78*
7.2.4. Create New Window ... *78*
7.2.5. Show All ... *78*
7.2.6. Snapshot ... *79*
7.2.7. Find ... *79*
7.2.8. Lock ... *79*
7.2.9. Perspective View ... *80*
7.2.10. Flow Animation ... *82*
7.2.11. Stage ... *82*
7.3. EDITING FUNCTIONS ... 82
7.3.1. View ... *83*
7.3.2. Add ... *83*
7.3.3. Edit ... *85*
7.3.4. Select ... *86*
7.3.5. Multi Select Options ... *86*

7.3.6. Delete ... *86*
7.3.7. Deletion Options ... *86*
7.3.8. Block ... *87*
7.3.9. Move ... *87*
7.3.10. Copy ... *88*
7.3.11. Reverse ... *88*
7.3.12. Insert Node ... *88*
7.3.13. Contaminant ... *88*
7.3.14. Message Boxes ... *88*
7.3.1. Reverse ... *89*
7.3.2. Contaminant ... *89*
7.3.3. Monitor ... *90*
7.3.4. Filter ... *90*
7.4. SIMULATION FUNCTIONS ... 90
7.4.1. Airflow Simulation ... *90*
7.4.2. Heat Simulation [ADVANCED] ... *90*
7.4.3. Contaminant Simulation ... *90*
7.4.4. Recirculation [ADVANCED] ... *92*
7.4.5. Financial Simulation [ADVANCED] ... *92*
8 THE DATA TOOLBAR ... 93
8.1.1. Data Category ... *93*
8.1.2. Data Type ... *94*
8.1.3. Dynamic Text Size ... *94*
8.1.4. Favourites ... *94*
8.1.1. Scaling ... *95*
8.1.2. Display Manager ... *95*
9 THE EDIT BOX ... 97
9.1. EDIT BOX – FILE MENU ... 97
9.1.1. File > SNAPSHOT ... *97*
9.2. EDIT BOX – EDIT MENU ... 97
9.2.1. Select Airways ... *97*
9.3. EDIT BOX – TOOLS MENU ... 99
9.3.1. Tools – Set Fix Flow Resistance / Orifice ... *99*
9.3.2. Pressure Survey Tools ... *99*
9.3.3. Apply Gradient Slope ... *99*
9.3.4. Distribute Rock Age ... *99*
9.3.5. Convert Fixed Resistance to Friction Factors ... *99*
9.3.6. Convert Linear Resistance to Friction Factors ... *99*
9.4. AIRWAY TAB ... 99
9.4.1. Airway Names, Coordinates and Stages ... *101*
9.4.2. Airway Size ... *101*
9.4.3. Airway Options ... *103*
9.4.4. Airway Attributes ... *105*
9.4.5. PQ Surveys ... *107*
9.5. FANS ... 108
9.5.1. Fan Duty Point ... *110*
9.5.2. Fans Stalled, Low Pressure or Negated ... *111*
9.5.3. Fan Pressure Curve ... *111*
9.5.4. Fan Efficiency Curve ... *111*
9.5.5. Fan Power Curve ... *111*
9.6. HEAT TAB (ADVANCED VERSION) ... 112
9.6.1. Heat and Cooling ... *112*
9.6.2. Point Sources ... *112*
9.6.3. Linear Sources ... *113*
9.6.4. Fixed Data ... *114*

9.6.5. Rock Conditions ... *115*
9.6.6. Contaminant ... *117*
9.6.7. Contaminant Options (Dynamic) ... *117*
9.6.8. Sourcing Location Tools ... *118*
9.7. INFORMATION ... 119
9.7.1. Fan and Fixed Information ... *119*
9.7.2. Pressure Information ... *121*
9.7.3. Heat Data ... *121*
9.7.4. Simulated Data ... *123*
9.8. NOTES ... 123
9.8.1. Sensors ... *124*
10 THE POPUP CONTEXT MENU ... 125
10.1.1. Fit All ... *125*
10.1.2. Zoom Out ... *125*
10.1.3. Flight ... *125*
10.1.4. Select Level ... *125*
10.1.5. Show All ... *127*
10.1.6. View ... *127*
10.1.7. Select ... *127*
10.1.8. Add ... *127*
10.1.9. Edit ... *127*
10.1.10. Block ... *127*
10.1.11. Delete ... *127*
10.1.12. Move ... *127*
10.1.13. Reverse ... *127*
10.1.14. Action, Data and View Toolbar ... *127*
10.1.15. Reset Display ... *127*
11 PRESETS ... 128
11.1. PRESET VALUES ... 128
11.1.1. Preset Values ... *128*
11.1.2. Sort Order ... *129*
11.2. ACCESSING PRESETS ... 129
11.2.1. Resistance ... *129*
11.2.2. Friction ... *130*
11.2.3. Shock ... *130*
11.2.4. Heat ... *130*
11.2.5. Layer Prim, Layer Sec, Air Type ... *130*
11.2.6. Fans ... *130*
11.2.7. Airways ... *130*
11.2.8. Profiles ... *130*
11.2.9. Wetness Fraction ... *131*
11.2.10. Sensors ... *131*
11.2.11. Combustion ... *131*
11.2.12. Leakage ... *132*
11.2.1. Gases ... *132*
12 SETTINGS ... 133
12.1. COSTING ... 133
12.2. GENERAL ... 136
12.2.1. Airway Defaults ... *136*
12.2.2. File Settings ... *137*
12.2.3. License Settings ... *137*
12.3. GRAPHICS SETTINGS ... 138
12.3.1. Background ... *138*
12.3.2. Colours ... *139*
12.3.3. Controls ... *140*

12.3.4. Coordinates ... *140*
12.3.5. Icons ... *141*
12.3.6. Rendering ... *142*
12.3.7. Size ... *142*
12.3.8. Text ... *143*
12.4. SIMULATION ... 144
12.4.1. Airflow ... *144*
12.4.2. Contaminants ... *147*
12.4.1. Dynamic Simulation ... *148*
12.4.1. Simulation Environment [ADVANCED] ... *149*
12.4.2. Examples of Rock Properties ... *152*
12.4.3. Explosive ... *153*
12.4.4. Fire [PREMIUM] ... *153*
12.4.5. Gas ... *155*
12.4.6. Heat [ADVANCED] ... *155*
12.4.7. Recirculation ... *158*
12.5. VENTSIM SYSTEM SETTINGS ... 159
13 HEAT ASSISTANT ... 160
13.1.1. Airflow # 1 ... *160*
13.1.2. Airflow # 2 ... *161*
13.1.3. Diesel Engine ... *161*
13.1.4. Diesel Fuel ... *162*
13.1.5. Electric ... *163*
13.1.6. Water Flow ... *163*
14 FANS ... 165
14.1. FAN DATABASE ... 165
14.1.1. Entering Data ... *167*
14.2. FAN PRESSURE TYPES ... 167
14.2.1. Simulation Handling of Exit Velocity Pressure Losses ... *167*
14.3. FAN DATABASE MENU ITEMS ... 170
15 BUILDING A VENTILATION MODEL ... 171
15.1. OVERVIEW ... 171
15.2. TYPES OF MODELS ... 171
15.2.1. Model Types ... *171*
15.3. INITIAL MODEL CONSTRUCTION ... 173
15.3.1. Manual Scaled Construction ... *173*
15.3.2. Manual Schematic Construction ... *174*
15.3.3. Spreadsheet Text Import ... *174*
15.3.4. DXF Graphics Import ... *174*
15.3.5. Correcting Errors ... *176*
15.4. CREATING PRESSURE FOR FLOW ... 178
15.4.1. Fans ... *178*
15.4.2. Fixed Airflow ... *178*
15.4.3. Fixed Pressure ... *179*
15.5. SIMULATING AIRFLOW IN A MODEL ... 179
15.5.1. Ventilation Pathways ... *179*
15.5.2. Ventilation Ducting and Blind Headings ... *181*
15.5.3. Interconnecting Mine Airways ... *181*
15.6. UTILIZING LAYERS ... 181
15.6.1. Primary Layers ... *182*
15.6.2. Secondary Layers ... *182*
15.6.3. Using Layers ... *182*
15.7. SUMMARY ... 183
16 AUXILLIARY VENTILATION AND DUCTS ... 184
16.1. INTRODUCTION ... 184

16.2. Applying Ventilation to Ducts 186
17 CONTAMINANT SIMULATION (STEADY STATE) 189
17.1. Introduction 189
17.2. Contaminant Steady State 189
17.3. DPM 190
17.4. Gas 190
17.5. Reverse Contaminant 191
17.6. Find Source 191
17.7. Fire Simulation? 192
18 DYNAMIC SIMULATION (ADVANCED) 193
18.1. View Dynamic Simulation Results 193
18.2. Contaminant Dynamic 194
18.3. Fixed / Linear / Logarithmic Release 195
18.4. Dynamic Explosive Contamination 195
18.5. Dynamic Gas Simulation 198
18.6. Dynamic DPM Simulation 198
18.7. Dynamic HEAT Simulation 198
19 MULTI GAS SIMULATION (ADVANCED) 200
19.1. Introduction 200
19.1.1. Inline Concentration Method 200
19.1.2. Injection Method 201
19.1.3. Linear Emission Method 201
19.2. Simulating Gas Sources 202
19.2.1. Placing Gas Sources 202
19.2.2. Simulating Results 202
19.3. Density Based Simulation of Gas 203
20 THERMODYNAMIC SIMULATION (ADVANCED) 205
20.1. Introduction 205
20.1.1. Sources of Heat 205
20.1.2. Source of Moisture 206
20.2. Application of Heat 207
20.2.1. Model Environmental Settings 207
20.2.2. User Inputs 207
20.2.3. Sensible Heat 207
20.2.4. Diesel Heat 207
20.2.5. Latent Heat 207
20.2.6. Oxidisation 207
20.2.7. Fan and Fixed Flow Heat 208
20.3. Injection of Moisture 208
20.3.1. Dust Suppression 208
20.3.2. Evaporative Cooling 208
20.3.3. Wet Material / Dam / Flooded airways 209
20.4. Application of Refrigeration 209
20.4.1. Placement of Refrigeration Sources 210
20.4.2. What portion of the air is cooled? 210
21 DIESEL PARTICULATE SIMULATION (DPM) 213
21.1. Application of DPM Simulation 213
21.2. How to perform DPM Simulation in Ventsim 214
21.2.1. Example 214
22 STAGING – (ALL VERSIONS) 217
22.1. What is Staging? 217
22.1.1. Example 1 – Multiple Stage Time Line 218
22.1.2. Example 2 – Multiple Options 218
22.1.3. Example 3 – Totally different models 218
22.2. Using Stages 219

22.2.1. Setting up Stage Names ... *219*
22.2.2. Selecting Stages ... *220*
22.2.3. Assigning airways to different stages. ... *220*
22.3. CREATING A UNIQUE VERSION OF AN AIRWAY FOR A STAGE ... 221
22.4. SUGGESTED TIPS FOR DEVELOPING STAGED MODELS ... 222
22.4.1. Independent Models ... *222*
22.4.2. Shared Models ... *222*
22.4.3. Other Uses for Staging ... *223*
23 VENTFIRE™ –SCENARIO SIMULATION (PREMIUM) ... 224
23.1. WHAT IS VENTFIRE? ... 224
23.1.1. Example 1 ... *224*
23.1.2. Example 2 ... *224*
23.1.3. Example 3 ... *225*
23.2. PREAMBLE ON FIRE SIMULATION ... 225
23.3. HOW IT WORKS ... 226
23.4. USE THE VENTFIRE™ FUNCTION. ... 226
23.4.1. Adding Events ... *226*
23.4.2. Adding Monitors ... *228*
23.5. ESTABLISHING SIMULATION PARAMETERS ... 228
23.5.1. Dynamic Simulation Settings ... *228*
23.5.1. Resistance ... *229*
23.5.2. Gases ... *229*
23.5.3. Fuels ... *229*
23.5.4. Preset Combustible Fuels ... *230*
23.5.1. Heat Sources ... *230*
23.6. SIMULATING EVENTS ... 230
23.6.1. Establish Settings ... *230*
23.6.2. Before Each Simulation ... *231*
23.6.3. Running a VentFIRE FireSim Simulation ... *232*
23.6.4. Multi-Sim Simulation ... *232*
23.6.5. Explosive Pressure Simulation ... *232*
23.6.6. Program limitations during simulation ... *233*
23.7. VIEWING RESULTS ... 233
23.7.1. Instantaneous Results ... *233*
23.7.2. Historical Results from Monitors ... *233*
23.7.3. Storing a static graph image of results ... *234*
23.7.4. Exporting simulation data ... *234*
23.7.1. Smoothing Data ... *234*
23.7.1. Video Recording ... *234*
23.8. INTERPRETING RESULTS ... 235
23.8.1. Overview ... *235*
23.8.2. Airflow reversal ... *235*
23.8.3. Choked and Alternating Airflows ... *236*
23.9. VENTFIRE™ LIMITATIONS ... 236
23.9.1. Fire effect simulation, not fire chemistry simulation ... *236*
23.9.2. Rollback ... *236*
23.9.3. Choking Limitations ... *236*
24 LIVEVIEW™ (PREMIUM) ... 238
24.1. OVERVIEW OF LIVEVIEW™ ... 238
24.1.1. How Does Ventsim LiveView use the data? ... *239*
24.2. CREATING LIVEVIEW DATA CONNECTIONS ... 239
24.2.1. Step 1. Connect to a Data source ... *239*
24.2.2. Testing the Data Source ... *242*
24.2.3. Step 4. Mapping the Sensors ... *243*
24.2.4. Testing the Sensor Data Import ... *243*

24.3. MANAGING CONNECTIONS 244
24.4. LIVEVIEW SETTINGS 245
24.4.1. Set Sensor Simulation Options 245
24.4.2. IMPORT and MODIFY SENSORS 245
24.5. DISPLAYING THE SENSOR DATA 248
24.6. COPYING LIVEVIEW CONNECTIONS TO ANOTHER MODEL FILE 249
25 RADON SIMULATION (PREMIUM) 250
25.1. INTRODUCTION 250
25.1.1. Radon Concentration 250
25.1.2. Radon Progeny 250
25.1.3. Threshold Exposure Limits 251
25.2. USING THE RADON SIMULATION FEATURE 251
25.2.1. Radon Emanation 251
25.2.2. Radon and Progeny Fixed Settings 251
25.2.3. Activating Radon 251
25.2.4. Simulating Radon 252
26 FINANCIAL OPTIMISATION (ADVANCED) 253
26.1. FINANCIAL SIMULATION 253
26.1.1. Graph Select Financial Optimiser 254
26.1.2. Quick Select Financial Optimisation 257
26.1.3. Financial Simulation Global 257
26.1.4. [ADVANCED] 257
26.2. COST DATA FUNCTION 257
26.2.1. Example 258
26.3. VENTILATION ON DEMAND 259
26.4. FAN OPTIMISATION 259
27 TUTORIAL - MODEL EXAMPLES 261
27.1. EXAMPLE 1 261
27.1.1. Suggested Steps 261
27.2. EXAMPLE 2 269
27.2.1. Suggested Steps 269
27.3. EXAMPLE 3 – IMPORT A COMPLEX MINE DESIGN 273
28 APPENDIX A – GLOSSARY OF TERMS 277
28.1. A GLOSSARY OF COMMONLY USED TERMS 277
28.1.1. Airway 277
28.1.2. Branch 277
28.1.3. TXT 277
28.1.4. DXF 277
28.1.5. Endpoint / Start point 277
28.1.6. Friction cost 277
28.1.7. Friction factor or k factor 277
28.1.8. Friction loss 277
28.1.9. Friction power 277
28.1.10. Hardy- Cross Method 277
28.1.11. Junction 277
28.1.12. Load (Pressure) 277
28.1.13. Network 278
28.1.14. Node 278
28.1.15. Pan 278
28.1.16. Pressure loss 278
28.1.17. Resistance 278
28.1.18. Shock loss 278
28.1.19. Thermal Diffusivity 278
28.1.20. Thermal Conductivity 278
28.1.21. Wetness Fraction 278

28.1.22. Relative Humidity *278*
28.1.23. Density *278*
29 APPENDIX B – SUMMARY OF DATA TYPES **279**
29.1. SUMMARY OF THE MAJOR DATA TYPES 279
29.1.1. Air types *279*
29.1.2. Airflow *279*
29.1.3. Pressure *279*
29.1.4. Airway Attributes *280*
29.1.5. Energy, Power Cost *281*
29.1.6. Thermo -dynamics *281*
29.1.7. Descriptors *283*
29.1.8. Contaminants *283*
29.1.9. Rock Properties *284*
29.1.10. Measured *284*
29.1.11. Gas *284*
30 APPENDIX C – ICON PICTURE GUIDE **286**
30.1. AIRWAY ICONS 286
30.2. CUSTOMIZED ICONS. 286
30.2.1. Fans *287*
30.2.2. Blocked Airway *287*
30.2.3. Airway Resistance *287*
30.2.4. Fixed Airway *287*
30.2.5. Fixed Pressure *288*
30.2.6. Contaminant Report *288*
30.2.7. Fresh Air Report *288*
30.2.8. Contaminant *288*
30.2.9. Gas *289*
30.2.10. Thermo- dynamic Heat or Moisture Source *289*
30.2.11. Thermo- dynamic Cooling or Drying Source *289*
30.2.12. Airway Notes *289*
30.2.13. Surface Connected Airway *289*
30.2.14. Unknown Airway End *290*
30.2.15. Orifice *290*
30.2.16. Backfill *290*
30.2.17. Obstruction *290*
30.2.18. Sensor *290*
30.2.1. Shock Loss *291*
31 APPENDIX D – DISPLAY PROBLEMS **292**
31.1. HARDWARE PROBLEMS 292
31.1.1. Screen fails to display after coming out of 'sleep / hybernation' *292*
31.1.2. Anti-aliasing does not work / is very slow *292*
31.1.3. Custom Icons cannot be used *292*
31.2. SOFTWARE PROBLEMS 294
31.2.1. No Graphics Shown on Screen *294*
31.2.2. I can see airways, but no text / arrows / nodes *294*
32 APPENDIX E – SIMULATION ERRORS **295**
32.1. WARNINGS 295
32.1.1. no entry airway or surface connection *295*
32.1.2. no exit airway or surface connection *295*
32.1.3. no entry or exit *295*
32.1.4. airway stopping redundant *295*
32.1.5. fan interfering with another fan *295*
32.1.6. Fix requires pressure *296*
32.1.7. temperature balancing issue *296*
32.1.8. stalled fan *296*

32.1.9. low pressure fan 296
32.1.10. negated fan 296
32.1.1. Water suspension velocity 296
32.2. ERRORS 296
32.2.1. airway attempted to reverse 296
32.2.2. Anomalous pressures 297
32.2.3. Duplicate airway 297
32.2.4. Fixed flow cannot be achieved 297
32.2.5. Fix being over-restricted 297
32.2.6. operating fan blocked 297
32.2.7. convergence problem 297
32.2.8. temperature outside allowable range 297
32.2.9. heat estimation error encountered 298
32.2.10. temp estimation near rock surface 298
32.2.11. overpressure across resistance 298
32.2.12. operating fan restricted by resistance 298
32.2.13. fix being over restricted 298
32.2.14. unresolved pressure or flow 298
32.2.15. fan static P curve invalid, check fan 298
32.2.16. fan total P curve invalid, check fan 299
32.2.1. Meshing error 299
33 APPENDIX F – SHORTCUT KEYS 300
34 APPENDIX TABLE OF FIGURES 301

Chapter

1

1 Ventsim Visual™ – Version 3 – What's new?

Ventsim Visual™ 3 marks a significant change to previous versions of Ventsim Visual.

Ventsim Version 3.0 introduces a multi window interface allowing users to simultaneously show different parts of the ventilation model in different windows. This required a significant re-write of the software, not only for the graphics engine which was now required to handle significantly increased levels of graphical complexity, but also for the user interface which needed redesigning to help the user manage the additional windows and settings.

To enable users to display different types of data and colour in each window, it is necessary for additional controls and toolbar buttons to be available in each window (for example, drop down lists to allow selection of colours and text). To ensure users can control the complexity of the controls on the screen, additional functionality was added to enable toolbars to be hidden or moved.

In addition, some of the most commonly used menu items such as edit 'locking' and airway interceptions, camera snapshots, perspective views, and the 'show all' function have been moved to the main toolbar.

However, Ventsim Visual™ 3.0 is much more than a graphical upgrade. The software contains a host of new features to enable ventilation models to be developed with more detail and sophistication than ever before.

The new staging feature allows models to include many variations and changes, all within a single file. A complete life of mine ventilation model is now possible, showing all different stages of ventilation design. In addition, models can contain multiple options within the same file.

Dynamic simulation routines have also been re-written, allowing users to simulate the time based effects of ventilation changes. Using a new 'multi-cellular' simulation approach, dynamic simulation is now performed in more detail, speed and accuracy than ever before, and for the first time, ALL simulation methods (Airflow, contaminants, DPM fumes, gases and heat) are now available in the dynamic function.

Finally, a new highly specialised simulation engine called VentFIRE™ has been included as an optional extra for users who require programmable events driven dynamic simulation tool, which includes fire combustion heat and gases. This exciting addition allows users to simulate all types of heat and gases, and programmatically makes changes to ventilation systems over time. Complete emergency scenarios coupled (as the module name suggests) with large fires can now be simulated complete with heat and gas predictions, and changes to the ventilation circuit such as doors opening or closing, or fans turning on or off can be made to examine the effectiveness of various emergency response strategies.

Welcome – To Ventsim Visual™ Version 3!

Chapter

2

2 Ventsim Visual™ – An Introduction

Ventsim Visual™ is the successor to Ventsim Classic which was first developed and released in 1993, and was widely lauded for its simple interface and graphical Windows based 3D wireframe approach to displaying ventilation models.

The relatively recent introduction of affordable 3D graphics hardware into everyday PC's encouraged a new approach with Ventsim ventilation software.

It became clear soon after the introduction of Ventsim Classic that very sophisticated and complex models were being developed with the program, however the application and analysing of these models was restricted by the shear amount of data being manipulated. In addition, in models of many thousands of airway branches, serious mistakes could often be made in the entry of data without being noticed. Viewing and editing of large datasets was becoming increasingly problematic, and use of these models by others not familiar with the mine was becoming more difficult.



A key factor in the development of Ventsim Visual™ was the observation that many sophisticated ventilation models were being developed in Ventsim Classic by bright engineers, but then simply gathered dust once these engineers moved on, and new engineers abandoned trying to decipher them.

Another key factor to the development of the next generation of Ventsim was the increasing demand to simulate and design underground environmental conditions, to ensure suitable conditions for mine workers and equipment.

As a result, Ventsim Visual™ Standard and Advanced were developed to address these requirements. Primarily, it has been designed as a ventilation tool, which can operated independently of other mine planning packages, but maintains a level a compatibility which ensures data from mine planning packages and other ventilation software can be passed to the program.

Ventsim Visual™ provides a full toolbox of tightly integrated utilities to analyse ventilation flows, heat, contaminants and financial aspects of mine ventilation. Building on the success and experience of fifteen years of Ventsim implementation at over 800 sites, Ventsim Visual™ goes a generation further in its approach to ventilation simulation and analysis, and sets a new standard in ventilation software design and implementation.

2.1. About Ventsim Visual™

Ventilation has been a primary concern in underground mines for hundreds of years, but until the introduction of computerized model analysis in the last 40 years, the planning and modelling of ventilation was largely a black art, relying on experience, guesswork and extensive calculations.

Even when computer ventilation software allowed simulations of large models of underground airways, the process of entering and interpreting results still remained a job for experts in the field. Ventsim Visual™ aims to make ventilation simulation and design accessible to any mine engineer or ventilation officer, even those without substantial ventilation experience.

Ventsim Visual™ Standard provides the user with the tools to;

- Simulate and provide a record of flows and pressures in an existing mine.
- Perform 'what if' simulations for planned new development.
- Help in short term and long term planning of ventilation requirements.
- Assist in selection of types of circuit fans for mine ventilation.
- Assist in financial analysis of ventilation options.
- Simulate paths and concentrations of smoke, dust, or gas for planning or emergency situations

Ventsim Visual™ Advanced provides additional tools to;

- Undertake full thermodynamic analysis of heat, humidity and refrigeration in underground mines.
- Take into account air compressibility for deeper mines.
- Provide tools for analysing multiple different airways size options, both financially and for establishing ventilation capacity.
- Show dynamic time based analysis of contaminant, gas, diesel fume or heat spreading through a mine from different activities.
- Provide a tool to check for recirculation in mines.
- Simulate Diesel Particulate Matter (DPM) concentrations through a mine.

Ventsim Visual™ Premium provides additional tools to;

- Dynamically and simultaneously simulate multiple ventilation parameters (contaminant, gas, diesel fume, heat and airflow), including the simulation of fire heat and fumes. Models can be programmed to self-modify during simulation. This tool is called VentFIRE.
- Connect and load external data (from mine sensors for example) to display realtime data within a Ventsim model. This tool is called LiveView.
- Ventlog : A separate software program to record and store measured ventilation data from underground areas. Ventsim Visual™ can link to this data and show it within a 3D model. This tool is called Ventlog.

Ventsim Visual™ has been written to make the process of ventilation model analysis as easy to use as possible. Both versions utilise sophisticated 3D graphics, driven by a fully graphical mouse driven interface. Ventsim Visual™ is compatible with Microsoft Windows XP, VISTA, WINDOWS 7 and WINDOWS 8. The software can also be run on Apple Mac Computers with suitable graphics hardware, running Microsoft Windows under dual boot or emulation.

Ventsim Visual™ automatically installs as a 32 bit or 64 bit version. The 64 bit version has the ability to utilise additional computer memory, and therefore much larger models can be used. Recommend maximum model sizes are 30,000 airways for the 32 bit version, and up to 100,000 airways for 64 bit versions. Increased amounts of DXF reference data can also to set to be displayed in the 64 bit version.

2.2. Computer Hardware Requirements

Ventsim relies heavily on 3D graphics hardware to present detailed smooth graphics. While most computers these days have this functionality built in, older computer may not and may struggle to produce acceptable performance.

Even modern computers, particularly laptops may have substandard graphics hardware for displaying 3D graphics and performance may not be as good as expected. The following guide is recommended for computers



Minimum Configuration

- Intel based (AMD or Intel) processor 1 Ghz +
- Windows XP, Vista or Windows 7 / 8
- Memory 2G or RAM, Hard Drive Space 100 Mb
- Direct X9 compatible graphics (minimum Intel integrated graphics)
- Two button mouse
-

Recommended Configuration

- Intel based 32 or 64 bit dual core processor 2 Ghz +
- Windows XP, Vista or Windows 7 32 or 64 bit
- Memory 4G of Ram. Hard Drive Space 100Mb +
- Dedicated /Discrete Graphics card from INTEL, ATI or NVIDIA with greater than 128Mb or RAM. INTEL 'COREi'' processors (generally sold from 2010 onwards) now have reasonable graphical power and perform well with Ventsim without a dedicated graphics card.
- Two button mouse with centre scroll / click wheel

- Ventsim Visual™ is not officially supported on Apple Mac computers, however it has been confirmed that Ventsim Visual™ is capable of running on newer Macbooks under Windows dual boot or Parallels™ virtualisation software.

-

Ideal Configuration

- Windows 7 64 bit. 4Gb or more RAM, Dedicated 1GB+ NVIDIA or ATI graphics card.

Chapter

3

3 VENTSIM CLASSIC™ TO VISUAL GUIDE



Ventsim Classic™ was released in 1994 and enjoyed many years as a simple but popular ventilation software program to simulate airflows and pressures in mine. Despite limitations such as incompressible flows and lack of heat simulation, many hundreds of mines adopted Ventsim Classic for use. Ventsim Classic™ was improved to version 3.9, however all development on this program was stopped in 2007, after which time Ventsim Visual™ was developed.

Ventsim Visual™ was completely rewritten from the ground up. It is a substantially different program than Ventsim Classic 3.9 and takes a new approach to ventilation display and simulation. This section will give you a brief overview of the major changes if you are familiar with Ventsim Classic 3.9, and may also assist if you are familiar with other ventilation software packages. In most cases, Ventsim Classic™ models can be imported directly into Ventsim Visual™.

Every graphical aspect of the program has a necessary function to help make ventilation models easier to understand and reduce the opportunity for error. The 3D graphics accurately represent the true size, shape and location of underground airways. The colouring represents many different types of data (for example temperature or pressure). The animated arrows show both the speed and direction of airflow. By removing or reducing the need to comb through excessive amount of textual data, ventilation models can be analysed and validated much faster than traditional means.

3.1. Display

Ventsim Visual™ default uses a 3D perspective view.

Three dimensional (3D) perspective views are rarely used in CAD or Mine Planning packages, except occasionally for final presentation purposes. The perspective view tends to distort distances and true directions and is therefore largely unsuitable for detailed engineering drawing. An orthogonal non-perspective view however is not required for ventilation modelling, which relies more on effective data presentation.

The Ventsim Visual™ Approach:

To create a user friendly, graphically rich program and interface, which shows the maximum amount of relevant data, in the most efficient and understandable way.

A 3D perspective view is the way we look at the world and when used to view computer models, it is natural and easily understood, particularly to someone unfamiliar with your model.

Airway solids shown with true dimensions and shapes allow quick appraisal to check whether dimensions are as intended. The author has found numerous examples of Ventsim Classic 3.9 models loaded in Ventsim Visual™ that immediately show inadvertent incorrectly sized or shaped airways which may prevent the model from simulating or balancing as expected.

A perspective view also permits closer visualisation of specific parts of a model, while other parts are hidden or obscured by distance. In cluttered large models this can help clarify intended data significantly.

3.2. Animation

They say a picture is worth a thousand words. Animation may therefore be worth a thousand pictures. Ventsim Visual™ animation again demonstrates a key feature of the software's presentation of complex data. By animating flow arrows, fans and heating/cooling sources, Ventsim Visual™ can show a huge amount of data in a way that the human brain can quickly visualise and interpret. Animated flows show the direction and relative speed of all airflows in a mine over potentially thousands of airways. Animated fans show whether they are turned on or off, while dynamic colouring draws the user's attention to specific data ranges. Using only animation and colouring of data, Ventsim Visual™ users can process and analyse complex models, without having to interpret a single line of textual data. In addition, it makes presentation of data very effective to the layperson (who often control budgets and have to make decisions regarding investing in costly ventilation infrastructure)

3.3. Elevation Database (Levels)

There no longer needs to be a defined surface level elevation. Any airway can be connected to the surface at any place in the mine, by clicking on Connect to Surface in the airway Edit Box. Ventsim Visual™ will calculate which end is connected to the surface, based on the free end available.

A level database, although still useful, is no longer mandatory for viewing different elevations of a model. While an overarching single elevation level covering all elevation ranges is still recommended, *any* elevation range can be viewed at *any* time by ***Right Clicking*** the screen, choosing Select Level from the context menu, and then clicking or fencing the area you wish to view. In addition the select level function can be used to quickly limit an elevation range, or multiple ranges, by drawing a box around the intended airways.

3.4. Airways

Airways no longer need to be connected to another and can be left open ended, as would be the case in blind development headings. Because this may still cause unintentional problems (such as airways not joined as the user intends), Ventsim Visual™ will alert the user to these during simulation.

These warnings can be turned OFF in the settings menu, or disabled individually by clicking "Closed End" in the edit box. No airflow will travel through closed ended airways, unless connected to surface.

No Entry / No Exit errors are largely abolished with Ventsim Visual™. Providing the airways are connected to a part of a model where a pressure can be derived, Ventsim Visual™ will automatically reverse and adjust airways into a node.

3.5. Data

The single biggest change to Ventsim Visual™ is the visual management of data types. Around ninety (90) different data types exist in the ***Advanced*** version, all of which may be displayed as text on the screen, in a spreadsheet or as a colour range.

3.5.1. Colour and Data Manager

This creates a rich, but potentially confusing interface. To simplify things, Ventsim Visual™ uses both a Display Manager Control form to assist in rapid analysing and changing of on screen data and colour. This control can be utilised via the view menu, or from the toolbar.

It is important to note that colours can be displayed independently of the text data which is shown on screen (for example pressures can be showed at a colour range, while text data could show air flows. Colour ranges can be adjusted ***in*** the Display Manager with the slider bars, or by manually entering new ranges.

3.6. Coordinates

Ventsim has switched to a more conventional Eastern / Northing / Elevation coordinate approach. The relative directions on screen of these coordinates can be changed in the Settings menu.

Ventsim Visual™ allows decimal point coordinates to be used allowing more accurate placement of airways. While this will have little effect on ventilation flows, it removes the 'saw tooth' effect often seen in the Ventsim Classic 3.9 integer coordinate display

3.7. Editing and Information

3.7.1. The Edit Box

The Edit Box now acts as a powerful editing and information tool for airways in a model. The Edit Box may be left open permanently, and will update with information from the airway clicked on during viewing, editing and adding modes. It will also automatically update after simulation, with the latest airway results.

3.7.2. The Information Tab

To view airway information for example, leave the Edit Box selected on the Information Tab, and airways throughout a model can be quickly analysed by clicking on the airway. Likewise, the Fan Tab could be left open, and operating fan curves can be analysed quickly at different point in the model in the same way.

3.7.3. Modifying Data

To modify data in an airway, simply click on the cell you wish to modify and change the data. The airway will automatically update when Apply or OK is pressed, or when another airway is selected. Multiple airways can be selected for simultaneous editing by fencing or selecting the airways while in Edit Mode, and then clicking on any selected airway. Any data within the Edit Box changed during editing multiple airways will be changed for all the selected airways.

For example, if all selected airways require a width of 6m, then after changing and applying the Width in the Edit Box, the width (and only the width) of the selected airways would change. All other attributes (even if different between the selected airways) remain unchanged. Data that will be changed turns **blue** after modification.

To abandon these changes, select ***Cancel*** from the Edit Box before moving to another airway.

3.8. Referenced Graphics

Ventsim Visual™ permits the use of referencing external 3D graphics into the program, such as wireframes, surface terrains, orebodies, actual development and mine infrastructure.

While referenced graphics do not interact directly with ventilation circuits, they provide a useful visual and construction aid to developing and presenting models. Mine ventilation model airways and sizes can be directly compared to actual or design development, surface terrains can be used to ensure shafts are set to the correct elevation, while orebodies and stope wireframes can be used to ensure ventilation circuits are not developed in the wrong area, and have adequate ventilation designs to control airflow.

3.9. Experiment!

Finally, by all means experiment with the program. Load up and view some of the included demos. Most features have a *Tool Tip* attached to them, which will provide further information if the mouse cursor is hovered near them. Ensure you save your model files frequently and create backups where necessary.



Craig Stewart
Author Ventsim Visual™
© 2013 Ventsim Software

Chapter 4

4 THE VIEW WINDOW

Ventsim Visual™ operates in a full three dimensional (3D) graphical environment. The main Ventsim Visual™ window contains all the functions you will require to *create*, *edit*, *view* and *simulate* airway models. Note that some of these functions may differ between ***Premium***, ***Advanced***, ***Standard*** versions.



Figure 4-1 Ventsim Visual™ Main Window

1 **Main Menu.** Consists of options required to load, save, view and manipulate the model, as well as options to change settings and simulate ventilation models.

2 **Action Toolbar.** Consists of many of the construction tools required to build ventilation models. In addition it contains a number of buttons for different types of ventilation simulations, as well as options to save or load new model, change stages and alter animation speeds for arrows. This toolbar can be hidden, but not moved to other locations.

3 **Data Toolbar.** Allows the text or colours of airways to be changed. Displays or hides the colour legend control. This toolbar can be hidden or moved to the upper or lower part of the screen.

4 **View Toolbar.** Contains options to show or hide various graphics items such as arrows, text, nodes and reference (DXF) graphics. This toolbar can be hidden or moved to the left or right of the screen.

5 **Display Manager.** Contains controls to alter the colour or transparency of airways on the screen. In addition it can also change the display to show different layers, levels (elevations) or air types on display.

6 **Data Position Control**: Selects the position along an airway from which data will be displayed as text on screen or as colours. The condition of air will change along an airway (particularly long or deep airway segments), therefore this option is available to select which position along an airway segment display data is sourced from. The first and last button displays the conditions of air entering and exiting an airway segment. The middle button displays an average of airway data through the segment. The middle left and right button displays the airflow conditions entering and exiting any icon (for example a fan) within the airway. If an icon is not present, then the middle conditions of an airway segment are displayed.

7 **Mouse cursor position** coordinates in the 3D screen.

8 **Simulation status.** Green = successful simulation, Yellow = successful simulation with warnings, Red = unsuccessful simulation.

9 **Main 3D view** display window. Up to seven (7) separate windows can be opened in Ventsim. The first four (4) windows can be docked within the main windows structure, while the remaining are 'undocked' or free floating.

The success on how to utilise some of the unique aspects of a 3D perspective view comes from an understanding of how it works. Ventsim Visual™ has a number of guides to assist in viewing and construction in 3D.

4.1. Point of Focus

The view in the main 3D Ventsim window is essentially a view seen from a 'camera' floating in space, aimed at a *point of focus*. Your eye is the camera. The point of focus is always in the centre of the screen, at a pre-determined distance away from the camera.

4.1.1. Moving the point of focus.

You can move closer or further away from the point of focus with the *Mouse Scroll* button, and rotate around this point of focus with the *Mouse Right* button. To move the screen to a different location, the point of focus needs to be moved.

There are several ways to move the point of focus;

- Draw a window with the mouse around the area you wish to focus on. The focus will move to the centre of the window, at the closest distance of an object or airway in the window.

- Drag (pan) the screen with the ***Centre*** mouse button. The point of focus will move along the current horizontal plane with the mouse cursor

- Click on an airway while in the view mode, or when in any other mode with the ***Mouse Middle*** button (or a ***Right/Left*** combination for those without a 3 button mouse). This will automatically put the focus onto the clicked airway *at the same viewing distance as was previously set.* If the object being clicked is a long way away, this has the effect of quickly flying through space towards that object in order to maintain the same view distance as the previous point of focus.

- The ***Elevation*** of the point of focus can also be changed by selecting the ***Shift*** key while using the ***Mouse Scroll*** button. A ***transparent grid*** (if the grid is turned on) will show the horizontal plane of the point of focus.

4.2. Multiple Windows

Ventsim 3.0 can display multiple graphics windows (up to 7), each with its own independent view of the ventilation model. Every window is fully 3D and is customisable in terms of data display including colours, levels, layers, text and graphical items shown.

- 

4.2.1. Docked Windows

By default, Ventsim will tile the first four (4) windows within the main Ventsim window. The direction of tiling can be changed in the Window Menu bar in Ventsim. These windows are called 'Docked' windows because they are constrained and sized by the main Ventsim window. Additional windows created after the first four will be 'undocked' and can be independently sized and located around the computer screen(s).

4.2.2. Undocked Windows

A docked window can be 'undocked' simply by dragging the window outside of the main Ventsim window. An undocked window can be 're-docked' by dragging the windows back inside of the main Ventsim window (providing there are less than four windows present) To disable the automatic docking behaviour, deselect the Auto-Arrange function from the Window Menu Bar.

4.2.3. The Active Window

Shared Ventsim functions (such as the Camera button or keyboard button inputs) are always directed to the currently active window. The Active Windows is the most previous window

clicked or interacted with the mouse.

4.2.4. Drawing between windows.

It is possible to construct an airway between windows. While in the DRAW mode, simply start drawing in one window (click at least one leg of the airway in the initial screen), then drag the mouse to the new window and location.

4.3. User Control Summary

Middle Mouse Button Wheel

Scroll
Zoom in / out of model

Scroll + Shift
Move Edit Plane Elevation up or down

Hold & Drag
Pan or move model about

Click
Centre model at mouse cursor

Note the combined LEFT /RIGHT mouse button can be used to simulate middle button

Right Mouse Button

Hold & Drag Up Down
Tilt Model

Hold & Drag Left / Right
Spin / Rotate Model

Click
Show Popup Menu



Left Mouse Button

View Mode

Click
Centre model at mouse cursor

Double Click
Edit airway at mouse cursor

Hold and Drag
Fence view and zoom into fenced area

Other Modes

Hold and Drag
Fence Select airways inside

Click
Activate Function

KEYBOARD COMMANDS

<ESC> :	Exit Function
<ESC> x 2:	Exit Function and return to View Mode
<SHIFT>	Move cursor in 3D vertical direction
<BSPACE>	Undo last action
<TAB>	Redo last action
<F2>	Plan / Section View Toggle
<F3>	Find airway
Others	See manual Appendix E for other commands

4.4. The Edit Plane

The ***Edit Plane*** is a horizontal plane at a set elevation. By default, any new airways are initially constructed on the edit plane. The edit plane can be viewed by ensuring the grid function is turned on. The plane will be crossed with grid coordinate lines. If ***Shift*** is selected the edit plane will be made semi-transparent which will indicate where it intersects existing airways.



Figure 4-2 The Edit Plane, shown with the SHIFT key pressed

To move an edit plane, select a new point of focus by centering on an airway, or use the ***Shift-Mouse-Scroll*** combination to move the edit plane elevation. The coordinates in the status bar at the ***Bottom Left*** corner will always show the elevation of the edit plane.

Hint : The Edit Plane will also temporarily move automatically to the level of an airway being drawn from another airway. Additionally, the edit plane and point of focus can be moved manually by the Set Edit Plane function in the View menu.



Figure 4-3 True Vertical Line showing top and bottom airways lining up



Figure 4-4 True Vertical Guide Line helps guide a shaft vertically into the airway below

4.5. Drawing in the Third Dimension

Drawing in three dimensions can be a challenge as the view is being displayed on a two dimensional screen monitor. Ventsim Visual™ alleviates this problem by only drawing on the horizontal plane except when the ***shift key*** is pressed, or the screen is orientated to a vertical cross section orientation.

4.5.1. The True Vertical Guide

3D perspective views do not necessarily show a vertical object as pointing straight up. As objects move further left and right of the point of focus, they 'lean' over away from the centre of the view. To assist the user as to which direction is truly up while creating or editing airways, a ***true vertical line*** is displayed while drawing, moving or copying. If the object being drawn aligns with the ***true vertical line***, then it is vertical. The true vertical line can also assist in locating airways directly under or over other airways at different elevations by observing where the line 'intersects' airways above and below the current point being edited.

4.5.2. Drawing Airways

To simplify construction of airways, initially all drawing, moving and copying of airways defaults to the horizontal ***Edit Plane***, regardless of the orientation of the view screen. To assist the user further, airways being drawn or moved will automatically 'click' and join to airways under the mouse cursor, even if at different elevations or distances away.

Hint: To quickly change the view from horizontal plan view to vertical section view, press the F2 button

If airways are drawn in isolation (not connected to other airways), they will use the default airway settings specified in the Settings form. If airways are drawn connected from another airway, they will ***inherit*** the settings from the airway from which they are drawn. Airways can be drawn from another airway end (node) or from any other point along an airway. Ventsim Visual™ will create a new node (or junction) if none already exists.

Hint: Ventsim Visual™ can detect whether an airway being constructed crosses the paths of other airways. For example, if a long airway is drawn from one point to another, over which it crosses the paths of existing airways, Ventsim Visual™ will join this airway into the crossed airways with new nodes. This will only

happen in the drawing mode. If airways are imported (from a DXF for example), crossed airway junctions will not automatically be detected).

To draw in the third dimension (up or down in elevation) where there is not an airway above or below to click to, first draw the airway to the desired horizontal (plan) location, then press the ***Shift key***. The ***Edit Plane*** will turn semi-transparent, and further movements of the mouse will occur in a ***Vertical plane*** parallel to the computer screen. The ***Edit Plane*** will follow the vertical movement, assisting in showing where the cursor is in relation to other airway elevations. In addition, the numbers in the lower left status bar will show the elevation and coordinates of the point.



Figure 4-5 Picture showing inclined airway being drawn down to the elevation of the level below

4.5.3. Manual Coordinate Entry

Airways can be manually added, moved or copied by selecting a manual coordinate entry system. To activate this system while in draw mode, click on an airway end or somewhere in empty space. To activate this system every time an airway is drawn (to allow manual adjustment or entry of airway ends) select the pull down arrow on the ADD button and choose the 'Coordinates' sub-options from the button.

To activate the system, when **moving** or **copying,** simply click an existing airway end while in the **Move** or **Copy** mode. A coordinate window will show and the coordinates (or offsets) of the airway can be entered.

The coordinate entry allow airways ends to be adjusted manually, or by using a vector polar coordinate or a physical offset of the easting's, northings and elevation. End coordinate values are adjusted in real time as offsets or polar coordinates are adjusted. To apply the change, simply click OK when completed.



Figure 4-6 Coordinate entry system

4.5.4. Moving Airways

Depending on where the airway is clicked with the mouse in *Move* mode, either end, or the entire airway may be moved. If the ends (nodes) of the airway are connected to other airways, they will be stretched to accommodate. An airway can be 'broken' away from a node by selecting it a small distance back from the node, and 'dragging' it away with the mouse. Multiple airways can be copied or moved by *Selecting* the airways (with the *Select* button, or by drawing a *Fence* around the airways while in *Move* or *Copy* mode), and then dragging the selected airways or clicking one with the mouse coordinates.



Examples of Moving Airways

- Upper left : Airways are selected and then moved simultaneously
- Upper right : Airway junction is moved with all attached airways
- Lower left : Airway is 'broken away from node and pulled away with mouse
- Lower right : Airway junction is moved vertically by pressing shift while using mouse.



4.5.1. Moving / Copying Icons

Icon placement is not normally critical, however for fans or heat sources it can have some effect due to changes in air density and pressure along an airway. The simulation will calculate the parameters and effects of an icon as the specific point it is located in the airway. To move an icon within an airway, simply choose the *Move* mode, and select and drag the icon along the airway with the LEFT mouse button. To move or copy an icon to another

airway, simply drag the icon to the new location. Note that an icon can only be copied or moved to an airway with no existing equivalent icon.

> Hint: Icon location can cause significant changes to fan performance on very long airways with elevation changes. For example, a fan place at the top of a 1000m deep shaft will perform very differently to a fan place at the bottom of the shaft due to different density and pressure variations at each location. Ventsim Visual™ Advanced will calculate the variations and simulate the fan at the location at which the icon is placed. Ensure the icon is correctly located along the airway, or use a very short airway segment (for example a short extension at the top of a shaft) to locate the icon where it is required to be simulated.

4.5.1. Copying Airways

Airways can be copied, much in the same way as the *Move* function. An airway can be 'grabbed' with the mouse and 'dropped' in a new location, or the airway can be clicked and manually copied with new coordinates. In addition, a group of airways can be selected with the *Select* button, or by drawing a fence around the airways, and then clicking or dragging one of the selected airways.



Figure 4-7 Example of copying a selected group of airways

Chapter 5

5 THE MENU BAR

The main menu bar accesses a host of functions including simulation options and settings, and viewing options and settings. Many of the main menu bar function are duplicated in the toolbar buttons.



5.1. File Menu

5.1.1. New / Close

Erases the model currently in memory.

An option is given to save any unsaved changes from the current model. The previously used Level, Layer and Fan Database will be retained for the new model. The New option closes the model, and load up the system startup defaults, whereas the Close option closes the model, but retains the previous model settings and defaults.

5.1.2. Open

Loads a pre-saved model.

You can also open Ventsim Visual™ files by dragging file icons from your Windows folders onto the Ventsim Visual™ screen.

Ventsim can open a number of different formats, including Ventsim Visual, Ventsim Classic, and provides limited functionality to load VNET-PC files.

Ventsim Classic files are slightly different in structure. While good compatibility should be retained when loading these files, it is always important to check and validate the model to ensure no significant changes have occurred during the transition from Ventsim Classic to Ventsim Visual.

VnetPC Files Ventsim can directly import VnetPC files and construct a workable Ventilation model from the file, however full compatibility is not guaranteed. Ventsim attempts to import all airway data, fan curves and environment data, however because of some fundamental differences in files formats and data used, there may be difference in simulation.

To maintain maximum compatibility, the resistance of all airways is fixed to the same value as the VnetPC file, however if the file has correct airway dimensions, the user is encouraged to remove this fixed value and utilise the AUTO resistance in Ventsim to calculate airway resistance from size and friction factor. To do this, select the airway or airways, then choose the EDIT button, and change the CUSTOM resistance to AUTO. Ensure the airway size and friction factors are correctly set for each airway.

Warning. Full VnetPC compatibility is not guaranteed and every file should be thoroughly checked for accuracy and consistency after import. VnetPC files are missing much of the information Ventsim normally used to simulate models, and assumptions are sometimes made which may not be correct.

Validating Imported Models

When loading Ventsim Classic or VnetPC models, a simple validation check can be done by comparing the model Summary before and after a simulation. For example, immediately after loading the model, select RUN > SUMMARY from the main menu, record the airflows and other data, then SIMULATE the model and compare the new SUMMARY results. If the results are very similar it is likely that there are no significant compatibility issues.

5.1.3. Merge

Joins two models together instead of erasing the currently loaded model.

Similar to the Open command, this may be useful for joining separate modeled areas of the same mine. Caution should be taken however, as duplicate branches are not immediately checked when the models are merged (duplicate branches will be subsequently be deleted if an attempt is made to simulate the model).

5.1.4. Save

Saves changes made to the ventilation model.

If the Ventsim title bar shows that the model is untitled, the user will be prompted to select a name before the file can be saved.

5.1.5. Save As

Saves the model, but gives the option of saving under a different name.

Ventsim can be saved in one of two formats. The default format in the VSM file which is the standard file format. This format is highly compressed and cannot be read by other programs.

Ventsim Visual™ files can also be saved as a ***Text*** format. This format follows the standard TAB separated values format and can be loaded by programs such as Microsoft EXCEL, WORD or ACCESS. The internal contents of the file can be viewed, modified and resaved as a ***Text*** file. The ***Text*** file can be reloaded into Ventsim Visual™ providing the basic structure and the HEADER and FOOTER tabs remain the same.

5.1.6. Master Link

Enables a common settings file (Master File) to be linked and shared with multiple Ventsim Visual™ files. Master Files replace the Template function used in Version 1 of Ventsim Visual.

Master Files store a user definable selection of shared settings (for example resistance and friction factor preset values or fans). When a Ventsim file is linked to a Master File, and the file is saved, the settings are also saved to the Master File and will be available to all other Ventsim Visual™ files which have a link to the Master File. The settings in linked Ventsim Visual™ files are updated from the Master File when loaded. If the Master File is not available, then a warning will show and the most previously saved settings will the used.



Warning : Using linked Master Files can be dangerous if settings made in one file adversely affect another linked file. For example if a fan is removed or replaced with another fan, and the file saved, then all other linked Ventsim Visual™ files which used to use this fan may no longer work correctly. If a linked Master File is used, it is normally better to add new settings, not remove or delete existing settings which may be used by other files.

Create New : Creates a new Master file template, which can then be linked to other Ventsim Visual™ files. When creating the file, it is automatically linked to the current file. Other

Ventsim Visual™ files can be linked to this same Master File by opening the files and using the Link option below.

Hint : When creating a new file, there is an option to specify what common settings you would like to make in the master file. For example if only the fan database, and the common resistance, friction and shock factors are to be used, then click on the Fan Database, and Preset options in the dialog box.

Save the Master File in an accessible file location. A descriptor can be saved with the file to explain information about what components have been saved.

Figure 5-1 Master File Options

Link : Opens a dialog form to search and link to a Master File. If the current Ventsim file has an existing linked Master file, the new Link will replace the data in the Ventsim file. An alternative method to link a file is to simply drag and drop a Master File into the current Ventsim Visual™ window.

Unlink : Breaks a link to the Master file (but does not change the Master File). Any changes to file settings made after the link is removed will no longer update the Master File.

Update : Refreshes the current Ventsim file with the data in the Master File. This may be necessary if another file has modified the data in the Master File after the Ventsim file has been opened. It is normally not recommended to have multiple files open accessing the same Master File as only the most recently saved Ventsim File will have updated the master settings. If another file has updated the Master File while the current file is open, then a WARNING will display indicating a possible conflict.

CAUTION – When selecting 'REPLACE' many components such as fan databases, levels and most presets may not correctly map to the existing model's fans, levels and presets, particularly if (for example) fans within the database are in a different order. These may need to be manually corrected by checking and re-editing fan airways to ensure the correct fans have been placed.

5.1.7. Defaults

The start up settings for Ventsim Visual.

The defaults file is stored in the user's personal Windows directory. The file is loaded when Ventsim Visual™ starts and specifies the settings, behaviour and fans when the program is first loaded. Each user who logs on to the computer will have a different default file which is initially created when the program is installed.

Ventsim Visual™ files have a copy of defaults stored within the file which may have been modified after the model file was started. This will override the standard start up defaults when the file is loaded.

Reload Startup - Reloads the original defaults file that is first loaded when Ventsim is initiated.

This may be required if the default settings that are automatically loaded with a Ventsim simulation file are incorrect or out of date, or you wish to overwrite the current file settings.

CAUTION – This will reset all file parameters such as fan databases and graphics options. If you wish to only update selected components, use the inherit function to load selected components from an existing file.

Save Defaults - Saves the settings currently loaded in memory to the defaults file. These will be loaded automatically next time the program is run.

Restore Defaults - Restores the defaults file to the original file created when the Ventsim Visual™ program was installed.

5.1.8. Inherit

Adopts selected attributes from another model.

Ventsim Visual™ files contain many different components such as fan databases, file and simulation settings, level and layer database and many other options. Instead of setting up new parameters for a model, these components can be loaded from an existing file without deleting the airway data in the current file.



Hint : Fans from other Ventsim Visual™ files can be used in your existing files by inheriting and 'combining' the fan databases. The simulation file fans inherited will only be added if no existing fans exist with the same name. The 'merge' option will ensure all the current model fans will be preserved, and new fans made available for selection. The fan list can be edited from the fan database, or from the Presets spreadsheet.

Once a suitable file is selected, an option panel is displayed to allow the user to select various components they wish to inherit from the saved file. Once loaded, these components will become part of the existing file. An option is provided to merged with existing presets (for example, the friction factors may be added to a list of currently used friction factors), or they can simply completely replace existing presets.

5.1.9. Icons

Offers tools to assist with applying custom pictures to fans, resistance or heat preset items in Ventsim.



Custom icons allow individual fans, heat sources or resistances to have pictures of (for example) real installations placed over the default icons in the model.

To place a new icon picture in a model, simply 'drag and drop' a picture file from any Windows folder, onto the icon in your Ventsim Visual™ model to be changed. The default icon will automatically change to the new picture.

Other tools that may be of use in managing custom icons include:

Export: Ventsim stores compressed copies of any icon pictures in the model onto a hard drive location that can be accessed from a Windows folder.

View: Shows the Windows folder with currently stored Ventsim Icon Pictures.

Refresh: Updates the Ventsim display with any changed icons in the model. The should normally not be required.

Clear: Removes any icon pictures from the Ventsim file. The pictures are still available in the Windows folder if they are required again.

5.1.10. File Tools

A series of tools to assist with securing, comparing or linking pictures to Ventsim files. The tools are described below.

- **Compare** : **Compares the current loaded file with a saved file.** Any obvious changes to airways such as moving, deletion, new attributes, presets or sizes will be highlight on screen and in the error list box.

  HINT : This function may be useful where there may be multiple similar versions of the same file, and it is unknown what changes may have been made between versions.

- **Security** : **Sets the file security with a password to prevent unauthorised changes or access.** In addition, a password protected file cannot be merged with another. To activate security for a file, simply select this option, enter a password and click what security option you wish to apply.



Figure 5-2 File Security Options

- View Only – Allows the model to be loaded and viewed, but not changed in any way or re-saved.

- Read Only – Allows the model to be loaded and modified, but not resaved or copied to a new model.

- Lock File – Prevents the file from being opened or viewed.

When a security enabled file is loaded a dialog form will request a password. If the password is not entered or is incorrect, only the restricted security access option will be available.



CAUTION – Passwords are case sensitive. Ensure you can recall the password. A lost password means the file will not be able to be opened or changed in the future.

5.1.11. Save Picture

Saves the current screen to a file location as an image file.

This file can be later loaded into documents or presentations from other software packages.

5.1.12. Import

Imports external data into Ventsim Visual™ to build model model.

Ventsim can import data from TXT (text) files, DXF (drawing exchange format Autocad) files, DWG (Autocad native format), STR (Surpac string files), DM (Datamine Files – String or Wireframe Solid) and VDP (VnetPC™ files).

Text Files

Imports model data from *TXT* format (text format with fields delimited by a TAB character). This format is widely available through most spreadsheets and can be read into word processors. The standard format for a *TXT* file can be saved from Ventsim Visual™ under the save as command. Most components (such as fan database and colour settings) can be excluded from a *TXT* file, leaving only the main file component if desired.

A Ventsim text file must have at least the first row **header** line, which defines the text file as Ventsim compatible and a **Completion** line 'END' (the last line in a Ventsim Visual™ saved *TXT* file).

Load any Ventsim file saved as a TXT file to view the structure in a compatible editor (for example Microsoft Excel™)

	A	B	C	D	E	F	G	H	I	J	K	L	M	N
1	4	MINEDESIC	1	1	0									
2	MAIN	Entry Node	Exit Node	Branch Na	Error Mess	pathways	X1	Y1	Z1	X2	Y2	Z2	Width	Height
3	1			Multiplate Arch		1	5510	1474	1256	5365	1558	1235	5.477226	5.477226
4	2	Tf95/Surf		Main Shaft		1	4949	1950	1257	4950	1950	1233	5.6	5.6
5	3	TVR/Surf		Temp VR		1	5396	1791	1256	5396	1791	1200	3	3
6	4	Surf/Rb82	60/Rb82	Rb82		1	4827	1716	1257	4827	1716	1194	3.5	3.5
7	5					1	5027	1780	1256	5027	1780	1179	4.1	4.1
8	6					1	5018	1798	1256	5018	1798	1176	4.1	4.1
9	7			SZ Decline		1	5365	1558	1235	5160	1677	1206	6.3	6
10	8			Fowler Shaft		1	4950	1950	1233	4950	1950	929	5.6	5.6
11	9					1	5160	1677	1206	5153	1679	1205	6.3	6
12	10			60mLv Access		1	5153	1679	1205	5012	1659	1187	6.3	6
13	11		Sa50/Surf	Sa50		1	4500	1800	1202	4500	1800	1265	5.6	5.6
14	12			Temp VR		1	5396	1791	1200	5396	1791	1121	3.8	3.8
15	13					1	4760	1571	1200	4825	1537	1192	4.5	4.5
16	14					1	4752	1624	1195	4768	1624	1194	5	5.2
17	15					1	4742	1605	1195	4760	1571	1200	4.5	4.5
18	16					1	4752	1604	1195	4752	1624	1195	5	5.2
19	17					1	4752	1604	1195	4742	1605	1195	4.5	4.5
20	18					1	4837	1720	1194	4836	1716	1194	5	5.2
21	19					1	4829	1718	1194	4837	1720	1194	2	2
22	20					1	4836	1716	1194	4832	1700	1193	5	5.2
23	21	60/Rb82				1	4827	1716	1194	4829	1718	1194	1	1
24	22	60/Rb82		Rb82		1	4827	1716	1194	4827	1716	1162	3.5	3.5
25	23			Qb80#1		1	4768	1624	1194	4770	1622	1256	2.2	2.2

Figure 5-3 An example of a Ventsim Visual™ Text File Loaded into Microsoft Excel

Import (DXF / DWG / DM / STR)

Imports ***DXF , DWG , Datamine and Surpac*** formatted data (supported by many CAD and Mine Planning packages).

Importing graphics items can serve two functions. Importing line string graphics can allow Ventsim Visual™ to directly create new airways, using the line strings as centre lines for the development. The centrelines can be converted to airways during the import function, or later on by selectively clicking or fencing the centrelines with the Add > Convert function. Further utilities under the tools menu allows users to quickly turn the new airways into viable models.

> HINT : Converting all imported centrelines to airways can be a problem if some model airways already exist and may be duplicated by this function. Instead, loading centrelines as a reference graphic without converting to airways can allow the user to check where extensions or changes to a mine model may be, particular if some of the centrelines may overlap existing airways. The reference lines will extend from existing ventilation airways showing where extensions to the mine ventilation model may be required. The referenced centreline can then be selectively clicked or fenced to convert to airways using the Add >Convert function.

A second option allows importing DWG or DXF files as 'references', which places the graphics within the model, but does not affect or interact with the model airways. Examples may include mine surface terrain, orebodies, actual development solids etc. This option allows the reference graphics to be used as a guide to building new airways, or simply enhances the display with more information about the mine environment. Any solids or wireframes that are present in the DXF will automatically be imported as a 'reference' graphic, as Ventsim Visual™ cannot build new airways from graphical solids (only centrelines)



Figure 5-4 Import Option form showing DXF import options.

Import reference files can be merged with an existing model (for example a mine addition), and new airways built with DXF centre lines can be set with default attributes (airway sizes etc) before importing. Attributes can easily be changed later within the program.

> HINT : File imports support drag'n'drop. Simple grab the file from a windows folder or directory and drop it on the Ventsim Visual™ screen. More than one file can be imported at a time by using the SHIFT or CTRL key to select and load the files.

Import Options Ventsim Visual™ will search a DXF file for both line strings and solids, as well as layers within the DXF file. The import options indicate what action to take if these items are found.

Layers

The right hand column lists available layers in the DXF file which may be imported. Only select the layers required to be imported into Ventsim.

Centrelines

Centrelines (lines or polylines) can be either converted to ventilation airways, which will carry airflow within a ventilation model, or simply as a reference graphical line string, which will not affect a mine ventilation model, but which can be used to help guide and place manually constructed airways.

Import Centrelines Disabling this function will tell the program to ignore any line strings found.

Merge Data Adds the new imported data to the current model

Import as reference only Tells the program NOT to build airways out of centrelines, but simply import as a graphical reference. A centreline can be converted later to an airway using the Add > Convert function.

Surfaces (referenced) Surfaces or 3D solids cannot be directly converted into airways (unless a 'convert all' option is attempted), however 3D data can provide a useful reference to manually developing Ventsim Airways. In addition, it can provide an important visual aid to viewing ventilation models within an actual mine environment.

Import Solids Disabling this function tells the program to ignore and not load any solid graphical data found in the reference file.

Merge References Adds the imported data to any existing referenced solid graphical information already within the model

Wireframed Only Adds the imported data as a wireframe line solids, instead of a polygon solid.

Metric or Imperial Coordinates Most imported files do not have an internal specification of whether the units are Imperial or Metric. Ventsim will assume the coordinates are the same as currently used in the Ventsim file, however if the coordinates system are mismatched, then the imported data will be displaced to incorrect coordinates (for example a metric DXF imported into an imperial Ventsim model). This setting allows you to override the default Ventsim setting to ensure coordinates will match up.

Offset X, Y, Z Allows a DXF file to be imported with an offset from the original file coordinates. This may be useful to match existing coordinates used in Ventsim, or when a 2D file single elevation file needs to be moved to a new elevation in Ventsim.

Convert 2D Flattens the entire DXF file on to a single elevation or level. Occasionally, flat 2D CAD files may have different elevations set in the file. When these files are used in a 2D CAD package, the elevations difference may not be noticed, however when loaded into Ventsim, the elevation differences may become troublesome in a 3D working environment. If the OFFSET Z option is entered, then the imported elevation will be at this number when this option is set.

Scale Allows the DXF import data to be scaled to a different size. This is sometimes usefull if the original DXF data has been scanned or converted from a PDF file at an arbitrary scale and no longer matches the true scale.

Rotate Rotates the DXF data around a zero based origin by a specified number of degrees.

Default Colour Allows the user to select the colour of the reference data to import.

Use DXF Colours Colours the imported graphics to the original colour (if selected), or the user selected colour (if not selected)

Split Layer Names Imports the reference graphics into Ventsim with each layer as a different reference name, instead of a single reference name encompassing all layers. The reference names can then be individually managed in the Reference Manager function under the File menu.

Filter Splines Imported splines (smooth curves) can have hundreds of data points to make smooth curved lines. This can consume excessive memory in Ventsim. Select this function to reduce the imported data requirements, and approximate the curves with a series of straight lines.

Import STR (Surpac Strings)

Similar to DXF functionality, Ventsim will attempt to import line strings and offer to directly convert to airways, or import them as a reference for later use.

Import DM (Datamine Strings and Wireframe Solids)

Similar to DXF functionality, Ventsim will attempt to import line strings and wireframe solids from Datamine compatible files.



Figure 5-5 Export to DXF Options

5.1.13. Export DXF

Provides a utility to export Ventsim centrelines, text and solid graphics to a DXF file for importing into other CAD software. The colours and text exported will be set to the current screen colours and text. Different items can be selected for exporting. They will be placed on different DXF layers so they can be turned on or off independently in the CAD program.

Note that any airway ventilation attributes will be lost during the export process, and DXF files cannot be re-imported back in to Ventsim as ventilation models.

5.1.14. Manage References

Provides a utility to separately manage any imported graphics reference. Each imported object can be separately coloured, made transparent or hidden from the main view through the form options.

Select one or more graphics objects from the list with the mouse (hold the shift key down to select multiple items). A [+] against the name indicates it is currently being shown. A [-] indicates it is currently hidden.



Figure 5-6 Reference Graphics Manager

Colour Changes the colour of the items. The second colour shows the transparency effect on the colour. Clicking the multi-coloured box will colour the reference graphics object with a full spectrum of colours based on elevation.

Transparency Changes the transparency of the item.

Hide Hides the object from the screen view

Show Shows the object in the screen view

Merge Joins together two or more selected files from the reference graphic list.

Delete Removes the reference object from the file

Duplicates Search all reference graphics for duplicate graphics and removes any duplicates to reduce memory requirements. This function does not remove duplicates on different reference

layers.

Memory Shows the current internal Ventsim memory reserved for storing reference graphics. If this approaches 100%, consider removing some reference graphics objects, or alternatively if the computer has sufficient memory increase the Reference Graphics memory from the Settings >Settings menu.

5.1.15. Title Note

Allows the user to specify a unique file comment which appears in the top title bar.

This comment can help identify the date, name and purpose of the model.

5.1.16. File Memo

Allows users to write an extensive descriptor regarding the function or description of the current model.

This is saved with the file for future reference.

5.1.17. Page Setup / Print / Print Preview

Prints a graphic picture of the model in the View Window to an installed printer.

Only printers with Windows supported graphics capabilities will be capable of printing the model. As Ventsim Visual™ uses a perspective view, no particular scale is applied to the image. The image is sized to the maximum size of the page and orientation. To reduce colour output, the Ventsim screen colours can be changed under the Settings > Settings > Graphics > Colours menu. For detailed engineering accuracy output, it is recommended to export the model to a DXF file for loading into a suitable CAD program for later output to a printer.

5.1.18. Previous File Listing

Quickly loads files recently loaded or saved.

5.1.19. Load Demonstration

Loads a generic model of a typical mine.

This is for demonstration purposes only, and contains a number of simple mine examples to view. Note that while these items can be modified, they cannot be resaved in the same folder.

5.1.20. License Manager

Opens the License Manager form.



Figure 5-7 Automatic License Activation and Release

Licenses Ventsim Visual™ licenses are floating licenses which can only be used on one computer at a time. They can be *activated* for use on one computer and then if required *released* and used on another computer (within the terms of the license agreement). License certificates are stored on the Ventsim server and prevent simultaneous installation of the same license on more than one computer.

As part of the digital licensing agreement, the license collects the computer name and user name of the computer that Ventsim Visual™ is currently activated on. This system protects against unauthorised use of the Ventsim Visual™ license and informs other users who has currently activated the software license.

Releasing a License Once a license is activated on a computer, it cannot be moved to another computer unless it is first ***released*** from the activated computer. If another computer tries to activate the same license simultaneously, this will be prevented and a warning will display the currently licensed computer and the login user name of the person who has installed it.

An internet connection is required to activate and release license certificates from a computer. If an internet connection is not available or an internet connection is not authorised by your firewall or company administrator, try to arrange a link to the http:\\ventsim.com website. If this cannot be done, a manual license transfer can be performed via email located under the file menu.

Licensing Problems In the event the license manager fails to activate or release the license, note the error message and take the following action.

If the error message reports the license is active and in use by another computer, then only that computer can release the license. If this computer is no longer available and license has not been released then contact license@ventsim.com for further assistance.

If the error message reports an internet connection problem, then click the "TEST www.ventsim.com web connection" link on the License Manager form. Ensure that Microsoft Internet Explorer can link to the Ventsim webpage. If this does not work, then the Windows connectivity problem needs to be resolved before further action can be taken in Ventsim. Ensure an internet connection is available, and the firewall or proxy server is not blocking the Ventsim website.

Some companies have PROXY settings that inhibit third party programs using the internet. In most cases, Ventsim Visual™ will automatically adopt the same proxy settings as Microsoft Internet Explorer. If these settings are not available from the local computer, they can be entered into Ventsim using the Proxy Settings section.

If the license is a DEMO or a STUDENT / EDUCATION license, and needs to be removed from the computer, click on the FILE > RESET LICENSE menu option in the license manager.

5.1.21. Exit

This command closes Ventsim. Ventsim will prompt if your model file, fan database or defaults have not been saved since last modified.

5.2. Edit Menu

5.2.1. Undo

Reverses the previous action

Undo is a fully functional undo facility that will undo a number of previous changes made to a model (up to the buffer size of the undo function). Note that while it will not directly undo a simulation, by pressing UNDO until your previously model is in place and then re-simulating, this will produce the same results.

5.2.2. Redo

Redo will reverse the result of the undo function.

5.2.3. Copy and Paste Airways

Copy airways from one Ventsim Visual™ program to another.

Copy and Paste Airways creates an *exact* replica of selected existing airways in a model and pastes them into the same location into the existing or new model. The function is primarily designed to copy and paste airways between Ventsim files or between different Stages in a mine ventilation design; for example to update airways from a model that has been modified.

To use this function to copy and paste between models, ideally have two copies of Ventsim Visual™ open with different model files. Select the *Copy Airways* menu item, and click on, or fence the airways you wish to copy.

To paste the airways, move to the new model (or load it up) and select the *Paste Airways TRUE* menu item. The copied airways will be pasted into the new model at the same coordinates as the original airways.

To paste duplicate airways between STAGES, use the same technique, but simply copy the airways in one stage, switch to the desired stage name or number, then Paste Airways TRUE. A copy of the airways will be set in the new stage.

If airways become duplicated in the process, Ventsim Visual™ will delete one of the duplicate copies.

To paste airways in a different location, use the Paste Airways LOCAL menu option. This will paste the airways around the current local screen location set in the view window, effectively copying the airways from the original location to a new location.

5.2.4. Clone and Apply Attributes

Clones selected attributes from one airway and applies the attributes to another.

Attributes are physical airway parameters such as size, friction factors and shock losses, as well as identifying attributes such as layers. You can decide which attributes to apply to an existing airway by selecting the **Clone Options** function from the menu or Select Manager Form from the toolbar.

To clone attributes, select the *Clone Attribute* menu item, and click on an existing airway. The airway properties will be copied to memory and the program will automatically enter the *Apply Attribute* mode.

To apply attributes, make sure you are in the *Apply Attribute* mode if it has not already been selected and either click on an existing airway, OR fence a selection of airways to apply the

attributes to that group. Cloned Attributes can be applied at anytime (even after other editing has been done) and will apply the most recently cloned values.



Figure 5-8 Clone Attributes

Example : An existing airway has been set as an exhaust airway with custom primary and secondary layers. To copy these attributes on to other airways,

- Select Primary, Secondary and Air Type options on the Select Box
- Select Edit > Copy Attributes
- Click the airway you wish to copy the attributes from.
- Select Edit > Paste Attributes
- Click or Fence the airways you wish to copy the attributes to.

5.2.5. New Airways

Control which attributes are applied to new airways.

Use Inherited New airways drawn from existing airways will inherit the settings from the airways they are attached to (such as size, shape, friction factors etc). Airways which do not originate from another airway will use the default setting values.

Use Defaults To force the program to use the Default Values (from the Settings Menu), choose Default. All new airways drawn (regardless of whether they connect from existing airways) will use the default settings.

Use Cloned Forces the program to use the Cloned Settings from a previously cloned airway. For example if a shaft is to be drawn from a horizontal airway, cloning a similar shaft and then drawing the new airway with this function set, will result in a new shaft with the same size, parameters and layer settings as the cloned shaft.

5.2.6. Find / Find Next / Find ALL

Automatically locates specific airways and moves the screen to selected parts of a model.



Figure 5-9 Find Airway Data

Selecting one of the options will find and highlight the airway searched for. The option may be repeated for further branches by pressing the *Find Next* menu function, the *Find* tool bar button or by pressing *<F3>* on the keyboard.

> HINT – Pressing <F3> will rapidly allow you to search through a model, by repeatedly jumping to the next item. To view more detail about the items being jumped to, LEAVE THE EDIT BOX open. The EDIT BOX will instantly update with detail about every airway that is jumped to.

5.2.7. Highlight or Select All

Highlights or select all airways matching the previous find criteria. To find *All* instances of an airway (for example to find all airways with the name 'shaft' in the airway name, or to find all fans, click on an initial find type and then click on *Find All*. All items with these parameters will *Highlight and Flash*.

For example, if FIND was used to locate an airway with the name "M52 Decline", Select All would select ALL airways with this name in the airway name field. The selected airway could then be edited or manipulated as a group.

5.3. View Menu

5.3.1. Fit All

Fits all the display data into the view window.

> CAUTION : If display data is from two regions a long way apart (for example data may have been imported into Ventsim Visual™ from a different coordinate system). The Fit All may not be able to accommodate the range of data attempted to be shown, or the camera may be too far away to view the data effectively. Ensure all data is in the same coordinate region before it is loaded or merged.

5.3.2. Show All

Resets all hidden levels, layers and airway data and displays the entire model. Occasionally a model may have hidden or semi-transparent airways set from a previous action. Show all will

quickly bring the entire model back to full view. *Show All* will force Ventsim Visual™ to show all elevations of airway data in your model, even if they are outside of the ranges specified in the *Level Database*.

5.3.3. Reset Display Resets the graphics display adaptor and re-establishes the graphics on the screen. Some types of hardware graphics display adaptors may occasionally corrupt or fail to show the screen graphics, particularly if the computer has been brought out of hibernation, sleep or screen saver. This option in most cases should recover the graphics.

5.3.4. Quick View Quick Views can quickly be saved and recalled sequentially outside of the normal Saved View system. Quick views are not added to the Save View menu selection. The views can be quickly recalled at any time using the arrow keys. The function primarily assists with navigation of large models, where different areas can be quickly returned to for viewing simulation results.

Save Quick View Creates a temporary view position for a model. The view is added sequentially to previous stored Quick Views. The sequence of stored quick view can be recalled or returned to using the LEFT and RIGHT arrow keys.

Clear Current Clears and removed the currently recalled quick view. The view is removed from the sequence of other stored Quick Views, and can no longer be recalled.

Clear ALL Clears all Quick Views from memory.

Previous Quick View Recall the previous Quick View from the sequence of saved Quick Views.

Next Quick View Recalls the next Quick View in the sequence of saved Quick Views.

5.3.5. Copy to clipboard **Copies the screen to the Windows clipboard for direct pasting into an external documents (such as a Power Point presentation)**. Static Views are primarily for referencing areas before and after simulation.

5.3.6. Copy to clipboard (all) **Similar to above, but copies any overlying windows (such as legends and graphs)**.

5.3.7. Copy to clipboard HI-RES **Similar to above, but copies an ultra-high resolution picture to the clipboard.** This picture has more detail than the screen graphics, but may fail to work on slower or older computers. Hi-Res pictures will show more clearly in large format printing or reports, but are of less use in screen or projector presentations where the screen cannot show the higher resolutions.

5.3.8. Snapshot **Creates a picture copy of the current window in a new form window**. Static Views are primarily for referencing areas before and after simulation. It may be useful in showing a sequence of changing ventilation simulation results by storing previous results for comparison with new results.

The form window defaults to 25% of the size of the normal view window, but can be resized or maximised at any time to show full detail. The static view forms can be renamed for reference or saved to a picture JPG file for future use in other software.

Static views are simply picture copies of the original model graphics and remain the same regardless what happens to a model after the static view is created. They cannot be edited, moved or rotated. The number of static views created is only limited by the memory capacity of the computer.

HINT : Both the EDIT box and the FAN DATABASE form can also be reproduced as a STATIC view. This is useful to provide a quick comparison between airways or model results before and after simulation changes. To use this function, simply RIGHT click the EDIT box or FAN form, and select Static View

5.3.9. Set Edit Centre

Sets the edit grid and point of focus to a specified coordinate or elevation.

New airways will be drawn on the specified elevation

5.3.10. Show All Elevations

Shows all elevation ranges for the model.

Turns on all level elevations views, and includes airways and references outside of the defined elevation ranges.

5.3.11. Show All Layers

Shows all layers (primary and secondary) in the model.

Turns on all layers so all airways graphics will be visible.

5.3.12. Hide Zero Flow

Hides airways with no flow. This function is useful for hiding disused or unventilated parts of a mine so they do not clutter the display. Airways with no flow (or airflow below the level set as zero flow value in the Settings menu) will be shown as transparent or hidden, depending on the transparency settings described above, and the transparency amount set in the Display Manager.

5.3.13. Hide Excluded

Hides airways which have been set as EXCLUDED from the model. This function is useful for hiding parts of a mine which are not required to be simulated, or are not set to be part of the current simulation model. The exclude options for airways are available from the EDIT box.

Hint: Old sealed off development, or future development yet to be mined can be excluded from the model to speed up simulation and display of models. Excluded airway can be hidden to simplify the display, but can be shown and converted back to normal airways at any time if required.

5.4. Saved View Menu

5.4.1. Save View

Saves the current view and stores the save name in menu for future recall. Save view will save all attributes in a view including RL levels, layers and display options. Saved views can be pulled back into any current window by selecting the saved name from the pull down view list.

5.4.2. Delete View

Deletes the saved view stored in the CURRENT pull down menu list (and hence removes this name from the list).

5.4.3. Saved Views

Four view orientations are set as defaults

- PLAN

- EW SECTION
- NS SECTION
- ISO

These standard views will display the model at various orientations (although the model can still be orientated to the same orientations by using the RIGHT mouse button. These views cannot be deleted or changed

Caution: The Perspective view will distort some aspect of the views. For example, the plan view will show the airways at the EDIT grid level to plan, but airways above and below this elevation will appear larger and smaller respectively.

Any further saved views will be placed below these items. Saved views save the position, orientation, colour scheme, data types and attributes of the screen at the time at which they were saved.

Hint: Saved views are not only useful for recalling the location and orientation of a model. Because they recall selected levels, layers, data types and colours, they can be a quick way to establish a template to edit and view different data aspects of your model. For example, you may have an AIRFLOW view, custom set to highlight a certain range of airflows in different colours, while a 'HEAT' view may be saved to highlight a range of temperatures.

5.5. Run Menu

The RUN menu allows menu access to the main simulation functions of Ventsim Visual.

Standard Functions

- Airflows
- Steady State Contaminants
-

Ventsim Visual™ Advanced Functions

- Thermodynamic
- Diesel Particulates
- Dynamic Contaminants, Gas, Heat and DPM
- Recirculation
- Financial
-

Ventsim Visual™ Premium / VentFIRE™ Functions

- VentFIRE™ Fire Simulation
- Multi type dynamic simulations

5.5.1. Airflows [ALL]

Undertakes a steady state airflow simulation of the model. The Standard version will only perform an incompressible flow simulation, whereas the Advanced and Premium versions will optionally perform compressible flow mass balanced simulation if selected in the settings.

5.5.2. Thermo-dynamics [ADVANCED]

Undertakes a steady state thermodynamic simulation, which derives initial airflow (and mass flows) from an airflow simulation. Thermodynamic simulation is complex and endeavours to simulate numerous parameters encountered in a mining environment. The simulation process follows well documented methods described in books such as *Subsurface Ventilation and Environmental Engineering by Malcolm J. McPherson*. Heat parameters that Ventsim Visual™ Advanced considers includes

- Heat and moisture derived from rock strata and ground water.
- Thermal properties of different rock types.
- Heat from point sources (such as electric motors), linear sources (such as conveyors), diesel engines and oxidisation of ores.
- Heat from auto-compression of air.
- Refrigeration and spot cooling of air.
- Changing densities throughout the mine, due to depth and temperature effects, as well as pressure from ventilation flows.
- Natural ventilation changes from changing densities.
- Moisture from sources such as dust suppression sprays.

- Condensation from over saturated air

To accurately model a mine, all of these factors must be considered. If data for a parameter is not entered, Ventsim Visual™ will assume a default value specified in the ***Settings*** and in most cases will simulate a result anyway. The accuracy of this result will largely depend on the accuracy of the entered data, and the default values used. More information regarding thermodynamic simulation can be found later in the manual.

5.5.3. Diesel particulates [ADVANCED]

Simulates the spread of diesel particulates throughout a mine model, derived from diesel heat sources placed throughout the model. The simulation process assumes a steady state emission of diesel particulate sources and a uniform mixing process throughout the model and its junctions. Note that this may not always be the case in a real mine, where incomplete mixing and dynamic changing of exhaust emissions through the day can change concentrations of diesel particulates at different times, however it provides a useful baseline to examine the effects of changing ventilation circuits and flow in a mine.

For more information see Diesel Particulate Simulation

5.5.4. Dynamic Simulations [ADVANCED]

Simulates the time based spread of contaminants, gases, heat and DPM contaminants. Time based dynamic simulation show the results of a simulation on the screen at increasing time increments that can be paused and resumed. Only one of these dynamic simulation parameters can be simulated at a time (although the PREMIUM VentFIRE™ module can simulate multiple parameters simultaneously) To record a history of time base simulation results, 'monitors' can be placed at defined locations to record changes to ventilation flow.

For more information see Dynamic Simulation

5.5.5. VentFIRE™ [PREMIUM]

VentFIRE™ as the name suggests allows for complex simulation of fire heat and contaminants. In addition, it allows for simultaneous dynamic simulation of multiple ventilation parameters such as airflow, gases, contaminants, DPM's and heat. VentFIRE™ allows models to be automatically modified during simulation to enable scenarios such as altering fans, opening or closing doors, or moving machines to be modelled dynamically over time.

For more information see the VentFIRE™ Simulation section.

5.5.6. Recirculation [ADVANCED]

Examines a model for paths which may recirculate airflow in a mine and reports the % or recirculated air in each airway.

The definition of recirculation is the passage of airflow or a portion of airflow through the same point in a mine more than once. Ventsim Visual™ uses a custom algorithm to track the paths and recirculated portion of every airflow throughout a mine, and report where airflow may recirculate. To prevent trivial reporting of recirculating air (such as minor leakage of air through a high resistance stopping) a default tolerance of 1m3/s recirculation is used. These limits can be changed in the Settings form. Recirculating airflows are shown as a portion or % of air which has recirculated through the same airway.



Figure 5-10 Example showing a ventilation fan recirculating air

Note that this is not necessarily the total amount of recirculated air travel through a location, only the portion of air travelling through the current location and returning to the same location. Air in some cases may have recirculated upstream in a different part of the mine, and will not be reported as recirculated in downstream headings that do no recirculate. To view the downstream effect of recirculated air, click on the 'Recirculated Stream' data or colour option, instead of the Recirculation % option.

5.5.7. Financial Simulation [ADVANCED]

Provides a number of methods for optimising airway sizes, including defining set airway sizes and costs for consideration or by defined mining costs as variable and fixed factors so that an unlimited number of different sizes can be considered.

See the financial optimisation section for further information.

5.5.8. Contaminant Simulations

Simulates the downstream spread or the upstream source of contaminants in the air. These routines are generally used to identify the path and spread concentration of fumes, gases, dust and smoke from a contaminant source, or to predict where the airflow for a particular location comes from. The routines are not generally recommended for large fires, due to the dynamic and changing nature of fires, and the dynamic heat effects on natural ventilation pressures.

To clear any contaminants or gases from a ventilation model, select the **Clear Contaminants** option from this menu, or the toolbar menu.

See the Contaminant Simulation section or the Gas Simulation section for further information.

5.5.9. Summary

Displays a summary of the current model collectively, or grouped under different *TABS*. The data may be copied to the clipboard, for pasting into another package such as Microsoft Word, or an email.

Note that if Staging is used, then only the currently viewed stage is summarised.

An example output is listed below from the *Advanced* version with explanations.

MODEL AIRWAYS	2772	Total number of discrete airways in a model
Total length	66196.0 m	Total summed length of all airways
Total airflow intake	1025.5 m3/s	Total airflow entering the mine from the surface
Total airflow exhaust	1040.2 m3/s	Total airflow exhausting from the mine to the surface. Because of air density changes due to heat an elevation, this may not match the intake value on models with compressible flow.
Mine resistance	0.00164 Ns2/m8	Cumulative resistance of moving the total airflow through the mine. This includes the resistance of ventilation ducts and recirculated air, so caution should be taken in adopting this value

		for primary airflows.
Total mass flow	1260 kg/s	Total mass of air flowing through the mine. Note that this is 'dry' mass flow which excludes moisture content.
POWER SUMMARY		
AIR (loss) Power	1772.2 kW	Total theoretical power required to move air through all airways
INPUT Power	3609.2 kW	Total installed electrical power required to move airflow
Consisting of ..		
9 fans @	3607.6 kW	
0 fixed press @	0.0 kW	
2 fixed flows @	1.6 kW	
Model Efficiency	49.1 %	Ratio of theoretical friction loss to installed power. Model efficiency will decrease as more fans are required to boost airflow through mine. Placing fans in series (i.e. boosting) accumulates fan efficiency losses at each stage of the fan.
MODEL FAN SUMMARY		
Fan Installations	7	Total fan installation in model
Fan Numbers	9	Total number of fans in model
Fan Sites Switched Off	0	Fans turned off
Fan Sites Stalled	0	Fans operating at their maximum pressure
Fan Sites Low Pressure	1	Fans operating at a pressure beneath the lowest fan curve pressure, but still above zero
Fan Sites Negated	0	Fans running with no or negative pressure added
Fans running reversed	0	Fans running in reverse (user selected)
Total fan power	3607.6 kW	Total of all fan electrical power. The is calculated from fan shaft efficiencies, and motor efficiencies. The fan power is

		calculate from the fan power curve. If the curve is unavailable, it is estimated from the fan total efficiency curve. If this is unavailable, the default fan efficiency is used.
HEAT & MOISTURE INPUT SUMMARY		
Diesel Sources	0.0 kW from 0 sources	Sources of diesel heat and contaminants
Sensible Heat Sources	0.0 kW from 0 sources	Sources of sensible (dry) heat
Linear (S) Heat Sources	0.0 kW from 0 sources	Sources of heat distributed along multiple airways
Latent Heat Sources	0.0 kW from 0 sources	Sources of latent (vapour) heat
Oxidisation Heat Sources	0.0 kW from 0 sources	Sources of oxidising heat
Electrical Heat Sources	3609.2 kW	Sources of electrical heat
Total Input Heat	3609.2 kW	Total heat input from man-made influences
Total Strata Heat	2885.1 kW	Total heat input from heat dissipated from rock
Broken Rock Heat	1450 kW	Total heat from broken rock, which is calculated when an advance rate is entered for airways or stopes.
TOTAL HEAT SUMMARY	6494.3 kW	Summation of all heat
Total Refrigeration	0.0 kWR from 0 sources	Refrigeration installations
HEAT BALANCE TOTAL	6494.3 kW	Summation of heat minus refrigeration
Moisture Point Sources	0	Number of point moisture sources (such as conveyor dust suppression spray)
Moisture Linear Sources	0	Number of liner moisture sources (man-made, such as decline dust sprays)

Moisture Input as Latent	0 ml/sec	Summary of moisture added from latent heat sources (such as diesel engines and latent point sources)
Moisture Airway Surfaces	4404 ml/sec	Summary of moisture evaporated from rock strata
Model condensation	0 ml/sec	Summary of moisture condensed as water (normally in upcast exhaust shafts) It can also indicate formation of fog in a mine.
MOISTURE EXHAUSTED	4403 ml/sec	Total moisture exhausted from mine.
HEAT AUDIT		
Input heat below surface	6454.5 kW	Check to make sure heat exhausted from mine, is accounted for from summation of underground heat sources.
Elevation adjustment	29.5 kW	Adjustment due to inlet / exhaust elevation differences (auto compression)
Differential inlet to outlet	6469.9 kW	Different between inlet from surface heat, and exhaust to surface heat
Potential heat imbalance	14.1 kW (0.2 %)	Error between the underground inputs and the surface recordings
Potential temp imbalance	0.01 C degrees	Potential error in temperature as a result.

Figure 5-11 Example of Summary Output with Description

Heat Audit errors occur due to simulation approximations made in calculating heat and airflow in a mine. Airflow simulation approximates flow in each airway to an acceptable error, while heat simulation approximates temperature to an acceptable margin. These errors and margins are adjustable in the settings. The summation of these approximations can cause minor variances between heat entered or removed from each airway, and the heat difference between the air entering and exiting the mine. The heat audit function is designed to highlight these potential differences and show the potential effect on simulation accuracy.

How much Heat Audit Error is too much?

It depends on the model and tolerance for temperature margins, however up to 5% is generally acceptable, and will only give a slight imbalance in temperatures. Errors beyond 5% are likely due to excessive airways in the model with little or no flow, which have a relatively high degree of approximation error. In most cases, the error can be reduced by EXCLUDING unused parts of the model with little airflow, reducing the mass flow limit in the heat simulation settings or reducing the temperature error in the heat simulation settings.

Graphs A selection of graphs derived from model parameters.

The energy losses show the loss of input electrical energy into various ventilation losses such as wall friction, shock loss and exit losses. Exit losses represent power lost due to the velocity of ejection of exhaust air into the atmosphere. Note that some of this energy can be recovered and converted to useful fan static pressure by increasing diffuser size and reducing exit velocities.

Heat Gain / Losses show the addition and removal of heat into the mine atmosphere. Note that while autocompression is a significant heat addition to deeper mine, the heat is removed when air travels back to the surface. Also note exhaust fan heat on surface fans has been deliberately excluded from this summary as the heat does not directly affect underground atmosphere.

Moisture Gain shows the addition of moisture to the underground atmosphere. Note that in most cases, moisture is due to either evaporation from rock strata or from diesel engine latent heat.



Figure 5-12 Mine Summary Graphs

5.6. Connect Menu

A selection of tools to connect to external data sources. Some tools may not be available unless purchased as an added extra.

5.6.1. LiveVIEW™

LiveVIEW™ is a Ventsim module designed to connect to external data sources such as SQL databases, Excel or Access data files, or text files. It is commonly used to connect to data coming from live underground sensors. The data can be mapped and displayed within a 3D Ventsim model, and can even be used to simulate new results based on the connected data.

Further information is available from the LiveVIEW™ section of this manual.

5.6.2. Ventlog™

Ventlog is a software program designed to record and collate underground surveyed ventilation data. The Ventlog database can be interfaced with Ventsim to provide the ability to show actual Ventlog data results, overlayed with Ventsim simulation results. This provides a useful tool to compare actual and simulated values when trying to validate a model.

Connect Allows the user to specify a Ventlog file (*.VLG) to connect to.

Import Stations Loads the Ventlog station data into the Ventsim model. The Ventlog data will be overlayed over the corresponding airways in the model. The date of the data import can be specified in the *connect* option.

Export Stations Exports stations created in the Ventsim model to a Ventlog database. This establishes stations in Ventlog complete with correct coordinates and eliminates the need to separately create the stations in the Ventlog program. When the Ventlog software is next used, the

stations can be viewed and edited, and new data can be entered against the stations.

To create a Ventlog station directly in Ventsim, EDIT an airways, then use the NOTE section of the tab to create a Ventlog Station. The name of the station can be changed to anything, however the **[LOG]** must remain unchanged as this represents a code used by Ventsim to export the station.



5.7. Tools Menu

A selection of tools and settings to check, modify and fine tune the model

5.7.1. Fans

Displays a windows form that allows editing, adding and deleting of all fans in the model fan database. Up to one thousand (1000) fans and the associated fan curves may be entered into the fan database. A display for each fan curve and data will be presented when a fan is selected from the display list.

For further information on entering and using fans, see the Fan Section in this manual.

5.7.1. Levels

A list of elevation ranges on which airway data can be individually viewed.

This form allows editing or creating of a list of levels (elevations) between which airway data is located. The level list can contain up to 1000 levels on which your model will be created.

Elevation data can be edited in any order, as well as added at a later date - Ventsim will sort the data from highest to lowest when next displayed.

To select which levels are displayed, use the Data Display manager to select what levels to display. Alternatively, levels can also be independently set by using the mouse context pop-up menu (right mouse button on the screen) to *Select Levels*.

To view ALL levels at any time, simply use the *Right Click* pop-up menu to select **All Levels**. Levels can be sorted by clicking the column header for the desired item.

5.7.2. Stages

Opens the stage form, where stage names can be entered or modified. In addition, detailed descriptions for each stage can be entered, and simulation events for air and heat can be enabled when the user switches between stages in the models.

For further information on staging, see the Stage Section in this manual.



5.7.3. Spreadsheet

Displays a READ-ONLY list of currently viewed or selected airways in a spreadsheet form.

The spreadsheet of airway data is displayed can be copied and pasted to other applications such as Microsoft **Excel** or **Word**.

Up to 100 different types of data can be displayed on the spreadsheet. To display different data types, use the SELECT > DATA OPTIONS menu to select which data you wish to display.

Data can also be removed from the spreadsheet, by selecting EDIT > REMOVE or using the right mouse button.

Data columns can be reordered by selecting the column title and dragging to a new location. In addition columns can be resized and resorted by using the appropriate menu commands.

> **Hint :** While the spreadsheet function is not designed for editing data, extensive data characteristics for each airway can be displayed, and copied to external programs such as Microsoft Excel ™. Ventsim Visual™ provides an Index number and a Unique number reference for each airway. The Index number is referenced internally and during simulations by Ventsim Visual, but may changed for each airway as airways are added or removed. The Unique number will not change, and should be used as a permanent reference number to each airway if other identifiers such as names are not used.



Figure 5-13 Spreadsheet view of model with selected data

5.7.4. Filter

Filtering tools consist of a selection of airway utilities to help filter and correct complex, disconnected or overlapping raw model data. The tools can be run simultaneously as a group, or individually.

The All Tools tab in the form, allows simultaneous filtering using the various selected tools. Alternatively, each tool can be selected and run individually from the other tabs.



Figure 5-14 Filtering Tools Combined

Simplify allows the user to reduce the number of airways in a model to a more efficient number without affecting the overall model analysis.

It is particularly useful where a model has been imported via a DXF file and contains a large number of very detailed but unnecessary small connected airways.

Simplify will search a model for sequences of airways that may be reduced to single straight airways. In doing so, much of the overhead and effort required to set parameters to every airway can be reduced. Note that the simplify function will only combine airways that have a single entry and exit. Airways at junctions and split branches will remain untouched.



Figure 5-15 The simplify dialog box

Maximum Joined Angle The ***Max Angle*** option specifies the maximum angle between two airways being considered for merging. For example, if the original model contains a number of airways that form a curve

and ***Max Angle*** is set to 20 degrees *Simplify* will keep on merging airways until the airways being considered have directions changed by 20 degrees or more.

Maximum Joined Length The ***Max Length*** option restricts simplification to airways less than the specified length. For example if set to 30m, only airways with lengths of less than 30m will be considered for merging and simplifying.

In general, the higher the values of the ***Max Angle*** and ***Max Length*** settings, the more aggressively Ventsim Visual™ will simplify and combine airways.

Use combined lengths: Ensure the new length of a combined airway is fixed to remain exactly the same as the original combined lengths *even if the original airways formed a curve*. If not set, the new lengths will be recalculated as the true length of the new straight line. In most cases the difference is minor, and it is recommended to leave this option unchecked.

Ensure no resistance presets filtered: Ensures that airways with a preset resistance (such as a bulk headed airway) are not simplified and merged with other airways.

Ensure airways dimensions are the same: Check to see if airways that are considered for merging and simplifying are only joined if they are exactly the same size.

Ensure wall types are the same: Similar to dimensions, only airways with similar wall (friction factor) types are joined.

Selected airways only: Only simplify selected airways and ignore all others.

HINT : Short irregular airway segments are best simplified with high joined angle settings (+45 degrees) or smaller joined length settings (<20m). Long smooth airway segments are best simplified with low joined angle settings (<20 degrees) and high joined length settings (>50m). Note that airways can be individually selected for simplification.

5.7.5. Binding

Binding connects disconnected airways ends or intersections. Many imported DXF files do not have correctly connected centre lines or ends. This function will search for unconnected ends or crossed airways and join them together if they are close enough. Airways must always be correctly joined to allow air to flow

Warning : These functions are intended for preliminary clean-up of new models, not for existing balanced models. It can permanently change the characteristics of your model and may delete some preset items or values. Ensure only the required airways are first SELECTED before binding or simplification.



Figure 5-16 Binding Tools

Bind loose airway ends

Defines the distance to join airway ends in a model which are close together but do not join. Imported DXF file commonly have lines which don't exactly join due to editing or drawing methods used in the original file. Airways which do not exactly join in Ventsim Visual™ will not flow air, and will result in a No Exit / Entry warning.

The search radius can be entered in the preset box. For example a search radius of 4 will join any loose end (airway end without another connection) to any airways within 4m of the end.

Bind adjacent nodes

Defines the distance to join adjacent connected nodes in a model which are close together but do not join. This function is a little like simplify, in that small airways between the joined nodes will be removed.

Warning : Selecting this option with too greater distance can seriously distort the model. Use with caution or not at all.

Bind airway ends to Junction

Defines the distance to join airway ends to other airway mid sections. It effectively splits and joins into the new airway. Imported DXF files commonly have lines which cross the path of airway ends, but do not have a joining node. This function will create a joining node along the line.

Bind Crossed Airways at Intersection

Defines the distance for joining airways that intersect or come close to intersecting, but do not have a joining node. It effectively splits and joins both airways into new airways. Imported DXF file commonly have lines which cross the path of another airway, but do not have a joining node.

5.7.6. Duplicates

Searches for airways which have duplicates in the same or similar position. Duplicate airways can cause problems with air simulation due to poorly defined or hidden flow paths that the user cannot see.



Figure 5-17 Duplicate Finding Tools

Adjacent Angle is the maximum angle difference between adjacent airways that may be considered as a duplicate. Airways next to each other with greater angles between them will not be considered as a duplicate. The smaller the angle in degrees, the more 'parallel' and airway must be to be considered a duplicate.

Adjacent Distance is the maximum distance two adjacent airways can be apart over which they will no longer be considered as duplicates.

Exact selects only an exact matching airway as a duplicate

Reversed selects airway the same, but facing opposite directions.

Similar selects airways similar but not identical. The adjacent angle and distance will be used as a criterion for selection.

Action defines what action will be taken when the duplicate airways are found.

5.7.7. Convert To 3D

Moves the model airways on to a 3D surface or contour plan, effectively converting the model from a 2D plan to a 3D model. Note that if only parts of a model need to be converted, they should first be selected with the Select tool



Figure 5-18 Filter Airways

Use Reference 3D Lines : Uses lines (such as contours) loaded in from a DXF as a reference to convert the model to 3D.

Use Reference 3D Solids : Uses solids (such a terrain polygons) loaded in as a referenced DXF object, to convert the airways to 3D,

Simple Method : A fast method which searches the closest 3D reference point. Suitable for relatively flat conversions

Detailed Method : A slower method which searches for the closest vertical intersection. It is more suitable for rugged 3D surface conversion.

HINT : To convert a multi seam or level model to 3D using this function, individually group select the airways required, and ensure only the relevant 3D DXF object for that level is turned on before conversion.

5.7.1. Utilities

The utilities sub menu provides many functions to assist with manipulation of airway data, particular raw data which may have been input from a DXF import or similar.

Swap Axis Swaps the Easting and Northing (X and Y) coordinates of all airways in the model. This may be useful where the coordinate system in Ventsim Visual™ does not match the directions used on the Mine Plan Grid. Where the direction of the coordinates needs to be reversed, use the Settings > COORDINATES settings to change direction of the axis coordinates.

Rotate Coordinates A utility which rotates all (if none are selected) or just the selected airways by a number of degree around the point of focus. The point of focus is always at the centre of the screen. It can be set by middle clicking the mouse button on a point, or by entering the centre coordinates in the View > Set Edit Centre option.

Mirror Axis Allows all airway coordinates to be mirrored around the centre location of the screen. Note that the centre location must be accurately set before this function is used.

Reverse Coordinates Changes the sign of airway coordinates from positive to negative or visa-versa. Not that this is similar to mirroring coordinates around a zero centre.

Scale Coordinates A utility which scales all airway or reference coordinates by an input factor. This effectively reduces or increases the size of the model without changing the airway size. An airway length will not be changed if it has been fixed.

Warning this function should only be used to scale schematic ventilation model with predefined fixed airway lengths. Scale a model without fixed length will change the airway length and resistance, making it invalid for true scale model simulation.

Scale Airway Size A utility which scales all airway dimensions by an input factor. This effectively reduces or increases the size of the airways in the model.

Warning this function will rarely find a practical use. One possible use is to incorporate an 'over break' factor into mine design airway dimensions, as mined airways are often slightly largely than design. Scaling model airway sizes will change the airway resistances, making it invalid for true scale model simulation.

5.7.2. Airways

Modify a selection of airway specific parameters

Lengths Fixes or un-fixes airway lengths, so that models may be manipulated without changing the calculated airway lengths.

Fix All Lengths This will fix and protect all airways in the model from changes in length when moving airways. This may be useful if airways are required to be moved for clarity, but lengths must remain the same.

Unfix All Lengths This will un-fix and recalculate all true airway lengths in a model.

This function will recalculate airways lengths and hence change any previously fixed lengths. If there are any doubts, use the EDIT function to individually fix/unfix lengths of only the airways that need to be changed.

5.7.3. Auto Name

Automatically places a code number on every airway without a current airway name. A letter may be specified to head the number if desired (e.g. B157).

Resequence Index/Unique Numbers

Sequences the order of airway numbers in a Ventsim Visual™ model.

Index numbers are dynamic numbers representing airways stored internally in Ventsim Visual. The numbers may change as airways are deleted or added. Ventsim Visual™ uses Index numbers to refer to airways during simulation and when identifying problems. All index numbers are sequential and the highest index number will be the sum of all airways. Resequencing index numbers renumbers all airways from higher elevation to lowest elevation, easting to northing.

Unique numbers are static numbers which do not change when airways are deleted or added. Numbers are sequenced incrementally from the last highest unique number. As such, as airways are added and deleted, there may be large gaps of numbers between airways. Unique numbers are a useful reference to identify the same airway as the model is developed. Resequencing the unique numbers renumbers all airways from number 1, sequentially top to bottom to the last airway.

HINT Resequencing numbers is not a requirement in Ventsim Visual, but may simplify tracking airways, as the resequence function tends to group airways in similar locations with similar numbers. This is particular handy in the SPREADSHEET function which initially lists airways in sequential index order.

5.7.4. Troubleshoot

This option allows detailed checking of models, and will identify areas of your model that may cause problems during the simulation process. A model with too many redundant bulkheads (bulkheads in the same airway path as other bulkheads), or fans that are in the same airway path as other fans, may result in a model that will not converge.

Restrictive Fans: Finds and alerts the user to fans that are directly competing against other fans.

Unnecessary Bulkheads: Finds and if desired remove bulkheads that are not necessary (usually because another bulkhead in the same airway has already stopped the airflow).

5.7.5. Reset Model

Removes all airflow and temperatures from a model. The simulation processes is restarted with fresh data. Ventsim Visual™ utilises flows, densities and temperatures from previous simulation to help it to recalculate new simulations faster and more accurately. If data has been corrupted during a bad simulation (which may have produced errors, excessive airflows, heat or densities), this may hinder subsequent simulations from finding an acceptable solution, or may simply produce further errors.

Resetting the model will remove all calculation flows, pressures, densities and heat. It will NOT remove any values fixed by the user, such as fixed flows, pressures or heat sources.

5.8. Settings

5.8.1. Presets

A list of preset factors and characteristic used for placing in airways.



Presets include

- Resistances
- Friction Factors
- Shock Factors and Equivalent Length
- Heat, Refrigeration and Moisture Sources
- Layers
- Air Types
- Combustible materials
- Fans (limited to header information only)
- Airway Types
- Airway Profiles
- And more

Values entered into the preset spreadsheet will be made available for applying to airways in the EDIT box. Updating existing values in the preset spreadsheet will automatically change all airways with that preset on the next simulation.

[See the PRESETS section for further information.]

Warning : Be careful when removing existing settings from the preset spreadsheet. Settings removed which already belong to an existing airway, will force the airway to 'set' the values permanently.

5.8.2. Units

Sets the metric and imperial conversion units and factors used for Ventsim Visual, as well as the number of decimal points to show on the display.

The conversion table displays the metric and corresponding imperial units for each type of data used in Ventsim Visual. The table is saved with every model, and can be individually modified for each model file. The conversion settings can be inherited by other models or saved in a template file.

The imperial unit names and factors may be freely changed to suit the region or preference of the mine. The imperial column in the table may even contain metric units if required, by setting the imperial unit name to a metric text value and a conversion factor to convert between metric types (eg '1000' could be used to convert metres to millimetres).



Unit Name	Always Metric	Metric Unit	Decimals	Imperial Unit	Decimals	Multiplier	Addition
Length	☐	m	1	ft	1	3.2808	0
Area	☐	m2	1	ft2	1	10.7639	0
Volume	☐	m3	1	ft3	1	35.315	0
Pressure	☐	Pa	1	mln.w.g	1	4.015	0
Pressure Atmos	☐	kPa	1	in Hg	1	0.2953	0
Pressure/unitLength	☐	Pa/m	1	mln.w.g/ft	1	1.2237...	0
Air Density	☐	kg/m3	2	lb/ft3	4	0.06243	0
Velocity	☐	m/s	1	ft/min	1	196.848	0
Quantity	☐	m3/s	1	kft3/min	1	2.1189	0
Mass Flow	☐	kg/s	2	lb/s	2	2.20462	0
Mass	☐	kg	0	lbs	0	2.20462	0
Thrust	☐	N	0	lbf	0	0.2248	0
Contaminant	☐	CO ppm	0	CO ppm	0	1	0
Heat Content	☐	kJ/kg	1	Btu/lb	1	0.43	0
EnergyFlow	☐	kJ/s	1	Btu/hr	0	3412.2	0
HeatOutput	☐	kW	1	Btu/min	0	56.87	0

Figure 5-19 Conversion Table

Decimals **Sets the number of decimal units to display on the screen and in text displays.**

Example A decimal value of three (3) for example will display a value of 123.123 on the graphics display, or in the spreadsheet view.

Caution While the metric unit text name can be changed, the underlying metric value cannot be changed. For this reason, the units must remain the same as preset in Ventsim. For example, the Velocity cannot be changed to km/hr as this would represent a different value scales, and the underlying Ventsim equations are hard corded to use m/s.

Imperial Unit **A text name describing the imperial units.**

Multiplier **The factor used to convert from metric to imperial**. Ventsim Visual™ performs all internal calculation using metric formula and methods, converting displayed data back to imperial (if set in SETTINGS). The factor is used to convert to and from metric to imperial, and will result in errors if not properly set.

Addition **This factor is only used in converting degrees Celsius to degrees Fahrenheit**, and added to the metric value before multiplied in imperial.

Always Metric Forces Ventsim to display the unit in Metric, even if the global Ventsim unit setting is set to Imperial.

5.8.3. Natural Ventilation

Apply natural ventilation pressures to the simulation model, based on the air density in every airway. Natural ventilation is applied based on the differential of density between air at an equivalent elevation outside of the mine and the air within the airway. Therefore, for accurate analysis it is essential that heat first be correctly modelled, and correct outside temperatures added. Unless heat is modelled accurately, it is recommended that Natural Ventilation be turned off.

Caution : Natural Ventilation may result in fluctuating airflow and temperatures between simulations. This is because the natural ventilation effects may cause airflows to change, which in turn changes heat build-up in airways, which again can change the natural ventilation pressure. This endless cycle of change cannot always be resolved, and can lead to variable (normally only small changes) simulation results.

5.8.4. Compressible Flows

Applies compressible flow effects to airflow based on elevation and fan pressures. As a result, airflow volume will change depending on depth and temperature, although mass flow will remain the same (ignoring any moisture content changes to the air). Compressible flow effects become significant over a few hundred metres in depth, and it is recommended for Advanced Version users to turn it on for more accurate simulate results.

5.8.5. Simulation Accuracy

Automatically optimises simulation settings to preset recommended values to achieve faster simulation speeds, or slower but more accurate simulation. The function automatically adjusts the airflow simulation allowable error, the heat simulation temperature margin, the minimum mass flow heat balance setting, and also a number of other simulation factors such as convergence iterations.

All of these settings can also be individually adjusted in the **Settings** section below. Where individual settings vary from the preset recommendations, the simulation accuracy menu will show the setting as 'CUSTOM'.

In most cases, the simulation accuracy will have little effect on the final simulation results, however if maximum accuracy is critical (and the range of assumptions entered into Ventsim is accurate), then the high/slow simulation accuracy setting is recommended.

5.8.6. Settings

An extensive list of settings used by Ventsim Visual™ that control the behaviour, simulation parameters and visual appearance of the program.

Settings are divided into a number of categories, including.

Main Category	Description
Costing	Parameters for ventilation and mining costs required for accurate optimisation of airways and sizes

	Basic program settings to establish default airway sizes, factors and file settings. Settings that control the display of Ventsim graphics and text on the screen. A wide range of factors and settings controlling the performance of different simulation methods in Ventsim. Technical settings controlling the memory requirements in Ventsim, language and the type of units used (eg Metric or Imperial)
General	Airway defaults, file settings and behaviour and license proxy information.
Graphics	Options to modify displayed graphics, including icons, text, sizes and more.
Simulation	Settings to control simulation parameters and behaviours
System Settings	Settings to control computer reserved memory, language and type of units for simulation data.

For further information on settings, go to the settings sections

5.9. Windows Menu

5.9.1. Fit All Fits all display data on the screen.

5.9.2. New Window Adds a new window form to the display. The new window is based initially on the view position and contents of the most recently used open window.

5.9.3. Zoom Out Increase the distance away from the window point of focus. This may be of use if the mouse used does not have a scroll wheel.

5.9.4. Tile Enables windows to automatically arrange to fill the master window form. Note that only docked (windows within the master window) will be affected.

Vertical Tiles all open windows in a vertical direction with equal spacing

Horizontal Tiles all open windows in a horizontal direction with equaly spacing

Tiled Tiles all open windows in square or tiles to fill the master window display.

5.9.5. Auto Arrange Enables windows to automatically dock and arrange the window position within the master window. Windows that are dragged into the master window will be automatically arranged when this function is activated.

Chapter

6

6 THE VIEW TOOLBAR



The VIEW toolbar adjusts the display of items shown on the screen.

6.1.1. Fit All 

Fits available graphics centrally on the screen. If graphics are spread over a huge area, then Ventsim may elect to only show the airways in the most prominent area.

6.1.2. Solid / Wirefr 

Switches the model between wireframe and solid display mode. The wireframe mode is sometimes useful for fine editing of models, particular when airways are large or very close together.

6.1.3. Grid 

Displays or hides the main grid. Note that in a section (vertical) view, the grid automatically changes to show elevations.

6.1.4. Nodes 

Displays or hides nodes (junctions) of airways. This option can also show or hide individual types of icons by clicking the sub option drop down arrow to the right of the button

6.1.5. Icons 

Displays or hides icons on airways.

6.1.6. Arrows 

Display or hides arrows showing airflows.

6.1.7. References

Displays or hides reference graphics (for example DXF graphics or data imported into Ventsim.



6.1.8. **Limit Data** 

Provides options for limiting the amount of data displayed in a model. For complex models, displaying data for every single airway segment this can lead to a cluttered display, and is often unnecessary, particularly if the data shown is largely the same (for example airflows). For other items however (such a heat flows) this large amount of text data can still be useful.



Figure 6-1 Example of limiting text display

Hint : For data which may vary from one end of an airway to another (such as temperature), Ventsim Visual™ will always show the ENTRY data on the airway unless otherwise specified.

Show Limited Only displays text, nodes and/or arrows on airways which specifically have 'Show Data' option set in the EDIT box. For example a loop in a decline consisting of 10 airway segments, will normally show data for every segment. To only show one text data for all the segments, ensure only one airway is set to 'Show Data", and the activated the LIMITED > text display. To force an airway segment to show data, use the EDIT box and click 'Always Show Data'.

Show Unlimited Shows all airway data, regardless of whether the 'Show Data' option is set in the Edit box.

6.1.9. Text



Controls how much text information is displayed on the screen.

Display ALL Displays text information for data values, node names, airway names and error messages.

Hide ALL Hides all text information.

Data, Airways, Nodes, Grid, Log Values Text data, airway names or node names can be individually turned on or off by selecting them from the view menu.

6.1.1. Transparency



By default, all data which is non-active (for example levels or layers which are turned off, data which is outside of the Display Manager, or zero flows if set) are shown as a transparency, with the transparency amount set in the Display Manager.

To specifically hide some items (for example layers which are not visible), but still show transparencies for other items (for example Zero Flows or Coloured Data), data types can be individually set to show transparency or be hidden.

Data : coloured data which is outside of the selection range in the Display Manager, and is selected to be hidden can be made transparent, or removed from the display.

Levels : level elevations outside of the selected ranges can be made transparent or hidden

Layers (primary and secondary) layers that are not selected can be made transparent or hidden.

Zero Flows : Airways carrying no flow can be made transparent or hidden.

6.1.2. Move Toolbar

Moves the toolbar to the left of right of the screen window.



6.1.3. Hide Toolbar



Hides the toolbar from the window. To show the toolbar again, RIGHT CLICK the mouse anywhere on the screen and select 'View Toolbar'

6.1.1. Scale Toolbar



Scales the graphics airway dimensions (except for length) on the screen. For cluttered areas this can be useful to decrease the relative volumes of the airway displays, and make the graphics easier to see.

For very long tunnels, the opposite effect may be desired, and the scale can be increase to 'thicken' the airways and make it more easily viewed.

This tools does not change the true dimensions or characteristics of the airway, therefore simulations will not be affected. It is simply a tools to improve clarity of the 3D models in the screen.

Chapter

7

7 THE ACTION TOOLBAR

The toolbar allows quick access to commonly used Ventsim Visual™ functions.

The toolbar will be slightly different between Ventsim Viewer, Standard and Advanced versions.



7.1. File Input and Output Functions



7.1.1. New File

Creates a new file. The current file will be cleared.

7.1.2. Open File

Open the file dialog to load a new file

7.1.3. Save File

Saves the existing file. If no name has yet been set, a Save File dialog will be displayed.

7.2. Utility Functions



7.2.1. Reset Display

Reset the graphics card if the display becomes corrupted

7.2.2. Undo

Reverses the last action performed in Ventsim Visual

7.2.3. Redo

Cancels the previous Undo, restoring any changes made.

7.2.4. Create New Window

Adds a new window to the display for multi windows viewing of the model. Up to seven (7) windows may be opened.

7.2.5. Show All

Automatically turns on all hidden airways to ensure all airways in the model can be seen.

7.2.6. Snapshot

Takes a static image of the screen in a form which may be saved, copied or remain on the screen for further comparison with other windows. Snapshot are static only and do not change.

7.2.7. Find

**Searches for specific items** within a ventilation model. Pressing the 'searchlight' icon directly, repeats the previous *find* action. Pressing the submenu arrow next to the icon, activates the find submenu as shown below.

Some examples include ;

Name Find the name of an airway name or node. Entering any part of the name will find airways containing the name part.

Number Find an airway with the specified index or unique number

Fans Find airways with operating fans, fans that are turned off, or fans that are performing outside of their rated fan curves.

Fixed Find airways with fixed flows or pressures.

Heat sources Find airways with artificially heat, cooling, diesel or moisture sources.

Contaminants Find airways with contaminant sources set.

Errors Find model errors defined during the previous simulation.

7.2.8. Lock

The lock function controls how the Ventsim cursor attaches to other airways or graphics objects. When editing, this is often desirable to ensure airways attach correctly to other airways or reference graphics while drawing or editing, however it may become problematic particularly in graphically crowded environments.



Individual graphical locks can be turned off using the function below. Note that **ALL LOCKS CAN BE TURNED OFF** temporarily by **pressing the CTRL key** while editing (moving or drawing) airways.

Hint : You may wish to carefully move airway ends or joins, however the move keeps connecting the ends to other nearby (or far away) airways in the same view direction. To disable this behaviour and allow fine control over moves, simply hold the CTRL key down while moving to prevent the airways locking on to other objects.

Lock Target Locks on to the closest airway when adding, moving or copying new airways. Deselecting this option will allow airways and nodes to be finely moved without locking on to a nearby node or airway, or to travel through each other without connecting.

Hint : The lock target can be deselected when arranging airways which are closer together. The lock function when selected will normally lock on to the closest available airway, ensuring a positive join between the airway.

Warning. If the lock target function is turned off, airways may not join into each other precisely (even if they appear close or overlap), resulting in no exit or entry errors. The 'lock target' function should always be selected when you intend to join into other airways or nodes. You can check whether airways truly join into each other by turn on the NODE display.

Lock Transparency Allows transparent (non-active) airways to be locked on to, selected or edited. Transparent airways are normally treated as invisible by the program and by default cannot be selected or changed. Enabling this function will allow the airways to be selected or edited the same as any other airway.

Lock Vertical Forces new airways, or moved or copied airways to be drawn exactly vertically when the vertical movement function is chosen (with the SHIFT key or the RIGHT MOUSE button) while drawing. When this function is not selected, airways can be moved both vertically and parallel to the plane of the viewing screen while being drawn.

Hint: Airway drawn or moved with the Lock Vertical function activated can still be angled. Simply release the SHIFT key or RIGHT mouse button while drawing and moving when you are at the desired elevation and the airway end can continue to be moved horizontally at the new elevation.

Lock On References Locks the mouse cursor onto a referenced graphic surface or wireframe. Ventsim Visual™ will preferentially search for airways when moving the mouse cursor to new locations. If no airway is found, if this option is enabled the program will search for a reference graphic (imported graphics) to lock on to.

Hint: This function is very useful for tracing or moving airways on to imported referenced graphic locations. By using the referenced graphics as a guide, airways can be accurately placed within a model. To force the program to use the referenced graphics only, and not lock on to other airways, turn the Lock Target options OFF.

Check Intercept Checks whether new airways intercept existing airways, and inserts a node if they do. The function works by searching surrounding airways for intersections or crossing paths that are close. Turn this function OFF if you require an airway to cross another without joining (for example an overcast airway) or airways are required to be drawn very close together without being joined.

Hint: When drawing Vent Duct within or close to an airway, ensure this function is turned OFF. The Vent Duct airway may inadvertently join into the adjacent airway, creating shortcuts or duplicate airways.

7.2.9. Perspective View



Sets the viewing system to orthogonal or perspective. Orthogonal removes the effect of perspective, making objects in the distance appear the same size as close objects. This mode

may be of assistance when viewing sections or plan views, where the perspective appearance would otherwise distorted the true scale of objects at different distances. The mode has the disadvantage of a more cluttered and complex display.

Perspective view is more suited to general editing and viewing, where objects in the distance are obscured by perspective scale, creating a less cluttered display.



Figure 7-1 Orthogonal Display



Figure 7-2 Perspective Display

Hint : When performing true PLAN or SECTION views, ensure that ORTHOGONAL mode is chosen to prevent perspective errors in these views. In plan or section view, airways at a different plan or section depth will be

shown at a different scale in perspective view. You can quickly change between views by pressing the 'P' key on the keyboard.

7.2.10. Flow Animation



The animation 'play' button animates the airflow arrows in the model. The airflow animation is performed at true scale speeds, with airflow arrows travelling at the simulated air velocities in the model. Providing the model is designed true to scale, the progress of airflow can be tracked at the same speed as expected airflow in the underground mine when set to X1 speed.



Figure 7-3 Animation Speed Control

The animate toolbar button has a number of sub menu items

X1 **Animate flows in true real time**. Arrows travel at the same scale speed as calculated air velocity.

X5 **Arrows travel at five (5) times** the scale speed of calculated air velocity.

X10 **Arrows travel at ten (10) times** the scale speed of calculated air velocity.

STOP **Stops flow animation.** Flow animation in large model can consume significant processing power and slow model response and rotation. It is recommended flow animation be turned off when not needed on larger models.

Hint: Clicking the main flow animation icon will cycle the airflow speeds through all available ranges.

7.2.11. Stage

Sets the stage number or name of the model. Only airways on the currently selected stage will be shown. The name of the stage can be changed by RIGHT CLICKING the combo box and selecting RENAME STAGE.



For more information on staging, see the Staging Section.

7.3. Editing Functions





7.3.1. View

Places the program in *view* mode

Left Mouse Drag **Draw a window to zoom into part of a model**. The front most airway in the view window will define the point of focus for the zoomed in area. To zoom into area behind other airways, ensure the zoom window does not contain any portion of the front airways.

Left Mouse Single Click **Centre the view on the airway.** Centres the view on an airway so the screen can be rotated around the point clicked.

Left Mouse Double Click **Edit the airway.** Left clicking the mouse on top of an airway will show the Edit Box for that airway.

Middle Mouse Drag **Press and hold to pan** the screen horizontal around the current Edit Plane

Click to centre the Edit Plane and rotation point about a specific airway or point on the Edit Plane.

Right Mouse Click IN ALL MODES, right mouse click will rotate the model graphics about the point of focus. Hold and move the mouse vertically to tilt the model. Hold and move the mouse horizontally to spin the model.

7.3.2. Add



Places the program into draw (add) mode to allow creation of new airways or measure between airways. The function has several sub-functions available by clicking the small arrow at the right.

In normal (free draw) mode, airways that are constructed from other airways will adopt the attributes of the joined airway (such as size and wall friction factors types).

Airways that are NOT constructed starting from other airways will adopt the default set in the *Settings* menu.

Left Mouse Click **Edit the airway.** Left clicking the mouse on top of an airway will show the Edit Box for that airway.

Left Mouse Drag Constructs a new airway from where the mouse is initially pressed, to the point where the mouse button is released.

To manually control the coordinates of the airway being constructed, select the sub-menu functions of the add button as shown below.



Figure 7-4 Manual airway drawing options

Draw Single Allows the mouse to draw both ends of a single airway. Airways can be drawn vertically by hold the SHIFT key down.

Draw Continuous Allows the mouse to continuously draw joined airways until either the ESCAPE button is pressed, or the airway joins into another airway. Airways can be drawn vertically by hold the SHIFT key down.

Draw Gradient Allows the mouse to continuously draw joined airways at a predefined gradient until either the ESCAPE button is pressed, or the airway joins into another airway. The defined gradient is request when activating the function and can be entered as a percentage (eg 10%), degrees (eg 12.5) or a ratio of horizontal to vertical distance (eg 1:10).

Draw Coordinates Shows the coordinate entry box after the airway is drawn to allow manual entry of airway end coordinates.

Construct Duct a tool for quickly building ventilation ducting which follows existing airways. Select the airways you wish to construct ducting along with the SELECT button.



Figure 7-5 The Vent Duct Builder Dialog Box

See the Auxiliary Fan and Ducts section for further information.

Construct Ramp A tool for quickly building spiral ramps. After selecting the tool, draw the initial direction of the ramp, and the ramp builder toolbox will show, allowing gradients, ramp bends, straights and heights to be established. A ramp can be previewed to try different factors before clicking BUILD to commit the ramp design to the model.



Figure 7-6: Ramp Build Function

Convert Centreline Allows the selective direct conversion of DXF reference lines to airways. If imported DXF centrelines are shown as a reference layer on screen (instead of automatically being converted to airways on import), then this function can be used to select or fence the reference lines that are to be converted to airways.

> Note that each reference line can only be selected once, as the program will not duplicate multiple selected lines.

Convert Any If centre lines are not available, this is an experimental feature which agglomerates groups of reference graphics to try and establish an airway path which could be constructed. Examples may include survey string data showing wall, floors and backs, or 3D solids of actual mine development or shafts. Note that the results from this function are very approximate and will likely require significant manipulation with the MOVE and DELETE tool function after being done, to create a workable model.

Measure Allows the mouse to measure distances between two points. Click on the start point of where the measurement will start, and drag the mouse to the end point. The measurement will display in the bottom left Status Bar area of the screen.

7.3.3. Edit

Place the program into Edit mode

Left Mouse Click **Edit the airway.** Left clicking the mouse on top of an airway will show the Edit Box for that airway.

Left Mouse Drag **Selects the airways within the fence box being drawn**. Selected airways can then be edited by clicking on any of the selected airways.

Hint : Selecting Multiple airways permits attributes for a large number of airways to be changed simultaneously. This can greatly speed up creating a model.

7.3.4. Select

Selects a group of airways. Selected airways are considered as a group by a number of other Ventsim Visual™ functions including *Edit*, *Delete*, *Move*, *Copy and Filter*. These options will apply changes to all selected airways simultaneously.

Left Mouse Click Selects or de-selects the airway under the current mouse cursor.

Left Mouse Drag Fences a number of airways for multiple selection.

<Escape> De-selects all currently selected airways

<SHIFT> Deselects fenced airways

<CTRL> Individually selects or deselects airways, ignoring the group setting or other group selection options.

7.3.5. Multi Select Options



Figure 7-7 Multi Selection Options

Permits groups of airway to be automatically selected, based on either an initial airway selection, or subsequent selections with the mouse. The selection mode will remain set, until it is reverted back to the single airway select option, or the <escape> key is pressed twice.

For example, to select all airways of the same size, either select a single initial airway with the select button, and then select the mult-select option "Same Size". OR select the "Same Size" option first, and then click on an airway. All airways of the same size as the initial selection will be selected. Once selected, the airways can be edited, deleted, move etc.

7.3.6. Delete

Deletes an airway or airways from a model

Left Mouse Click **Delete the airway.** Left clicking the mouse on top of an airway will delete the airway beneath the mouse cursor. If multiple airways have been selected, it will delete all selected airways.

Left Mouse Drag **Selects the airways within the fence box being drawn**. Selected airways can then be deleted by clicking on any of the selected airways.

7.3.7. Deletion Options



Figure 7-8 Deletion options

Presents a number of deletion options.

Delete airways outside fence will delete all airways not inside the fenced area. This can be useful to remove errant airways which may be located a long way away from the main model.

Delete references removes DXF graphics within the fence area. Delete references outside fence remove DXF graphics not within the fenced area.

7.3.8. Block

Blocks or unblocks an airway with the highest resistance available (as defined in the Settings menu). This will restrict nearly all airflow through the airway.

Warning: Ensure that fans or fixed flows are not present in blocked airways, or in airways leading to or from blocked airways. This will create a simulation error, as airflow will be unable to travel through the blocked airway without unreasonable pressure or heat build-up.



Figure 7-9 An airway stopping

7.3.9. Move

Moves the selected airway, airways, airway ends or icons to a new location by clicking and dragging the LEFT MOUSE BUTTON. Unless the SHIFT key is held, the move will always be done at the same horizontal elevation. A 'true vertical' line is displayed showing where the move point is in relation to other airways.

- To move an airway end (and all other attached airway ends), *click* on of close to the end node of an airway
- To move an airway end away from other airways, *click* slightly back from the airway end node. The airway should 'break' away from other connected airways.
- To move an entire airway (both ends), first select the airway with the select button, or fence the airway to be moved, and then drag the selected airway(s) to the new location.
- Multiple airways can be moved by first *selecting* the airways and the dragging any one of the selected airways to the new location.
- To move an icon (such as a fan, heat source or resistance) along an airway, simply grab the icon with the left mouse button and drag the icon along the airway to the new location. Icons can also be dragged to other airways.

Left Mouse Click Opens the coordinate entry dialog box to allow the move to be specified as a coordinate or offset from the current position.

Left Mouse Drag + Shift Drags the airway or node to a new location in the vertical plane, adjacent to the viewing screen. The Edit Plane is moved with the dragged airway to indicate where the elevation is in relation to other airways.

7.3.10. Copy



Copies the selected airway, airways or icons to a different location. The original airways or icons remain in place.

Left Mouse Click Opens the coordinate entry dialog box to allow the copy to be specified as a coordinate or offset from the current position.

Left Mouse Drag Drags the copied airways or icons to a new location. If the ICON is being copied, it will show on airways under the mouse cursor. When moving airways, a 'true vertical' line is displayed showing where the move point is in relation to other airways.

To copy an icon (such as a fan, heat source or resistance) along an airway, simply grab the icon with the left mouse button and drag the icon to another airway.

Left Mouse Drag + Shift Drags the copied airways to a new location in the vertical plane, adjacent to the viewing screen. The Edit Plane is moved with the dragged airway(s) to indicate where the elevation is in relation to other airways.

7.3.11. Reverse



Reverses the direction of the selected airway. The direction of the airway, and the airflow within the airway is reversed. Fan, fixed flows and pressures are also reversed.

7.3.12. Insert Node



Inserts a node or junction within an existing airway. The airway is split into two airways as a result. This node can then be moved or joined into by other airways.

Hint : Drawing an airway into the middle of another airway will automatically create a new node or junction into the joined airway.

7.3.13. Contaminant



Places a contaminant type within an airway. A number of different contaminant types can be chosen.

7.3.14. Message Boxes



Message boxes allow text and messages to be place in the display, independent of airways. The message boxes can be coloured and sized individually, and can be locked at a specific screen location, or positioned in 3D coordinates so that it moves and rotates with the rest of the model.



To create a text message box, select the toolbar button and click on the location on the screen where the box will be located. The message box dialog box will show allows colour, sizes and position to be adjusted. Message boxes can also be assigned to belong to one or more stages.

7.3.1. Reverse



Reverses the direction of the selected airway. The direction of the airway, and the airflow within the airway is reversed. Fan, fixed flows and pressures are also reversed.

Reverses the direction of the selected airway. The direction of the airway, and the airflow within the airway is reversed. Fan, fixed flows and pressures are also reversed.



Figure 7-10 Contaminant placing options

7.3.2. Contaminant

Places a standard contaminant value (defined in the Settings > Contaminants) in an airway. Standard contaminants are considered unit less, however different units can be specified in the settings. All downstream simulation values will be related to the initial concentration of a contaminant in the airway's airflow. Downstream contaminants are diluted proportionally to this value. See the contaminant section for further detail.

Report Smoke

Used in the contaminant source tracking routines, this will place a smoke report within an airway. After a contaminant tracking simulation, all airways below this point will be considered as contaminated. All airways upstream from this point will be considered as a potential source of the contamination.

Report Fresh

Again, used in the contaminant source tracking routines, this will place a fresh air report within an airway. After a contaminant tracking finding simulation, all airways above this point will be considered as fresh air.

Left Mouse Click Places or removes one of the above types of contaminants.

7.3.3. Monitor



Records ventilation conditions at this airway location during dynamic simulation.

See the Dynamic Simulation section for more detail.

7.3.4. Filter



Applies a filter to selected airways to simplify or bind together airways. See the TOOLS > FILTER section for more detail, or more control is required on how the filtering is applied.

7.4. Simulation Functions

The simulation functions control the major simulation capabilities of Ventsim Visual. The buttons assumes that a valid model has been created and all required data has been entered in preparation for simulation.



7.4.1. Airflow Simulation



Performs an airflow simulation on the model data.

For more information, see Airflow Simulation

7.4.2. Heat Simulation [ADVANCED]



Performs a thermodynamic simulation on the model data

For more information, see Thermodynamic Simulation

7.4.3. Contaminant Simulation



Performs a steady state contaminant simulation on the model data. Contaminant sources or flag must be present in the model to work. Three different types of contaminant simulations are available from the sub menu pull down (arrow to the right of the icon). See the Contaminant Menu bar for more information.



Figure 7-11 Contaminant Options

Contaminant **Spreads contaminant sources through the model as a never ending continuous stream (steady state)**. The display and colour legend automatically switch to a contaminated concentration display, showing the simulated spread and contamination of the contaminants. See Contaminant Spread from the menu bar section for further information.

Hint : A number of additional contaminant data types are available including the 'spread time' of data.

Diesel DPM [Advanced] **Performs a diesel particulate matter spread simulation** based on diesel heat sources in a mine model. The result is displayed as a concentration per unit volume of airflow. The diesel heat sources are defined under the thermodynamic Heat Tab from the Edit Box form. Diesel heat sources are converted to a diesel particulate emission rate per unit of engine power, based on either a default setting, a preset heat source setting, or entered directly in the Edit Box or Preset form. Diesel emissions are spread throughout the model using a steady state, complete mixing algorithm that assumes perfect mixing and no settling or deposition of particles. Diesel sources are assumed cumulative, and downstream sources or recirculation may increase concentration higher that the initial source.

The simulated air concentrations are given in the same emission type as specified in the exhaust emissions. For example if Total Carbon (TC) matter emission rate is given for a diesel engine (which includes elemental and organic carbon), then the air concentration rates will also be based on Total Carbon. Most air quality standards will quote either an Elemental Carbon exposure limit or a Total Carbon exposure limit.

To convert to an Elemental or Total Carbon concentration, a factor will need to be applied either to the original emission rate, or to the simulated air concentrations.

See DPM emissions for further information.

Gas Performs a steady state gas simulation based on gas settings edited into an airway. See the gas simulation section for further information.

Reverse Contaminant **Performs a reverse contaminant simulation**, where the sources of airflow through the contaminant point are tracked back to the surface. The contaminant markers are used to define the point(s) at which the simulation searches upstream for paths. The display and colour legend automatically switch to a source concentration display, which shows the relative amounts (%) of airflow along different airway paths which eventually flow through the contaminant marker. See Contaminant Source from the menu bar section for further information.

Find Source **Performs a contaminant search simulation** which tracks the likely paths of fresh and contaminated air. See Location Tool from the menu bar section for further information. Recirculation Simulation [ADVANCED]

7.4.4. Recirculation [ADVANCED]

 **Performs a recirculation search simulation** which attempts to find any paths and portions of airflow that recirculate in the model. Any recirculation paths are highlighted after simulation and the portion of each airflow recirculating through each airway will be shown on the screen as colour and text. For further information, see Recirculation Simulation under the Menu Bar Chapter.

7.4.5. Financial Simulation [ADVANCED]

 **Performs a financial and airflow simulation** for multiple airway sizes, to assist in determining the optimum airway size for mine ventilation flows. For further information, see Financial Simulation under the Menu Bar Chapter.

Chapter

8

8 THE DATA TOOLBAR



The DATA TOOLBAR control the colours and text displayed on the screen.

8.1.1. Data Category

Limits the data types shown in the adjacent pull down menu, to the category type specified.



Figure 8-1 Select a data category, followed by a data type

Airflow Show data types such as air flow volume, velocity, mass flow and density

Pressure Shows pressure related data such as relative to surface, barometric and friction loss.

Attributes Shows airway resistances, friction factors and shock loss numbers

Energy Shows power and cost calculations for airflow, fan and fix inputs

Heat Shows heat related data, such a temperatures, internal heat content, humidity.

Identifiers Show airway specific indentifying traits, such as index or unique numbers and primary and secondary layers numbers

Contaminants Shows airway contaminant factors, source values, simulated values, spread times and diesel particulate levels.

Rock Show airway rock conditions, such as wetness fractions, specific heat and other rock parameters.

Measured Not currently used.

8.1.2. Data Type

Displays screen data related to the Data Category specified in the left hand pull down menu. Each data category will have a unique selection of data types that are made available when the category is changed.

Warning: some data types (such a pressures) may not be correctly set until after a successfully simulation. While Ventsim Visual™ saves previous simulated values in a file, these values may not be valid if further changes and modifications have been made to the model. Another simulation may be

8.1.3. Dynamic Text Size

Dynamically rescale the text on the screen so that it can be easily adjusted for clarity or presentation. The  button will toggle between zoom scaled text (which grows larger or smaller the closer to the object graphics) or constant size text (which remains the same size regardless of zoom level)

8.1.4. Favourites

Shows the Favourites Manager. Favourites are names for groups of data that can be simultaneously displayed on the screen. For example, airflow volume, velocity and massflow could be displayed on each airway from a favourite. If favourites are used for colours, only the first favourites item in the list will be used.

To create favourites, press the  button, and add, remove or edit the favourites in the left hand column. The favourite name, and the type of data under each selected favourite can be defined in the right handle panel. The "Text" and "Colour" options define whether the favourite will appear in the text and / or colour selection boxes.



Favourites can be displayed on the screen by selecting the favourite options from the drop down list.





Because the display can become cluttered with too much data, favourites can also be displayed only on individual airways with a text box panel. To show a selected favourite on an individual airway, EDIT the airway, switch to the INFORMATION panel, and select the desired favourite from the list.

8.1.1. Scaling

Dynamically resizes text, data and graphics on the screen. 

Each sliding control quickly rescales different items on the screen. For example the data text can be made larger or smaller to improve display clarity. Use the mouse to move the slider up and down. For finer control of sizing, click the slider once then use the mouse scroll wheel to move the slider up and down.

8.1.2. Display Manager

Shows the Display Manager dialog box, which floats on top of the Ventsim Visual™ windows, and can be kept open at all times if desired.

The Display Manager control provides options as to what graphics details and colours to display. The display manager contain five (5) tabs which change the colour display between data types, and air, layer and elevation types.

The Display manager can be displayed or hidden by clicking this icon 

The Manager controls many of Ventsim Visual™ advanced display functions. At the core of the manager is the ability to display any type of ventilation data as a colour range, including the ability to hide or make transparent data outside of a set range.



Ranged **Data**. The data which creates the colour legend is automatically 'ranged' to fit the model data values. It may occasionally require resetting if new or changed values are present in a model (after a simulation for example), or the values do not divide the colours as you would like. The data can be re-ranged by either manual typing in new values, or allowing Ventsim to automatically choose new values by selecting the median or linear range **RESET buttons.**

Transparency level slider, for data outside of data range values

Data range of airway data, equally divided by airway numbers. To manually change, simply enter a new value in the box.

Upper and lower range limiters

Hide or make transparent data outside of range. At full

OPTIONS (Right Click Mouse Button)

Reverse Spectrum **Reverses the colour range** direction

Restore Colours **Restores the colours** to the default Ventsim Visual™ palette.

Auto Range **Restores the range** to the full spectrum of available airway data values.

Hint: The Display Manager will initially default to automatically range and set colours for the displayed data. If the range values are manually adjusted, or the colours are changed, the Display Manager will no longer automatically range and adjust colours for the data displayed. To restore or recalculate the range and colours, simply click the 'Auto Range' or 'Restore Colours' buttons.

Hint: Ventsim Visual™ will store a custom colour and data value range for each type of data type. This setting is saved with the Ventsim Visual™ file.

Levels  Selects which levels (elevation ranges) are displayed on screen. To select or de-select **all** levels, choose the check box adjacent to the Level Name.

To change a level name, right mouse click on the existing level name and type in the new name.

Air Types  Selects and colours the air types to be shown on screen. Air types are designed to allow the user to colour airways according to air quality or purposed (for example fresh or exhaust air). Air Types behave in much the same way as primary or secondary layers.

To change an air type name, right mouse click on the existing air type name and type in the new name.

Primary / Secondary Layers  **Selects which primary or secondary layers are displayed on screen**. Layers are a way to show selected airways (such as a decline system or a shaft system) on screen while hiding other airways. Primary and Secondary layers can be set to individual airways in the Edit Box

To change a Layer name, right mouse click on the name and type in the new name. Names can also be changed directly from the airway Edit Box, or in the Preset Box available from the Settings menu.

Chapter

9

9 THE EDIT BOX

The edit box is a powerful tool required to manipulate and display airway attributes. In summary, the Edit Box can perform the following functions



- Set airway attributes for airflows and pressure simulation.
- Set airway attributes for heat simulation.
- Set contaminant, radon and gas attributes for airways
- Allow custom comments and information (such as survey results) to be set for each airway
- Select and display working fan duty curves
- Display airway information derived from simulation
- Enter a PQ (Pressure Quantity Survey) to automatically calculate and apply resistance.

The Edit Box can be activated by clicking on an airway while in the *View*, *Edit* or *Add* modes selected from the main toolbar. The Edit Box is divided into a number of TABS to allow quick access to each function.



Figure 9-1 Edit Box Tabs

9.1. Edit Box – FILE Menu

9.1.1. File > SNAPSHOT Creates a picture of the current airway information. This picture can be saved (by right clicking the form) or used to compare results with an updated simulation.

9.2. Edit Box – EDIT Menu

9.2.1. Select Airways Allows the selection of multiple airways based on a selection criteria. Multiple selected airways

can be edited simultaneously from the Edit Box. The number of airways selected will be displayed in the form Caption Box (at the top of the form).

Select Joined Airways Selects all airways directly joined to the initial airway (for example a decline loop). The selection will stop when the airways reach a junction.

Select Same Primary Layer Selects all airways with the same primary layer

Select Same Secondary Layer Selects all airways with the same secondary layer

Select Same Size Selects all airways of the same size

Select Same Resistance Type Selects all airways with the same resistance type (eg bulkhead). This may be useful for group changing and testing different regulator types on model performance.

Select Same Friction Factor Type Selects all airways with the same friction type (eg 'rough blasted' walls).

Select Same Shock Type Selects all airways with the same shock type.

Select Same Fan Selects all airways with the same fan. Note that while fan types cannot be changed in multiple headings, however fans can be turned on or off over multiple headings.

Select Same Air Type Selects all airways with the same air type (for example 'exhaust')

Select Same Heat Type Selects all airways with the same heat type (eg trucks). This may be useful for example to rapidly change all similar heat sources in a model to a different heat source (for example change all Truck Models from ABC500's to ABC750's)

Select Loose Ends Selects all airways with one end that are not connected to others, and which are not flagged as connected to surface or marked as 'allow closed end'. This function is useful for quickly editing new model creations (from a DXF file for example) which may have lots of dead ends and development stubs (eg truck bays) that need to be flagged or deleted to prevent no entry / exit errors in the simulation. Note that this function should only be used when all valid connections have been accounted for.

Select Both Loose Ends Similar to the loose end selection, but only selected airways with no connection on both sides.

Select Same Contaminant Type Select airways with the same sourcing contaminant type. This selection was included to allow rapid definition of different air types in a mine by using the contaminant finding function. For example is a 'smoke' sourcing pin was placed, all airways downstream will be turned 'red' for contaminated air. If a 'fresh air' sourcing pin is placed, all airways upstream will be turned 'blue' for fresh air. Once all entries and exhaust pathways to the mine are marked, similar

airways can be selected and the air type for those airways could be changed to 'Fresh' or 'Exhaust or 'Intermediate' etc.

9.3. Edit Box – TOOLS Menu

9.3.1. Tools – Set Fix Flow Resistance / Orifice

Where a fixed flow has been used to retard or resist normal airflow, the resulting resistance can be used instead of the fixed flow. Select this option to convert the fixed flow into a custom resistance or an orifice size that will give a similar flow based on current model pressures. If multiple airways are selected, then all selected fixed flows will be converted to resistances or orifices. The fixed flow is removed once this action is done.

9.3.2. Pressure Survey Tools

Pressure surveys of airways or shafts allow more accurate resistances to be calculated and used in Ventsim. These options provide tools to convert differential or barometric pressure survey information into resistances or friction factors. Select the airways along which the pressure survey was performed and select the menu option. A dialog form will show which allows the survey information to be entered and the resistance or friction factor to be calculated. Select the desired resistance method (fixed resistance, linear resistance or friction factor) and select OK to update the model airways.

Note that if Friction Factor is chosen, then an accurate survey of the airway dimensions is required if the factor is to be used elsewhere.

9.3.3. Apply Gradient Slope

Applies a gradient or slope to the selected airways. The gradient will start from the end selected first in the EDIT box. This tool assist in creating ramps between levels, particularly if survey data has been entered in 2D and requires to be converted into 3D.

9.3.4. Distribute Rock Age

Distributes rock opening ages evenly along a series of connected airway segments. The rock age distribution will start at the end selected first in the EDIT box. Ensure that the airways selected do not have split airways into other areas otherwise the function will fail to distribute the ages properly.

9.3.5. Convert Fixed Resistance to Friction Factors

Convert any custom resistance in the edited airways to friction factors, and resets the resistance to AUTO.

9.3.6. Convert Linear Resistance to Friction Factors

Converts any custom linear resistance in the edited airways to friction factors and reset the resistance to AUTO.

9.4. Airway Tab

Changes made to the airways in the Edit Box are highlighted in BLUE. The changes are applied to the airway when;

- *Apply is pressed.* – the Edit Box form will remain open
- *OK is pressed* – the Edit Box form will then be close
-

If another airway is selected, the changes will be applied, and the next airway data will be displayed.

Multiple airways can be selected and simultaneously edited from the Edit Box. Note that not all Edit Functions are available for multiple editing and some function may be hidden. To utilise multiple airway editing, simply *Select* the required airways before the Edit Box is opened. Only attributes that are *changed* (and therefore highlighted in BLUE) are applied to the selected airway(s)

The Airway Tab Page defines most of the airway attributes associated with airflow and pressure simulation, as well as basic airway information such as names and airway coordinates.



Figure 9-2 Airway Edit Box Form

9.4.1. Airway Names, Coordinates and Stages

Sets the airway and node names, data box display and airway stages. To set new names or coordinates, simply type the information into the relevant text boxes. Names are optional and are not required for the simulation.

The data box display shows a selection of simulation data in a special text box that floats above the airway. Data boxes are an alternative to highlight special data on a selected number of airways. The data types display in the data box can be defined by pressing the heart symbol to create a 'favourites' group of data.

The stages which the airways belong to can be selected from the shaded squares. See the Staging section for more information on this.



Figure 9-3 Set airway names, coordinates and stages.

9.4.2. Airway Size

Sets the physical size and shape characteristics of the airway



Figure 9-4 Set airway physical characteristics

Type Allows a preset type of airway to be specified, which will automatically set the airway profile, dimensions and friction factors. Pressing the TYPE 'T' button will open the PRESET form where airway preset types can be entered or modified. If an airway type is modified, all airways set to that type will be automatically modified during subsequent simulations.

Shape **Sets the profile of the airway**. If the shape chosen is 'irregular', the Width box will be changed to Perimeter, the Height box will be hidden and the Area box will become editable.



Square

Round

Arched – an airway with arched upper corners.

Shanty – an airway with one side higher than the other.

Irregular – an undefined shape characterised by area and perimeter

- If the shape chosen is 'round; the Width input box will be changed to Diameter.
- If the shape chosen is 'irregular' the Width input will be changed to Perimeter and the Area box will allow data entry.
- Further profiles can be created in the Presets form.



- Recommends an airway size based on the current simulated or fixed flow. Note that this is a recommendation based exclusively on the current flow, airway attributes and cost data entered into the Settings. If these values have not been established yet, do not use this feature to estimate the most efficient airway size. Also note that if the airway size is accepted, this may actually change simulation results, and other adjustments elsewhere in the model to fans or regulators may be required to return the airway to original flow rates.

  Warning – do not use this feature unless the required airflow rate has currently been simulated or fixed in the airway, and the default COST settings have been set in the Settings > Settings > Costing.



Removes wall contacts from the airflow to simulate open airways or stope panels that are 'joined' to each other, but do not have (for example) side wall connecting the airways. The air friction and heat transfer factors on these excluded walls are removed from the simulation. Select the check box representing the walls that do not exist.

Number of Airways The number of parallel airways defined by the single airway. This allows multiple airways in parallel to be represented and simulated by a single displayed airway.

Width **The width of the airway**

Height **The height of the airway**. For vertical airways, the width and height are interchangeable. For 'Arched' or 'Shanty' airways, the height is assumed to be at the centre of an airway.

Area **The calculated area of the airway**, derived from the width, height and shape. If the shape chosen is 'irregular' then the 'Area' box can be edited, otherwise it will remain as Read Only and display the calculated size based on the width, height and shape.

Obstruction Assumes a **continuous area obstruction** along the airway (for example a duct, services or compartment) and removes this value from the available area of the airway. Note that this should not generally be used for short fixed objects (such as a vehicle); in this case the orifice function may provide a better simulation result.

Backfill Assumes a continuous % obstruction of backfill along the length of the airway and removes this value from the available area of the airway. In addition, it removes the area of covered airway that transmits heat into the airway, to represent the insulating effects in heat transfer calculations for backfilled stopes.

Length **The calculated length of the airway**. The calculated length is automatically derived from the airway coordinates. To change the length, click on the Check Box, and type in the new length. This may be required if the model is drawn as schematic if an airway is moved to allow easier viewing, but the true original airway length still needs to simulated in the model.

Quantity **The calculated flow in the airway**. This number can be modified to provide a resistance based on the frictional pressure loss entered below. The calculated resistance will be entered in the resistance box as a custom resistance. The airway WILL NOT be fixed to this flow rate and

will automatically recalculate next after the next simulation. Use the Edit Box > FAN Tab > Fix Flow function if this is required.

Friction P **The calculated pressure drop in the airway**. This number can be modified and will be used to calculate a resistance for the airway if an equivalent flow is entered in the above box.

Velocity **The calculated velocity of air in the airway**. This is the average velocity of air across the airway area, and is 'Read Only' and cannot be changed.

9.4.3. Airway Options

Controls various attributes relating to the airway behaviour and identification within a model



Figure 9-5 Further Airway Options

Surface Connects the airway to the surface, allowing it to freely exhaust and intake air from the surface atmosphere. The airway end which is not connected to any other airway is assumed to be the end connected to the surface. If both airway ends are connected, this item is ignored by the simulation. The exit to the surface is assumed to be at the elevation of the airway end. Barometric pressures at this point will be adjusted for any difference in height between the airway elevation and the defined surface elevation in the settings.

Close End Allows Ventsim Visual™ to assume the airway is a 'dead end' without connecting to other airways or to the surface. Examples of this may include a dead end, blind developing heading or undeveloped heading. The simulation process will assume this path is blocked, and allow no airflow along the airway. If this settings is not used, a simulation will report a 'no entry' or 'no exit' error.

Group Groups any selected airways into a single selectable group that can be selected with a single Select click. Individual airways can still be individually edited by clicking on them directly with the EDIT button instead of using SELECT first, or by holding the <CTRL> key down while selecting. Grouped airways are a convenient way to collect airway systems together (for example shafts or decline sections), so they are easier to select and edit simultaneously. It has no effect on simulation.

Exclude Excludes the airway from the simulation process. Any errors or problems with the airways are ignored during simulation and no flow is allowed through the excluded airways. Any non-excluded airway which joins with an excluded airway will be assumed to be blocked. This function is handy for excluding sections of a model design which have yet to be mined, or perhaps removing old sealed of filled sections of a mine which no longer carry ventilation. Excluding airways will speed up simulation for the remaining airways.

Fix Direction Prevents Ventsim Visual™ from changing the airway's airflow direction during simulation. An error is displayed after simulation if an attempt to reverse is made. This function is useful to ensure critical airflow locations underground are not arbitrarily changed without first warning the user.

Show Data Always shows text data for this airway when the LIMIT view option is set.

Gradient Specifies the gradient of the airway as a percentage. For example a gradient of 10% results in an airway increasing 1m in height for every 10m in horizontal length. If a group of selected airways needs to be change simultaneously, use the TOOL > APPLY GRADIENT option in the

EDIT form menu. Note that the first selected airway clicked with the EDIT button will be the airway from which the gradient is applied.

Diffuser **Specifies an evasé or diffuser for the airway outlet.** This function will only be simulated on a surface connected airway, and will only have an influence on an exhaust airway. An evasé or diffuser reduces exit velocity pressure losses to the mine, lowering overall total system pressure requirements to produce the same airflow. Where fans are present, an improvement in the performance of the fan will be noted with increasing evasé sizes. Note that the simulated evasé effect is theoretical only, and will ultimately depend on the efficiency and placement of the design to produce the simulated effects in a real mine. As with all ventilation structures, there will be some efficiency and shock loss factors that will reduce performance from the theoretical calculation. These should be considered when observing the effects of simulated evasé.

Ventsim simulation assumes diffusers are 100% efficient, however typically diffusers may only be 70-75% efficient. Therefore it is recommended simulating a diffuser at only 75% of the design area of the actual diffuser size to account for this inefficiency.

Note that only the Total Pressure simulation method calculates lost velocity pressures. This additional lost velocity pressure is added to the Fan Total Pressure requirements for the mine. If Static or Mixed pressure simulation is used (which will happen if fans with only Static Pressure curves are used), then any calculated primary fixed or fan pressures will exclude velocity pressure and therefore be more representative of Fan Static pressures only.

Orifice Places a sudden restriction in the airway, with an open hole equivalent to the specified area. The resulting shock loss and resistance of the orifice will be added to the resistance of the airway. Orifice settings are normally used to simulate the effect of regulators, holes in wall, partly open doors or other sudden restrictions which may occur in underground headings.

It can also be used to simulate the effect of large equipment blocking an airway by entering the 'remaining' area around the equipment as the 'orifice' size.

Air Type Sets the type of air the airway is carrying, for example fresh, exhaust, mixed etc. The air type can be shown as a separate colour on screen by selecting ***air type*** under the ***favourites*** menu on the Display Manager.



Figure 9-6 Example of use of fresh / exhaust airway type colouring

Hint : Most mines have designated fresh and exhaust airways, and may also have airways which may be designated as potentially either, depending on production activities. Ventsim Classic 3.9 defaulted to a blue / red / green colour scheme for these three types of airways. Ventsim Visual™ uses these three air types, but also has up to potentially 25 other types (and colours) which can be specified under the Edit Box. Other air types could be set by the user as 'emergency access', flooded', 'vent duct' etc.

Primary Layer **Sets the primary layer type of the airway**. Once set, primary layers can be independently displayed using the Display Manager. The name of the primary layer can be changed by clicking the ***Primary Layer*** button, and entering a new name or colour in the Preset spreadsheet.

Secondary Layer **Sets the secondary layer type of the airway**. Once set, secondary layers can be independently displayed using the Display Manager. The name of the secondary layer can be changed by clicking the ***Secondary Layer*** button, and entering a new name or colour in the Preset spreadsheet.

9.4.4. Airway Attributes

Sets resistance, friction factors and shock loss factors for an airway.

The sort order of the attribute items in the list boxes can be specified in the Preset Spreadsheet



Figure 9-7 Resistance, Friction and Shock Factors

Resistance **Sets the resistance for an airway**. Resistance can be set to automatic, preset or fixed.

'Auto'matic allows Ventsim Visual™ to calculate the resistance automatically from the airways size, length and wall friction factors.

'Preset values', can be selected from the resistance list. Preset values are added to the underlying automatic resistance value. To create a new Preset Resistance or change an existing one, select the Resistance Button to enter the Preset Spreadsheet and enter or change any existing resistance values from the Preset Spreadsheet. When the Preset Spreadsheet is closed, the new preset resistances will be available in the pull down menu for all airways.

'Custom' values are fixed resistances that override the automatic resistance calculation, and therefore ignore any pre-existing airway shape, size or friction factor. Values can be type directly in to the resistance value text box.

One way Resistances Resistances are normally set to apply equal resistance to airflow in either direction, however resistances can be specified to apply a different resistance when airflow is reversed. To enable this function, create a Preset Resistance and enter both a primary and a secondary 'reversing' resistance in the preset spreadsheet. This will force the simulation to consider an alternative resistance if the airflow is reversed from the direction that the resistance was originally placed. If a reversing resistance is not required, simply leave the reversing resistance value at '0'

To swap the direction of a one-way resistance, use the "REVERSE" button on the ICON toolbar. One-way resistance that currently are applying the secondary reversing resistance will be shown in a RED colour on the screen. Example of use for this function include resistances such as hanging flaps or swinging doors which may either seal better, or alternatively swing open if airflow is reversed.

Resistance Density Adjustment Preset Resistances are assumed to be entered at a sea-level air density, therefore can change according to the air density at which they are applied. Ventsim Visual™ will internally automatically adjust resistances during simulation according to the local air density. This behaviour can be overridden from the global settings, or with the resistance Check Box on the edit form.

- If this box *is not* checked, the resistance entered is assumed to be derived from a standard air density as specified in the Settings Menu for Simulation – Air (which is normally 1.2kg/m3 unless set otherwise). In most cases, resistances are likely to have been derived from preset values and standard air densities, and this option should remain unchecked.
- If the box *is* checked, Ventsim Visual™ will assume an adjustment has already been included and will not attempt to adjust the resistance from density changes further. Examples of this may be if the resistance has been measured at a specific site underground at a density similar to that simulated by the program.
-

Friction F Sets the friction factor for the airway. Friction factors describe the unevenness of wall profiles, which produces airflow turbulence and hence pressure loss. The value can either be entered directly in the Friction F text box, or can be selected from the pull down menu. As with resistance, new preset values can be entered by clicking the Friction button, and entering new preset values in the Preset Spreadsheet. The new Preset Friction Factors will be available for all airways.

Friction F Density Adjustment

Similar to the resistance density adjustment, friction factors are also normally standardised to sea-level air density, and will be adjusted for different air densities. Ventsim Visual™ will internally adjust friction factors during simulation according to the local air density. If this box *is not* checked, the friction factor entered is assumed to be derived from a standard air density as specified in the Settings Menu for Simulation – Air (which is normally 1.2kg/m3 unless set otherwise). In most cases, friction factors are likely to have been derived from preset values at standard air densities, and this option should remain unchecked.

If the box *is* checked, Ventsim Visual™ will assume an adjustment has already been included and will not attempt to adjust the friction factor further. Examples of this may be if the friction has been measured along a specific airway underground at a density similar to that simulated by the program.

Shock Loss Factors

Sets a shock loss factor for the airway. Shock losses can be set as an equivalent length, or as a shock loss factor (X). The method used is defined in the Settings.

Only one method can be used for all airways. Ensure shock values are consistent with the method chosen in the settings throughout the model.

Shock values can be **manually** entered in the text box, set to a ***Preset Value*** or set to an ***Automatic*** value from the pull down menu at the right. To change or establish new ***preset values***, press the Shock button, and enter or change the values in the Preset Spreadsheet.

Preset values can be added or changed by clicking the Shock button next to the value box.

If ***Automatic*** is chosen, Ventsim Visual™ will attempt to recalculate a new value during simulation, by observing airflow direction, airway geometries and airway size changes. Ventsim will only calculate the Automatic Shock Value once, to prevent oscillations in simulation results. If the model geometry or air direction changes it is recommended to RESET the shock value to zero (0) and let the AUTO shock loss recalculate the value during the next simulation.

Note that this is a rough estimation only and may change slightly with every simulation due to changing airflow and directions. It assumes sharp corners on all direction changes and size changes, and is therefore considered to be a 'worst' case value.

DO NOT use AUTO shock losses everywhere through a model. AUTO shock loss should only be used on known areas of high airflow and sharp direction change or size change, Using SHOCK loss throughout a model will over predict total model pressure requirements by up to 20% because every corner and bend will be considered as a 'worst case' geometry. This is not the case for most mines as corners and bends are often smoothed or rounded.

In critical areas which are subject to high airflows and large shock losses, a more thorough examination of airways should be performed, and the shock factor settings manually calculated and used. Guides in setting Shock Value are available in most quality ventilation texts.

9.4.5. PQ Surveys

PQ (Pressure Quantity Surveys) allow the direct entry of a measure flow and pressure to automatically calculate the resistance of single or multiple connected airways.

The PQ entry mode can be established by selecting the PQ Survey item in the Preset Resistance drop list. Once selected, the PQ entry boxes will be shown.

PQ measured resistance is recognised as the most accurate way to create accurate ventilation models as it bypasses many of the variables (such as size, shock losses and friction factors) that would otherwise be required to calculate resistance. If a PQ method is used, other airway definitions such as size and friction factors are ignored in the resistance calculation.



PQ surveys can be entered as a fixed survey or linear length method. A fixed survey is intended to be applied on specific single airways in Ventsim (for example a shaft section between levels). The resistance calculated from the PQ entry variables is applied directly to the airway. Ensure the linear length option is not selected in this case. Only a single airway should be edited when applying this method.

The linear method allows the length of the PQ survey to be also entered. This allows the resistance per 100m or 100ft to be calculated and applied to underlying airways of any lengths. This method is intended for use where the PQ survey may have been performed covering multiple Ventsim airway segments (for example around the bends in a ramp), or when a sample portion of PQ survey is intended to be applied to additional lengths of Ventsim similar airways. To apply this method, one or more airways can be selected and edited simultaneously.

> Hint : To select and edit an existing linear PQ survey in Ventsim, use the SELECTION > SAME PQ survey option on the toolbar to ensure all airways that were used in the original linear PQ survey are first selected before EDITing.

9.5. Fans

Displays a form allowing fan and fixed airflows and pressures to be applied to an airway. If a fan is present, a fan curve graph and duty will be displayed after simulation showing fan performance in a simulated model airway. The operating duty point and system resistance curve will be shown on the fan curve graph. If no fan is present in the airway being edited, a blank window will be displayed.



Figure 9-8 Edit Box Fan Information

Fan Settings **Sets fans, fixed flows or fixed pressures within the airway.** This setting allows the user to include a pressure or flow to move air around a model. Without at least one airway within a model containing a fan or a fix flow or pressure, there will be no airflow within a model (unless natural ventilation pressures are present).

ON **Turns on the fan or fix during simulation** enabling the item to influence airflow within the model

OFF **Turns off the influence of the fan or fix during simulation**. The airway and model will behave as if the fan or fix is not present.

Reverse Button  **Changes the direction of the fan or fix pressure.** This is a convenient way to reverse the direction of airflow and performs the same function as using the REVERSE button on the main toolbar. Note that this is not the same as pressing the COUNTER ROTATE button, which forces the blades of the fan to rotate backwards at reduced performance.

Auto Close **Closes the airway when a fan or fix is turned off.**

Many actual fan installations have a mechanical device which shuts off airflow when a fan is turned off or loses power. The self-closing option allows the simulation to reflect this. If this option is unchecked, airflow will be allowed to flow freely back through the airway, as if the fan is not present. Activating this option will close the airway; preventing airflow when the fan is switched off.

Fix Flow **Forces the simulation to produce an airflow** equivalent to the value entered in the box. A fixed flow cannot be set when a fan is present, and a fan will be removed if the fixed flow is checked. To remove the influence of the fixed flow, simply uncheck the fix check box. When a fixed flow is simulated, the program will calculate a required pressure and power to produce the fixed flow. Where the fixed flow is less than what would normally be simulated, the fixed flow acts as a 'resistance' or negative pressure influence, and restrict flow. In both cases, the results of fixing a flow will be displayed in the ***INFO*** box.

Selecting the  **will recommend a fan** if a fixed flow is present and has been simulated. The program will examine the pressure and flow required to achieve the flow, and then search the fans in the program database for a suitable match. The program will consider up to 4 parallel fans as being a viable match, and display them in descending match order. To swap the fixed flow for a recommended fan, select the desired fan from the list.

Restrict Restrict is similar to a fixed flow in that a certain air flow rate is targeted during simulation. The main difference however is the 'restrict' is designed to resist flow and provide an equivalent resistance. If the restrict value is greater than what would normally be required to restrict airflow (ie it boosts the airflow) a warning will be displayed during the model simulation.

Fix Press **Forces the airway to produce a constant positive pressure** equivalent to the entered value in the box. A fixed pressure cannot be set when a fan is present, and a fan will be removed if the fixed pressure is checked. To remove the influence of a fixed pressure, simply uncheck the fix check box. When a fixed pressure is simulated, the program will calculate the required airflow and power to produce the fixed pressure. The results of fixing a pressure will be displayed in the ***INFO*** box.

Fan Name, Number and Configuration

Selects a fan for the airway. The upper pull down menu allows a fan to be selected from the fan database. Fans are sorted in the order established in the Preset form. Adjacent to the fan name, is the number of fans to be included in the model, and below this is the configuration of the fans (parallel or series). Fans installed in series will increase available fan installation pressure according to the number of fans available, while fans installed in parallel will increase available airflow.

Selecting the  **will remove the fan** from the airway. Selecting EDIT will jump straight to the fan curve database edit screen.

Fan Pressure Curve TOTAL / STATIC

Displays the fan curve pressure type used for the simulation. TOTAL is a Fan Total Pressure (FTP) curve while STATIC is a Fan Static Pressure (FSP) curve. This is selected automatically if one or the other curve is unavailable. Ventsim will preferentially use an TOTAL PRESSURE fan curve if available, except for auxiliary fans connected to ventilation duct, which will use STATIC curves.

If a combination of FAN STATIC and FAN TOTAL curves are used in a model, then (with the exception of auxiliary fans) a mixed pressure simulation solution method is used, which ignores exhaust velocity pressure from a mine. It is recommended that FTP (TOTAL PRESSURE) fan curves be used throughout an entire model if possible, however if this is not possible then the entire model should use FSP (STATIC PRESSURE) fan curves instead. Both types should not be mixed throughout a model as a mixed pressure solution may overestimate the performance of any fan using an FTP curve, as the surface velocity pressure loss is ignored.

Counter Rotate

Reverses the fan blade direction during simulation. This item is useful for emergency simulation where fans are available in the model to reverse airflow at specific locations. The fan curve is adjusted by the reverse factors set in the fan database, to reflect the poorer performance of fans with blades run in reverse. The reverse function is only available for fans, not fixed flows or pressures.

Warning : This is not the same as reversing a fan installation direction where the maximum fan performance would be applied in the opposite direction – the reverse toolbar button should be used for this purpose instead.

%RPM

Adjusts the fan blade rotation speed from the default setting defined by the fan curve in the Fan Database. Note that this is a theoretical pressure and flow adjustment which may not exactly meet true fan performance at different speeds.

Hint: While the simulated speed adjustment to a standard fan curve should be reasonably accurate, if an exact fan pressure and flow curve is required for fan performance at different revolutions, it is suggested a separate manufacturer guaranteed fan curve be entered for the adjusted variation.

9.5.1. Fan Duty Point

The fan duty point defines the pressure and airflow that a fan operates at, and is shown by blue lines on the fan curve. Note that either an **individual fan duty** can be selected, or if multiple fans are present at the installation in parallel or series configuration, the entire **combined installation duty** can be displayed. Due to local air density adjustments, the fan curve may have been adjusted to the one defined in the Fan Database.

The efficiency returned reflects the efficiency curve entered with the fan. The efficiency curve is the shaft efficiency of the fan. It does not include electric motor or drive inefficiencies, which are considered separately in the Settings menu under Motor Efficiency.

EDIT  **Enters the fan database screen to view or adjust fan data**. Note that any fan changes will not be reflected in the EDIT box until after a simulation. Also note that modifying the fan database will change ALL fans of the same name in other locations in the model. To create a custom change only for the fan at one location, you will need to create a duplicate of the fan in the database, and only modify the duplicate.

Hint : Fan operating density is an important specification for designing fan types and installations. Higher air densities will increase the available operating pressure curve (and power draw) for the fan, while lower air densities will have the reverse effect. This can be an important consideration when selecting or designing a fan for a particular area in a mine. Note that for Ventsim Visual™ Standard, air densities are assumed fixed at all locations in a mine.

9.5.2. Fans Stalled, Low Pressure or Negated

If fans are forced by other model conditions to run beyond the limits of the fan curve, a warning showing stalled, low pressure or negated will be shown during model simulation.

Stalled fans occur when the fan pressure build-up is greater than the capacity of the fan curve to accommodate. Ventsim Visual™ reduces the airflow quantity to a point where the fan pressure is no more than the maximum pressure specified in the fan curve.

Low Pressure fans occur when a fan pressure falls below the lowest pressure point of the fan curve, but is still operating above a zero pressure. This may occur when a fan is run with too little resistance or the fan is a high pressure type, being used in a low pressure application. The fan pressure curve in this case may not extend down to the point the fan is operating at. This is undesirable as the program must make assumptions as to what duty point the fan is actually running at. In addition the fan is unlikely to be running efficiently at this duty point. To prevent this warning, simply extend the fan curve to a lower pressure point.

Negated fans occur when the fan offers no useful pressure to the system, and may even retard airflow that would otherwise flow more freely without the fan. This may be a result of other model factors or fans forcing or drawing air through the fan.

When Ventsim Visual™ encounters a low pressure or negated fan situation, it applies a resistance for airflow through the fan above the highest curve quantity. This mimics real life performance of fans and effectively restricts airflow moving through a fan above its limit. The induced resistance results in an additional pressure drop and in negated situations, the fan may apply a nominal negative or 'resisting' pressure, effectively acting as a 'brake' or orifice for the airflow.

Any of these situations are not desirable, as fans are not designed to run beyond their fan curves. Without a fan curve Ventsim Visual™ is forced to approximate fan performance and power consumption. While stalled, low pressure and negated warnings *can* be ignored, every effort should be made to reduce or eliminate these occurrences within a model.

9.5.3. Fan Pressure Curve

The fan pressure curve associated with the fan (or fans if **combined** is selected) in the airway. Note that the fan curve may have been adjusted by the simulation from the curve entered in the fan database to reflect the change in air density at the fan location. The fan operating duty point is shown at the intersection of the horizontal and vertical lines.

9.5.4. Fan Efficiency Curve

The efficiency curve and the airflow volume intersection point define the efficiency the fan is operating at. The efficiency value is used to calculate the estimated fan shaft power. If fan shaft power is entered in the database directly, a fan power curve will be shown and the program will derive shaft power from this curve instead.

9.5.5. Fan Power Curve

If a power curve has been entered for the fan, the power curve and the airflow volume intersection point will define the shaft or absorbed fan blade power the fan(s) are operating at.

Ventsim will preferentially use this curve to calculate power if present. If the power curve has not been entered for the fan, the efficiency curve will be used to calculate power. If this is not present, the default efficiency in the settings menu will be used.

9.6. Heat Tab (Advanced Version)

[ADVANCED] The heat Tab Page controls most of the airway attributes associated with heat and moisture simulation.



Figure 9-9 The Edit Box Heat Entry Tab (Advanced Version Only)

9.6.1. Heat and Cooling

Sets the heating, cooling and moisture inputs for the airway.

Heat Assistant Calculator



The Heat Assistant helps calculate or estimate heat and moisture values to place within airways. The heat assistant calculator is described further in the next Chapter.

Preset On or Off (check box) The check box allows heat and cooling preset sources to be turned on or off, while leaving the preset in the airway. If the box is unchecked, the preset will have no effect on the model thermodynamics. Presets which are turned off will show in the model as a grey colour. Note that custom heat values which are not presets cannot be turned on or off, and must be removed if no thermodynamic effect is desired.

9.6.2. Point Sources

Point Sources of heat and moisture are applied to one specific location within an airway. The

thermodynamic change occurs immediately at that point.

Heat Sensible **Adds (+ve) or removes (-ve) sensible heat from the airflow**. The number will be coloured RED (+ve) or BLUE (-ve) according to the heating or cooling effect of the value. Sensible heat is added or removed without changing moisture content. If sensible heat is removed, and the air temperature dips below the dew point, moisture will condense and will be removed from the air by the simulation.

Heat Latent **Adds (+ve) or removes (-ve) latent heat from the airflow**. Latent heat is sometimes describe as a 'moisture' heat and does not directly change the air temperature, but rather increases (+ve) or reduces (-ve) water vapour in the air. Sigma Heat and Enthalpy increases with latent heat addition.

Refrigeration **Removes sensible heat from the airflow**. If heat is removed, and the air temperature dips below the dew point, moisture will condense and be removed from the air by the simulation. Refrigeration is essentially the same as placing a negative Sensible Heat, and is included as a separate item to clarify its intended function within the model analysis.

Moisture **Adds (or removes) moisture in an airflow**. Moisture addition has a neutral effect on airway heat content, and is therefore added without changing the Sigma Heat content of the airway. The effect of adding moisture is therefore an 'evaporative' effect which reduces dry bulb temperature and sensible heat, and increases latent heat. Removing moisture will produce the opposite effect. Example of adding moisture to the air may include an evaporative cooling chamber or a dust suppression scrubber. Directly removing moisture from air (without cooling) although technically possible, is not a common mine process, and this option in Ventsim Visual™ would only normally be used to 'condition' air to a certain temperatures and humidity for simulation purposes.

Diesel Engine **Adds a combination of sensible and latent heat** to the air to simulate a diesel heat source. The result is generally a warmer moister air flow after application. The ratio of sensible and latent heat added is controlled by the diesel to water ratio set in the heat settings menu.

9.6.3. Linear Sources

Linear sources of heat and moisture are thermodynamic changes applied evenly over the length of an airway or airways.

Oxidisation **The amount of heat per linear length generated by oxidising material in airway walls.** While oxidisation is not a significant factor in most mines, exceptionally reactive sulphide or carbonaceous materials may have a significant effect where airflows are low or airway drives travel an exceptional length through high oxidisation rock.

Sensible / Latent Heat **Adds heat per unit length of the airway**. The value is intended to define heat sources which emit heat over a long length (such as conveyor belts). Setting a single equivalent point sensible heat to each airway will produce the same heat result.

Moisture Linear **Adds (or removes) moisture per unit length** of airway. Similar to the moisture point addition, this less commonly used function may be of value is simulating a long length of airway water addition, such as decline dust suppression sprays.

Hint : How much moisture as being added to your airways from sprays? To practically assess the amount, take a wet and dry bulb temperature above and below the sprays, and use the Ventsim Visual™ Heat and Moisture Calculator to estimate the change in moisture content.



Diesel Engine **Adds a combination of sensible and latent heat** to the air over the length of the airway. A linear diesel source is sometimes used in preference to a number of individual diesel point sources to represent a fleet of diesel equipment travelling along a selected route of airways. To establish this type of collective heat addition, the average diesel motor output of the equipment fleet needs to be summed, and divided by the length of airway the fleet would travel. The resulting heat per length value can then be applied at a linear source to all the airways the equipment fleet would follow. This method is considered to provide a slightly more accurate way to apply a moving heat source, but has the disadvantage of being harder to visualise as independent machines.

9.6.4. Fixed Data

Provides methods for forcing ventilation conditions along an airway to be a required value.

Fix Temp WB, DB **Allows wet and / or dry bulb temperature** of the outlet air from the airway to be fixed to a value. This forces the heat simulation to adjust the air temperature from any previous simulated heat temperature upstream, to the fixed values. The corresponding heat and moisture values required for the transition will be calculated and reported after simulation. This function may have several useful functions

- To adjust air temperature to a known value at a certain location, without having to modify simulated results above this location
- To predict the heat or cooling required to condition the airflow to the fixed temperatures. The INFO tab will provide this information after simulation.

Hint : Fixing the air temperature requires an adjusted to both sensible and latent heat content of the air. Entering the wet and dry fixed values as the **same** temperature forces the simulation to assume a pure 'refrigerative' condition which is converted to sensible heat and condensation, instead of the normal sensible and latent heat calculation. This is useful for determining refrigerative loads required for producing particular airway conditions. Note that there still may be some residual latent heat reported for the airway due to strata heat and moisture transfer.

Diesel Emission An optional value used for Diesel Particulate Matter simulation which **defines the total amount of diesel particulates emitted** by an engine over a period of time for each unit of engine power. This can be derived from manufacturer's specifications or by practical testing of exhaust emissions.

Note that EPA measured values are likely to include all particulate matter including elemental carbon, organic carbon and other trace matter. Atmospheric DPM exposure limits are normally limited to elemental or total (elemental + organic) carbon levels, therefore either emission rates or final simulated results will need to be scaled accordingly.

Advance Rate The rate of advance or progression of the airway per month. The area size of the airway dictates the number of tonnes entered into the simulation, and this figure is included in the Simulation Summary. Heat from broken rock entering the mine atmosphere is highly

dependent on the geometry of the muck pile, the length of time the rock is exposed to air and the airflow and moisture over the muck pile.

To simply the process, heat from broken rock is added to the atmosphere at a rate defined in the settings as a percentage of heat contained in the broken rock that is between the mine atmosphere temperature wet bulb, and the virgin rock temperature. The exposed rock surface of the advancing airway is automatically assumed to be freshly mined for simulation purposes.

9.6.5. Rock Conditions

Sets specific rock conditions for the airway. Airways will normally source these values from the default values in the Settings menu, however they can be individually overridden for each airway. Using these functions, it is possible to set parts of the mine with different rock parameters types or wetness fractions.



Figure 9-10 Rock Condition entry for airways

Rock Type Specifies a rock type that has been pre-defined in the Preset menu (click on Rock Type) to enter the menu. Selecting a preset value overwrites any manually defined rock parameters.

Thermal Conductivity **The thermal conductivity of rock surrounding the airway**.

Thermal Diffusivity **The thermal diffusivity of rock surrounding the airway**. This value is optional and can be derived by entering the rock density instead.

Specific Heat **The specific heat value of rock surrounding the airway**.

Rock Density **The density of rock surrounding the airway**. This value is optional and can be derived by entering the thermal diffusivity instead.



Wetness Fraction **The fraction of the airway surface which is wet**. A value of 0.01 would describe a nearly dry surface, while 1.0 would describe a fully wet surface. The Wetness Fraction button can be clicked to enter the preset spreadsheet and create names for defined wetness fraction values.

Age or Year Entry **The age in years since the start of the airway was mined** (in decimal years, for example 4.5), or the calendar year of mining (in decimal format, for example 2006.5 would represent end of June in the year 2006)

Age or Year Exit **The age in years since the end of the airway was mined**

Airway ages can be a mixture of calendar years and age in years. Ventsim Visual™ determines which age type has been entered by the number of digits in the date field. Four (4) digits indicate a calendar year age. Where calendar year ages are entered, airway ages are calculated from the Current Calendar Year age set in the Settings Menu.

VRTemp Entry / Exit **Manually sets the Virgin Rock Temperature at the start and end of an airway.** This function is unlikely to be used often. It forces the heat simulation to use preset rock temperature values, instead of calculating the rock temperature from the geothermal gradient. This function may be of assistance if the rock does not conform to the geothermal gradient parameters (for example mining through backfill) or the rock temperature is being modified by other factors such as local geothermal sources or reactions.

Note that the values normally reported in these cells are calculated from the simulation and will change with depth and time. To FIX the values to permanent temperatures, simply overwrite the pre-existing calculated values.

9.6.6. Contaminant

The contaminant tab display options and settings required for contaminant simulation in a model.



Figure 9-11 Edit Box Contaminant Input

Contaminant Concentration Places an initial average contamination value into the airway. The value can either be unit less or represent a volume concentration value of a particular type. It is proportional to the airflow in which it is entered, and could be considered as a percentage, part per million (ppm) unit or any other unit which is representative of a value per unit volume of air. Clicking on the check box adjacent the value box, will automatically set or remove a value specified in the Setting defaults.

This value is ignored if 'Explosive Simulation' is selected as in this case the initial concentration is automatically calculated from the explosive yield rate (established in the settings) and the airflow.

9.6.7. Contaminant Options (Dynamic)

Specifies dynamic contaminant simulation options which can be modified for the airway.

Fixed Release **Specifies a constant concentration release of contaminant into the airstream** for a specified number of seconds.

Linear Decay **Specifies a reducing concentration release of contaminant into the airstream** for a specified number of seconds. The concentration initially starts at the specified amount, and decreases at a linear rate over the specified number of seconds.

Logarithmic Decay **Specifies a logarithmically decreasing concentration release of contaminant into the airstream** for a specified number of seconds. This means the concentration of contaminant will start at the initial concentration and rapidly decrease over the initial time frame, with a longer lower concentration period after that.

Explosive Amount **The amount of explosive to place** for dynamic contaminant simulation. The higher the amount placed, the more contaminant that must be dispersed into the model during simulation.

Dispersion Rate The logarithmic factor rate at which contaminant will be dispersed. This does not impact the mass volume of contaminant entering the model, but rather the rate at which it escapes into the model airflow. Higher values will simulate more rapid dispersion of contaminant from the initial contaminant source. It does not affect dispersal rates once the contaminant has entered the main model airstreams.

9.6.8. Sourcing Location Tools

Provides options for setting contaminant reports and simulating possible location sources of contaminants underground.

Report Smoke Places a smoke report in the airway.

Report Fresh Places a fresh report in the airway.

See Location Tool menu item for further information.

9.7. Information

The information tab provides a list of detailed information of settings and simulated values for an airway. The list may be copied to the Windows clipboard for pasting in another application such as Word or Excel. This can provide a valuable tool for comparing changes in specific airways before and after simulation.

In addition, a thermodynamic summary is provided showing conditions at the start and end of the airway.



Figure 9-12 Airway Information Tab

While most data values are self-explanatory, some notes below provide further explanation.

9.7.1. Fan and Fixed Information

An airway with a fan, fixed flow or fixed pressure will display the specific pressures, power and cost of the fan or fix for the airway installation. Unlike the Fan Tab, the pressures and volumes displayed will be for the entire combined fan installation (if more than one fan

present), not for individual fans.

Fan Present

Fan Pressure Fan pressures are derived directly from the pressure volume curve of the fan. If the Fan Total Pressure (FTP) method is used, the duty point will be simulated from the FTP fan curve, and static pressure will be derived from the fan diameter or airway size. For the Static Pressure (FSP) method, the duty point is simulated from the FSP fan curve and the total pressure derived for the fan or airway size.

Special consideration is required for surface exhaust fans. For an exhaust surface fan, by definition, the Mine Total Pressure (loss of total pressure across all mine resistances) at the collar (inlet) to the fan is equal to the required Fan Static Pressure (FSP). The Fan Total Pressure includes the velocity pressure loss of the fan to atmosphere. The value provided by the simulation (FTP) considers evasé and discharge area size, but is theoretical, and does not include shock or frictional losses between the fan collar and the fan discharge outlet. As a result, for an actual fan installation, additional FTP beyond the simulated result may be required to achieve the simulated results. As every fan and installation is different, it is best to discuss this with your fan manufactures in pressure critical installations.

Fan Power The fan power is calculated on Fan Total Pressure (FTP) and represents the power the fan motor is applying to the fan blades to generate the pressure and flow through the fan. The fan shaft (absorbed) power is calculate from the fan power curve. If a power curve has not been set for the fan, the fan total efficiency curve is used in conjunction with fan total pressure and volume flow, to calculate shaft power. If *this* is unavailable, the default fan efficiency is used.

Fan Electrical power is the estimated electrical power drawn by the fan motor. It is calculated from the Fan shaft power factored up by the motor efficiency factor set in the Settings menu.

Fan Cost The annual cost figure is derived from the power cost set in the Setting Menus for a fan operating at this duty point continuously for a full year.

Fix Present ? Fix flows or pressures are often entered where a specific fan is not available or needs to be calculated. The fixed flow information in particular is useful for identifying duty points for fan pressure at a specific volume. This point can then be used to specify and source a suitable fan with a curve that can matches the pressure and flow.

Fixed Duty Point A fixed flow will show a Collar Total pressure for a surface exhaust fan or a Fan Total pressure for an equivalent underground fan in the airway. This is similar to a duty point for a fan.

For a surface exhaust Fan, the Fan Static Pressure is arguably the critical pressure value, as the velocity portion of the Fan Total Pressure is lost to atmosphere. A fixed flow will give a Total Collar pressure value for a fan. This is equivalent to the Fan Static Pressure if the fan is a similar size to the airway shaft, however this correlation will change for differing fan diameters.

For an intake or underground fan, the fixed flow with provide a equivalent Fan Total Pressure value.

Required Power The power value will utilise the default efficiency set in the Settings Menu and describe a minimum motor size (shaft power) for the required fixed flow, and estimated power

(electrical) consumption for the fixed flow.

Annual Fix Cost The annual cost figure is derived from the power cost per kilowatt hour set in the Setting Menus for a fixed flow or pressure operating at the duty point continuously for a full year.

9.7.2. Pressure Information

Describes various pressure conditions at either end of the airway.

Relative Pressures The pressure at either end of the airway in relative to the equivalent surface pressure at the same elevation. Negative values indicate the relative pressure is lower than the surface pressure, while positive values indicate the opposite. Relative pressure in different parts of the mine can help show which direction air would flow if they joined. Air will always flow from higher relative pressures to lower relative pressures if a path is available.

> Note : As the relative pressure describes airway pressure at an equivalent elevation, if effectively ignores elevation and barometric effects of depths.

Barometric Pressures Describes the calculated barometric pressure at the start and end of an airway. Barometric pressure increases with elevation depth, and is in addition to any pressure influences on the model by fans or other pressure sources. Barometric pressures and the resulting densities are an important factors in fan performance and heat simulation.

Pressure Loss Describes the frictional pressure losses along an airway, plus pressure additions due to fans or other pressure sources. A negative value indicates frictional pressure drops are larger that pressure additions to an airway. A positive value indicates pressure additions from fans or fixes have more than overcome frictional losses and contribute to system pressure increases elsewhere in the model.

9.7.3. Heat Data

Heat data shows various air conditions derived from heat simulation.



Figure 9-13 Heat Data

Temperatures Wet bulb and dry bulb temperatures at the start and end of the airway

Sigma Heat The Sigma Heat content of the air at the start and end of the airway. This value describes the heat content of air per unit weight, and is therefore independent of air or mass flow rates.

Heat Addition / l The amount of sensible and latent heat added to the airflow per unit length. The heat may be sourced from rock strata, auto compression or a heat or refrigeration input value.

Heat additions total The total amount of sensible and latent heat added for the full airway length.

Manual addition The amount of heat added by the user in the form of sensible, latent or diesel heat input.

Contained energy The amount of sigma heat present in airflow, multiplied by the mass flow of the air through the airway. The difference in these values should be equivalent to the total heat addition to the airway.

Relative Humidity The moisture content of the air relative to the total saturation potential of the air at the current temperature and pressure conditions.

Condensate The volume flow of moisture condensation from airflow due to environmental conditions changes which result in air temperatures or pressures falling below the saturation point of air. This normally results from a refrigeration source chilling air below the dew point temperature,

or a reduction in barometric pressure (from air travelling up a shaft for example) reducing air moisture carrying capacity.

9.7.4. Simulated Data

Displays the results of heat simulation at the entry and exit of the airway. The data displayed is 'Read Only' and is for information purposes only. Most of the values displayed are self-explanatory. More detailed airway information is available under the Information Tab.

Elevation The calculated elevation of the start (left) and end (right) nodes of the airway.

Wet Bulb The calculated wet bulb temperature at either end of the airway.

Dry Bulb The calculated dry bulb temperature at either end of the airway.

RH Moisture The calculated relative humidity and the moisture content of the air.

VRT The calculated virgin rock temperature at either end of the airway. This value is calculated from the geothermal gradient, the elevation of the airway and surface rock temperature settings.

Sensible Heat Addition **The total sensible (dry) heat addition to the airway**, from rock strata and any user sensible heat inputs into the airway

Latent Heat Addition **The total latent (wet) heat addition to the airway**, from rock strata and any user latent heat inputs into the airway.

9.8. Notes

The Notes Tab allows detailed information to be recorded for any airway.



Figure 9-14 Recording sheet for entering general airway information

Notes may include specific model setup information, or may consist of ventilation survey results of airflow, temperatures or gas levels for actual underground ventilation conditions. Such information could be used to help validate simulated models, or could provide a useful ventilation recording tool to demonstrate ventilation conditions underground over a period of time, or provide a Statutory record of ventilation information.

Add Ventlog Station Adds a Ventlog compliant name to the airway notes. A Ventlog name in the notes field will indicate that the airway is a Ventlog station that can be exported to a Ventlog database. The default name starts with [LOG] however the name after this text field can be changed to any valid text name representing the name of the station.

For example, Ventsim may automatically name the station [LOG] VS50, however the user can change the name to [LOG] MainDecline80D. When exported to the Ventlog database, the name MainDecline80D will appear in the database with the correct coordinates and directions.

9.8.1. Sensors

The sensor option in the edit box allows live imported data from the optional LIVEVIEW™ module to be placed and displayed on an airway.

The dropdown lists permit the specific sensor to be attached to an airway, and also offer an option to modify the simulated conditions in the airway during LiveVIEW™ simulation. See the LiveVIEW™ section for further information.



Figure 9-15 Attaching sensors to airways

Chapter

10

10 THE POPUP CONTEXT MENU

The popup menu, activated at any time by a Right Mouse Click, provides a useful collection of commonly used function. While most of the functions are also available from the toolbar or top menu, the popup feature can save considerable time as the mouse cursor is not required to return to the top of the page when a new function is selected.



10.1.1. Fit All

Scale view window, so all model graphics fit on the screen.

10.1.2. Zoom Out

Increases the distance away from the point of focus by a factor of two.

10.1.3. Flight

Enters a flight mode, which allows the user to freely 'fly' around the model in three dimensions. To control the flight system, simply move the mouse similar to an aircraft flight stick, using the scroll wheel to move forwards and backwards.

Mouse Controls

Mouse Up	Pitch down
Mouse Down	Pitch up
Mouse Left and Right	Yaw (turn) left or right
Mouse Scroll Button	Control Speed Forward and Reverse
Escape Key	Exit flight mode

10.1.4. Select Level

Selects one or more levels or elevations for separate display on screen. This can isolate a specific elevation range of airways for display, which can clarify display on screen in complex models. The function works independently of the levels specified in the level (elevation) database. Any elevation or range of elevations can be selected at any time.

The elevation range is selected by LEFT mouse clicking one or more airways on the screen, and RIGHT mouse clicking to commit and activate the selection. As airways are clicked, the elevation range selected will turn YELLOW. To select a larger area or range of elevations,

draw a fence (by holding the left mouse button and dragging the box) around the airways within the desired elevation.

All airways outside the elevation range will be hidden or made transparent. The level of transparency can be adjusted from the ***Colour Palette Manager.***

HINT: Airways outside of the normal range of the LEVEL (elevation) database will be displayed as invisible or transparent. The LEVEL database should have a least one level which encompasses all elevations of airway data in your model.


Ventsim Visual Blue_sky.vsm VentSim Demonstration Network
File Edit View Saved Views Run Tools Window Help
Airflow
Quantity
M41 FAR
M40 Decline
M40 Decline
M40 Decline

10.1.5. Show All **Display all elevation ranges**. This function will reset any levels selected from the previous function.

10.1.6. View **Enter the view mode.** See toolbar view for more information.

10.1.7. Select **Enter the selection mode.** Airways selected can be deleted, edited, moved or copied. See toolbar selection for more information.

10.1.8. Add **Enter the airway construction mode.** Airways can be drawn by dragging the mouse or edited by clicking the mouse. See toolbar add for more information.

10.1.9. Edit **Enter the airway edit mode**. Airways clicked or fenced can be edited in the Edit box. See toolbar edit for more information.

10.1.10. Block **Enter the airway block mode**. Airways clicked can be blocked or unblocked to prevent or allow airflow. See toolbar block for more information.

10.1.11. Delete **Enter the airway delete mode.** Airway clicked, or fence selected and clicked are deleted from the model. See toolbar delete for more information.

10.1.12. Move **Enter the airway move mode.** Airways clicked can be moved via coordinates. Airways dragged can be moved with the mouse. See toolbar move for more information.

10.1.13. Reverse **Enter the reverse airway mode**. Airways clicked are reversed along with any fixed flows, pressures or fans. See toolbar reverse for further information.

10.1.14. Action, Data and View Toolbar The toolbars at the sides of the screen can be turned off or on as required. Use this function to select the visibility of each toolbar.

10.1.15. Reset Display **Reconnects the Windows operating system to the graphics hardware device**. The software link may occasionally become disconnected or corrupted, resulting in a blank display. Reconnect the DirectX interface will reset the graphics software to hardware link and re-establish the display.

Chapter

11

11 PRESETS

11.1. Preset Values



Figure 11-1 Preset Table Options

Preset values provide a quick and convenient way to specify airway characteristics and parameters that may be commonly used in the ventilation model. Examples are resistances (such as doors or seals), common wall friction factors, shocks losses, heat sources.

The preset table also provides access to model primary and secondary layer names and colours, as well as air types, tunnel profiles, fans, wetness fractions and numerous other items used in Ventsim simulation.

11.1.1. Preset Values

Any preset value which is changed will be applied to ALL airways using that preset value. For example if a model has 10 airways using a resistance preset called 'Rubber Flaps' and the resistance for 'Rubber Flaps' is changed in the preset box, then ALL 10 airways using rubber flaps will have the new resistance applied when simulation is next performed.

Most items can be deleted by selecting the entire row (or a selection of rows) and pressing DELETE, or by selecting and deleting individual values. If a preset is currently in use, a

warning may appear stating the fact, and the result it will have on the model. Ideally, presets should not be removed if they are currently in use.

11.1.2. Sort Order

The sort order of the preset values displayed in the spreadsheet, and displayed in forms in other parts of the program can be specified. All columns in the preset form can be sorted by Ascending or Descending by clicking the column header once or twice. For example, resistances can be sorted by name (by clicking the 'Resistance Name' column header, or by value (by clicking the value header).

In addition, row items can be manually sorted, by selecting the row and pressing the UP or DOWN arrow on the keyboard. The sort order will be retained next time the form is accessed and will be saved with the file.

11.2. Accessing Presets

Preset items are accessed from the main TOOL menu, however most preset items can also be directly accessed from the EDIT form by pressing the appropriate preset button. When activated from the EDIT form, the currently used preset will be highlighted in the Preset form.



11.2.1. Resistance

Up to 100 different resistance presets can be entered. Resistance presets can be applied to

airways from the EDIT form. Any resistance entered in the preset will be applied to an airway during simulation.

It is important to note that underlying airway resistances due to wall friction WILL ALSO be applied in addition to the preset resistance. For example if a preset resistance of '10' for a 'DOOR' is applied, and the airway has an underlying resistance of 0.015, then a total resistance of 10.015 will be applied during simulation.

The reversing resistance is an optional field which applies a different resistance should an airflow be reversed during simulation, and the 'restrict airflow direction' flag is chosen for the airway. Reversing resistances may be useful in situation where resistance increase (such as automatic doors closing, or flaps sealing) or where resistances decrease (such as doors swinging open automatically) when airflow direction changes. Such setups may occasionally be used to prevent recirculation or assist with emergency response design when fan direction may be reversed. If the value is left at zero (0), then a default reversing resistance (specified in the SETTINGS) will be applied if an airway is reversed AND the 'restrict airflow direction' flag is selected.

11.2.2. Friction

Up to 250 different friction factor presets can be entered or used. The friction values in the EDIT box can be applied as presets (entered in the preset form), as individual 'CUSTOM' values or as AUTO values which defaults to a value specified in the SETTINGS.

11.2.3. Shock

Shock equivalent lengths or shock factors can be entered in the shock preset area. The application of these factors will depend on which shock loss method is specified in the SETTINGS. The values for each shock item during simulation will be applied according to the method chosen. Only the value of the shock loss method currently used needs to be entered.

11.2.4. Heat

Up to 250 different heat, moisture and refrigeration sources can be entered. Each 'Heat' source can be a combination of different heat parameters (such as moisture and sensible heat combined). Airways with a specified heat source will have these values applied during simulation. The screen also shows the number of heat sources currently in use.

11.2.5. Layer Prim, Layer Sec, Air Type

The form shows current names for these items, and in the case of layers, whether they are being used or not. The names can be changed at any time, and new layer names and air type names can be added. Colour can be changed by clicking on the colour box. There are currently 250 layers and 25 airway types reserved for use.

11.2.6. Fans

Present a summary of current fans, and the basic characteristics of those fans (eg diameter, air density for the curve etc). While the fan curve data cannot be directly edited from this screen (you will need to go to the fan database function), the fan names can be changed as well as the other fan parameters. Fans can also be fully deleted from the model. A read only column states the number of fans in use in the model.

11.2.7. Airways

Airways presets allow a specific size and type of airway to be set with pre-defined dimensions, friction factors and profiles. Airways can then be quickly selected in the EDIT box to the preset airway type containing the preselected values.

11.2.8. Profiles

Profiles allow custom profile shapes to be entered into Ventsim. The first five (5) profile shapes – square, round, shanty, arched and irregular are preset and cannot be changed, however the profile string is shown to help users define new profile strings.

Profile strings are dimensionless coordinates centred around an origin point of (0,0). Airway profiles are intended to extend from (-1, -1) to (1, 1) which represents the full extent of the profile. The actual airway size of the profile is set in the EDIT box which then scales the profile

to whatever size is specified. The profile shape is updated in the lower right corner, once the profile string is entered and re-selected.

To enter or add a profile, click on the Profile String cell on the profile grid. A data enter form will show allowing points to be entered or modified.

For example a square would have an X, Y profile -1,-1 ; -1, 1 ; 1 ,1 ; -1, 1, which represents the X,Y extents of all four corners around a centre point of 0,0. If this profile is chosen in the EDIT box when setting an airway, entering a width and height dimension of 5.0m would scale the profile accordingly. Note that there is no need to provide an area or perimeter. Ventsim automatically calculates the perimeter and area, based on the profile shape given.



11.2.9. Wetness Fraction Defines the wetness fraction options for underground airway wall wetness. Wetness fractions can be applied to airways in the HEAT section of the EDIT box. In general, wetness fractions closer to zero represent dryer airways and fractions closer to one (1) represent wet airways.

11.2.10. Sensors Lists the current sensors imported from the LiveVIEW™ option.

11.2.11. Combustion A selection of combustible products used in VentFIRE™ simulations. Combustible products are defined by the amount of heat released MJ/kg, the oxygen consumption (kg Oxygen per kg fuel burned) and the yields rates of various combustible products (kg combustion product per kg product burned).

> Note that the yield of carbon monoxide is specified as a minimum and maximum. This provides some flexibility in the emission rates for oxygen rich and fuel rich fires. If the calculated equivalence ratio (ratio of fuel available per oxygen available) exceeds above (1) then the maximum CO value will be used in simulation. It the ratio falls below 0.5 then a value close to the minimum will be used. For ratios between these values, a value between minimum and maximum will be calculated, increasing towards the maximum

value as the ratio approaches one (1). The equivalence ratio is not fixed and is constantly recalculated during simulation.

11.2.12. Leakage

Defines the resistance of leakage of air from a Ventilation duct. The values define the area sum of holes per total unit area, specified as mm2 per m2 of duct. Because this ratio uses the same units, any number representation of the ratio x 1 x 10^6 (million) could be used – for example parts per million (ppm).

11.2.1. Gases

Defines a mixture of gases that can be applied to airway gas simulation. If the total volumetric concentration of gases defined is less than 100%, then the remaining volume will be used during simulation to allow airway gases to volumetrically balance into the remaining void. The will retain the preset gas mixture of the defined gas value, but allow other undefined gases to changing depending on the airway gas content as simulation time.

Chapter

12

12 SETTINGS



Settings provide control over a large number of parameters used in Ventsim for simulation, graphical display and file handling. Settings are normally saved specifically for the file in which they are modified for, but can be shared with other files using the INHERIT function, or the MASTER LINK function.

12.1. Costing

Defines the mining and ventilation cost components of a model. These figures are used in calculating optimum airway sizes, and total ventilation cost to run a modelled ventilation system.



Currency The symbol used for the local region currency value. This symbol will be applied in text displays and reports. Ensure all costs defined in this section are set in the local region current value.

Cost Horizontal **The cost of mining a unit volume of rock for horizontal or inclined airways.**

This figure is an approximation used in the global optimisation routines to calculate efficient airway sizes. If a mine has an approximate cost per linear distance (eg per metre) for each tunnel size, this can usually be approximated back to a fixed cost per metre and a variable cost per m3 which is largely consistent over different airway sizes. Ventsim uses both the fixed and variable component in calculating total airway cost.

Cost Shaft **The cost per unit volume for mining vertical or inclined ROUND shafts**. As with horizontal costs, this can be approximated if the linear cost of vertical airway mining is converted to a fixed linear and variable unit volume cost. Ventsim uses both the fixed and variable component in calculating total airway cost. Ventsim assumes any airway with a slope greater than 45 degrees is defined as a vertical airway.

Cost Vertical Other **The cost per unit volume for mining vertical raises that are NOT ROUND**. The cost basis for a raisebored airway (round) and a blasted vertical area (eg a winze or Alimak raise) are normally very different, hence this category allows costs of different types of vertical development to be differentiated. Ventsim assumes any airway with a slope greater than 45 degrees is defined as a vertical airway.

Fan Purchase Cost **The purchase cost is an approximation of a fan total cost per unit of power**. For example a cost estimate of $1000 per kW, would mean a fan of 30kW in size would cost $30,000 to purchase. This figure is used in the optimisations to estimate fan costs for different fan power requirements. This cost should be calculated to include the electrical infrastructure and installation costs as well as the fan purchase cost.

Mine Life **The expected average mine life of airways in the mine.** This figure is used by the optimisation to estimate to power costs consumed over the life of an airway.

NPV Rate **The discounted rate of future costs** to determine the present value of expenditure on power over the life of the mine. Values higher than zero (0) will decrease the significance of (discount) future cost savings, placing more importance on initial capital costs such as the airway mining cost and the fan purchase cost.

Power Cost **The cost of power supplied to the mine**. The power cost is used to calculate the ventilation cost of running a mine model, and applied to all fans, fixed quantities and fixed pressures. The power cost is local currency unit dependent. Total power costs for mine model will be displayed as a factor of this value.

HINT : To gain the true operating cost of a ventilation model, users should consider including a maintenance and depreciation component in the power cost to cover the future cost impact of maintenance, repair and replacement of ventilation infrastructure. A value of 15% – 20% additional cost is typically used.

12.2. General



General factors describe default airway sizes and settings when first building a model, as well as file saving and loading behaviour in Ventsim.

12.2.1. Airway Defaults

Various defaults used by Ventsim in establishing airways without defined dimensions.

Airway Shape **Default shape of airway**.

Efficiency Fan Motor: **Default fan motor efficiency** to apply to calculated fan shaft power to estimate the electrical power absorbed by the fan motor. In most cases it will be around 95% for direct drive electrical motors, or as low as 80 – 85% for offset or gear drive fans.

Efficiency Fan Fix: **Default efficiency factor** to apply to motor shaft power calculations for fixed quantities and fans without efficiency or power curves.

Friction Factor **Default friction (K) factor** to apply to new airways

Friction Factor Type The number of the friction factor type to use on a default airway

Primary Secondary Layer **Default view layers** to set to new airways.

Reversing Default Resistance **Default resistance** to apply if resistances are set in airways which have reversed airflow AND the 'restrict' reverse airflow button is pressure. This is only applied if no reversing resistance already exists for the preset item. For example a resistance for a door may be 10 during normal flow direction, but may reduce to 0.5 when the airflow is reversed and the door

swings open. Once again, this figure is ONLY applied if the 'restrict reverse airflow' option is chosen in the EDIT box, AND there are no pre-existing reversing resistances set in the resistance preset spreadsheet.

Layers – Primary and Secondary **Default layers** to apply for new airways.

Size Width, Size Height, Size Area **Default size of new airways**. Imported DXF and text files without specific airway size will also be set to these values

Hint : Airway defaults are normally only applied if airways are constructed without connection to other airways. Where airways are connected to existing airways, they will INHERIT the settings of the airways the new airways is connected to. This behaviour can be modified from the EDIT > NEW AIRWAYS menu item.

12.2.2. File Settings

Auto Backup Forces Ventsim to make a backup of the currently worked model every 5 minutes. If the program crashes, or is forcibly exited, the backed up model will be loaded automatically next time the program is run.

Warning – if the model has become corrupted for some reason, there is a possibility that the auto-saved model may also be corrupted. For this reason, it is recommended that a model be regularly saved to ensure that good working copies are available as backups if required.

Maximum Airway Numbers Automatically performs an heat simulation when the file is loaded. This will update heat simulation summary parameters and a number of calculated heat parameters only available after a simulation

Maximum Reference Elements Automatically performs an heat simulation when the file is loaded. This will update heat simulation summary parameters and a number of calculated heat parameters only available after a simulation

12.2.3. License Settings

Alters license activation settings which may be required to allow Ventsim to access the internet to validate licenses. Ventsim normally uses Microsoft Internet Explorer settings to access the internet, however on occasions third party programs like Ventsim may be denied direct access, requiring the proxy name and proxy port address to be entered manually.

These values can also be adjusted in the License Manager form.

12.3. Graphics Settings

Control the various aspects of the screen graphics and presentation.



12.3.1. Background

Background Picture Sets a preset or custom picture to the background of the visual display. This may provide some visual flair for presentations or may simply suit the users preferences. An option exists to use a preset background (current CLOUDS or GROUND), or a custom background picture can be displayed by simply dragging a picture file from windows on to the screen.

Background Picture Tinting Tints the background picture using the Screen Colour Top and Bottom settings. Note that a black screen colour will totally hide the pictures, while a white screen colour will fully show the picture in natural colours.

Background Colour Bottom and Top Colour of upper and lower halves of background. The colours are smoothly blended to provide a gradient effect. Lighter colours may be more appropriate for presentations and report.



Dark and stormy background image

12.3.2. Colours

Brightness Controls the relative brightness and intensity of the colour displays on screen.

Grid Colour **Colour of grid lines.**

Grid Sheet **Colour of semi-transparent edit plane** sheet shown during vertical drawing operations.

Colour Text Data **Colour of the airway data**. Text colours may need to be adjusted to provide contrast if the background colours are adjusted.

Colour Text Airway **Colour of the airway text names** and error messages. Text colours may need to be adjusted to provide contrast if the background colours are adjusted.

Colour Text Node **Colour of the airway node names**. Text colours may need to be adjusted to provide contrast if the background colours are adjusted.

Print to White Background Instructs the program to make the background white when printing a graphics model to a printer or saving the image to a file.

Selection Colour **The colour of selected airways**. The default colour is yellow, however sometimes this colour may not be as visible with lighter colour backgrounds.

Text Background The colour behind text on the screen if transparent text is not used.

12.3.3. Controls



Snap Tolerance Adjust the willingness of the Ventsim cursor to adjust or join to other airways while drawing or moving airway items. For finer control (less propensity to connect to close airways) reduce this number (minimum 1, maximum 100)

Use 3D Mouse Turns on an option to use a Connexion™ 3D mouse. This type of input allows for models to be rotated, panned, and zoomed with a single control, leaving the regular mouse free to operate menus and selection duties. This option will have no effect if a Connexion™ 3D mouse is not present.

12.3.4. Coordinates

Grid North Orientation Defines the direction of grid north on the screen. Therefore, if grid north direction is defined as UP, then the Northing coordinate numbers will start lower from the screen bottom, to higher numbers towards the screen top. If a GRID NORTH system is not chosen, then this setting will show CUSTOM.

Grid System Most mines use a GRID NORTH system. Ventsim's coordinate convention when using grid north coordinates is Easting, Northing and Elevation in that order. If another type of system is used, then an XYZ system can be specified, which allows for orientation of coordinates in

any direction. Some Ventsim CLASSIC models use a custom system and in this will likely be automatically set when a Ventsim Classic model is imported.

Coordinate Centre Defines the centre of the grid system from which the grid lines will be drawn. Note that this can only be specified if Automatic Grid Centering is turned OFF (otherwise the centre numbers will be automatically adjusted when the model is viewed or reloaded).

Level Range **The range of elevations to show around a single selected level**. Selected levels may be chosen from the RIGHT CLICK mouse popup menu, and limit the range of airways data shown on screen.

Orientation of Elevation, X Axis, Y Axis This option should only be used for CUSTOM grid orientation. Grid NORTH orientations do not require these settings to be adjusted.

Spacing for Grid The spacing between grid lines on the screen.

12.3.5. Icons



Figure 12-1 Graphics Setting Options

Custom Resistance Display Threshold Controls the display of resistance icons where airways have been assigned a custom resistance. Only airways with a resistance above the threshold will have an icon displayed.

Transparent Icons Shows transparent sides for icons over airways.

12.3.6. Rendering

Anti-aliasing **An advanced graphics option** (not supported by all graphics card) which smooths the appearance of the edges of solids to give a visually more appealing look. The option may significantly slow some graphics cards or cause graphics irregularities. By default, it is set to FALSE.



Figure 12-2 Graphics Setting Options

Backface Culling Removes hidden surfaces from the display. This may make older graphics cards more responsive in displaying complex graphics.

Hide Text While Rotating **Hides text while model is rotated or zoomed**. Very large models with lots of text can slow or make smooth rotation movements unresponsive. Use this option to hide text and make rotation movement much smoother.

Rotation Inertia / Damping Ventsim model rotation results in a short period of continued rotation after the mouse is released. This is purely for visual appeal and is provided to give models the illusion of 'weight' and solidity. The speed at which rotation is damped can be adjusted or turned off using these settings.

HINT To allow the model to rotate freely without stopping, choose a damping level of zero (0), or HOLD THE CTRL key down when rotating a model with the mouse.

Show All Arrow/ Node/ Text data. Hide or shows arrow, node and text data by default. This can be used to improve display clarity by removing unnecessary graphical details. Note that this function can be overridden from the View menu options or the RIGHT click context menu options for text and other graphical items.

Maximum / Minimum Frame Rate The rate at which to update the screen graphics. To conserve laptop battery power, the minimum frame rate option is available to reduce power when Ventsim Visual™ is not the active program in Windows.

12.3.7. Size

Airway Scale Scales airways graphically so they appear larger or smaller than the specified dimensions. This does not change the calculated airway size. A factor of '1' is normal scale. Factors larger than one will enlarge airway graphics while factors smaller than '1' will shrink airway graphics. This function may make very large extensive models larger and easier to see, or conversely can make very small model (eg lab scale apparatus) also easier to see.

Size Data Node Airway Text **Size of airway text displayed on model**. Larger text sizes are generally clearer to read, however excessive data may clutter display.

Size Node, Icons, Arrows **The size of the nodes, icons and arrows.** Note that the size reduces in wireframe mode to improve display legibility.

Size Node Icons/Arrows **The size of the nodes, icons and arrows**. Note that the size reduces in wireframe mode to improve display legibility. In Solid mode, Icons and Nodes will not be reduced smaller than the airway size.

12.3.8. Text



Font for Text Allow selection of the type of FONT to display on the screen.

Icon Heat Test Display text on icons with heat sources.

Show Heat Text with Airway Text Shows the thermodynamic setting names on the airways they are attached to.

Maximum Distance for Text Hides text beyond a defined distance from the display front. For large models, this can speed up display.

Show Fan Description Display text showing fan name description

Text Transparent The background for text characters is shown as a solid colour, or transparent. Turning off text transparency can improve clarity of text graphics, but will obscure the airway graphics behind the text.

[TRUE] Text labels backgrounds are transparent and show graphics under the label.

[FALSE] Text label backgrounds are solid and do not show graphics underneath. In some cases, this may improve the legibility of text.

Text Scale Relative **[TRUE]** Reduces the size of text labels relative to distance away from view camera. This make close airways larger and more legible and distant airway text smaller. Simulation – Airflow

12.4. Simulation

12.4.1. Airflow

Simulation airflow settings directly influence how the airflow simulation operates.



Airflow	
Allowable Error	0.050 m3/s
Auto Simulation	Yes
Compressible Airflows	No
Density adjust friction factors	Yes
Density adjust preset resistances	Yes
Fan Reverse Flow Factor	0.5
Fan Reverse Pressure Factor	0.5
Ignore Warnings	No
Iterations	500
Maximum Simulation Pressure	1,000,000.0 Pa
Mesh Surface Airway Priority	Yes
Shock Loss Type	Shock Factor Method
Stop Resistance	1,000,000,000.0 Ns2/m8
Use Natural Ventilation Pressures	No
Warn On Direction Change	No
Water Suspension Checking	No
Water Suspension Lower Limit	7.0 m/s
Water suspension minimum length	15.0
Water Suspension Upper Limit	12.0 m/s
Zero Flow Limit	0.100 m3/s

Figure 12-3 Ventsim Visual™ Settings

Allowable error **Defines the level of accuracy** Ventsim must resolve down to before an acceptable solution is displayed. This should normally be set to less than 0.1 m3/s error. If a final analysis is required it may be advisable to set this to 0.01 m3/s or lower. The smaller the value, the more accurate the simulation process, but the longer it may take.

Auto simulation **Automatically performs an airflow simulation** after every modification to a model. This will conveniently display airflow amounts and directions without having to simulate the model. For large models, or models undergoing extensive modifications, it may be preferable to turn this function off, as it will slow down editing and view functions.

Compressible Airflows **[Advanced]** **Use compressible airflow simulation techniques.**

Compressible airflow has a significant influence when simulating deeper mines. In deeper mines (greater than 500m) or when heat simulation is used, it is recommended that compressible airflow be set to **True**.

When set to **True**, Ventsim Visual™ will assume compressible air, and adjust air densities, volumes and fan curves according to airway depth and corresponding density. In the ***Advanced*** version, temperature effects on density are also taken into account when *Heat* simulation is *run* in conjunction with air simulation.

Airflows and fan curve performance after simulation is shown according to the density of air at the location of the airway.

Density Adjust Friction Factors **Enables the simulation to adjust the friction factors to the local airway density**. As resistance is a factor of friction, this will in turn adjust the airway resistance value. This setting is set to YES by default.

When set to YES, all preset friction factors are assumed to be specified at a standard density of 1.2kg/m3. If compressible airflows are enabled, the factor will be adjusted to the simulated local air density, otherwise the factor is adjusted to the standard environment density setting.

If this setting is not enabled or the airway EDIT form has set the value to 'Already Adjusted', then the actual value entered in the preset will not be adjusted.

Density Adjust Resistance Factors **Enables the simulation to adjust the preset resistance values to the local airway density**. Preset resistance values do not use friction factors, therefore any friction factor setting is ignored.

When set to YES, all preset resistances are assumed to be specified at a standard sea level density (1.2kg/m3) and will be adjusted to suit the local airway conditions. If compressible airflows are enabled, the preset value will be adjusted to the simulated local air density, otherwise the value is adjusted to the standard environment density setting.

If this setting is not enabled or the airway EDIT form has set the value to 'Already Adjusted', then the actual value entered in the preset will be used.

HINT : Density adjusted friction and resistance values are a potential source of confusion. Most text books will quote friction and resistance values standardized to a 1.2kg/m3 air density. If standard values are used, ENSURE that both of the Density Adjust options are set to YES

If resistance or friction values are measured locally however, then the values obtained are only valid for the density at which they are measured. To use measured values in Ventsim, you will need to consider one of the following options.

OPTION 1 : If all preset values are measured at the true mine density and will not be used or duplicated elsewhere in the mine, then simply set the " density adjust" setting for resistance and/or friction values to 'NO'

OPTION 2 : If only some values are measured and other values are standardized to 1.2kg/m3, then you will need to use the EDIT form setting to set individual airways to 'Already Adjusted" (the check box next to the resistance or friction value)

OPTION 3 : To avoid the potential confusion of Option 2, you may want to simply convert all of your measured values (at the local mine density) to a 1.2kg/m3 standard and set both settings to YES. This also has the benefit of allowing the setting to be used elsewhere in the mine at different densities.

Fan Reverse PFactor, Fan Reverse QFactor **Defines the default reverse fan performance** relative to the original fan curve for the pressure and quantity of a fan running in reverse. These factors decrease the performance of fans set to run in reverse (for emergencies for example) in the EDIT box. Note that the default values may be overridden by values directly placed in the Fan Database for individual fans.

Ignore Warnings **[TRUE]** Ventsim Visual™ will ignore all warnings related to No *Entry or No Exit* errors found during simulation (airways with no other airways joining)

[FALSE] Ventsim Visual™ will only ignore airways which have been set to *Allow Closed End* in the *Edit* box. Any other 'orphaned' airways will cause the simulation to show warnings.

Iterations Sets the number of attempts Ventsim Visual™ can take to achieve an acceptable error, before the program abandons the simulation process.

Maximum Simulation Pressure The maximum pressure the simulation will allow between airways before a simulation error is reported. This error may indicate unreasonable fixed flows or resistances which interact and cause large pressure changes in the model.

Mesh Surface Priority Modifies the Ventsim Visual™ simulation algorithm to give mesh forming priority to surface connected airways. This normally ensure rapid solving of model simulations, however for models with extensive surface connected airways this may cause simulation balancing issues, and turning off this option may give better results.

Shock Loss Type **Defines the shock loss method to use.** Ventsim Visual™ can be set to calculate shock losses using the equivalent length method, or the shock factor (X) method. Shock loss calculations are necessary to estimate pressure loss due to air turbulence cause by a change in airway direction, a junction or a change in airway size. Note that changing this value in an existing model will result in Ventsim Visual™ requesting to recalculate the shock losses using the alternative system.

The equivalent length method requires the user to estimate an equivalent extra airway length required to approximate pressure loss due to shock.

The shock factor (X) method uses a calculated factor derived from both empirical and calculated changes in airway areas and velocities. Both methods are described in any number of ventilation texts.

Once the method is set, the Edit Box will require an appropriate shock loss value for each airway. The Edit Box can accept a manually entered number, but also has a number of preset values, as well as an AUTO function which will force Ventsim Visual™ to attempt to calculate a shock loss factor or an equivalent length.

Stop Resistance **Defines the minimum resistance** at which Ventsim Visual™ will completely stop all airflow in an airway. All preset resistances above this value will cause airflow in the set airway to completely stop. Only one Preset Resistance value should be greater than the Stop Resistance value. This function artificially restricts airflow and has the potential to cause simulation problems if used on too many airways. The simulation will check and ensure that only one (or nil) preset resistances are greater than this value.

Use Natural Ventilation Pressures **[TRUE]** Forces Ventsim to calculate natural ventilation pressures derived from air heat and density differences in the underground model. Natural ventilation pressures can sometimes produce unstable simulation air flows due to dynamic changes in airflow affecting subsequent heat balance simulations. This is discussed further in the *Heat Simulation* section. If this problem impacts heat simulation, providing natural ventilation pressures are not critical it is suggested to set to it to *False* to produce a stable simulation.

[FALSE] Ignore natural ventilation pressures. Where heat simulation is not required, or natural ventilation pressures are not likely to be significant in a mine, it is suggested that this setting be set to FALSE.

Warn On Change Direction If set to TRUE, and an airway is specified in the EDIT form with a FIXED DIRECTION, Ventsim Visual™ compares airway directions before and after a simulation and alerts the user which airways have airflow that has changed direction during simulation.

Water Suspension Checking If set to TRUE, Ventsim Visual™ will perform a check on all up casting vertical or semi vertical (>45 degrees) airways. The water suspension phenomena occurs on water droplets where the up casting air velocity friction is counteracted by gravitational forces, forming a suspended column of water droplets which can greatly increase shaft resistance and pressure. This can only be overcome by reducing airflow velocity allowing water to fall to the shaft bottom, or

increasing velocity to carry the water out of the top of the shaft. The exact critical velocity depends on shaft size and geometry, as well as water droplet size and geometry of entry into the shaft.

Water Suspension Upper and Lower Velocity The upper and lower limits at which Ventsim Visual™ will flag a warning if water suspension checking is optioned. Warnings do not affect simulation, but simply alert users to potential problem areas.

Water Suspension Minimum Length Water suspension is unlikely to be a problem in shorter shafts. This setting allows the simulation to ignore shafts that are less than a defined length.

Zero Flow Limit The flow at which Ventsim Visual™ assumes 'zero' flow. This function does not directly affect simulation, and is simply used to determine whether airways are displayed when the 'zero flow' graphical option is used to hide airways with no flow.

12.4.2. Contaminants

The default contaminant values and factors to use in simulation. In most cases these values can be overridden in the Edit > Contaminant box.



Figure 12-4 Simulation Contaminant Settings

Contamination Unit **An arbitrary unit defining the volume concentration value of the contaminant simulation.** Ventsim defaults to a unit-less value, which normally represents a percentage, however any volumetric portion unit such as ppm or mg/m3 could be used. Results of the simulation shown will be representative of the original value entered in the contamination value field.

Default Contamination Value **The default amount of contamination to place** in an airway if the contaminant tool button is clicked. For steady state simulation, this would normally be the maximum concentration expected through the model unless recirculation or upstream contaminant sources are present.

For dynamic state simulation, this should be considered the average concentration of the contaminant volume to be cleared.

Diesel Particulate Emissions The default diesel emission factor to use, if the preset heat sources do not have a specified factor. It is normally recommended that preset heat sources each have their own defined diesel particulate emission value. See DPM Simulation for further information.

Dynamic Contaminant Threshold **The value at which dynamic contaminant simulation will stop** if every airway in the mine is below this number. It is suggested this threshold should be set to a number equivalent to safe access for the area.

12.4.1. Dynamic Simulation



Dynamic simulation factors control simulation parameter required during dynamic simulation or when using the VentFIRE™ option.

Dynamic Increment The increment at which Ventsim will advance the dynamic simulation. Smaller increments result in more accurate simulation and greater sub cell formation, however will take proportionally longer to simulate.

Warning – because of the way sub-cells work, it is not recommended to use large increments, as this will result in a loss of fidelity and accuracy in dynamic modelling. If airflow travels the length of an airway faster than the time increment, then the movement of cells through that airway is capped at the time increment, resulting in a small inaccuracy in time calculated to travel through the airway. Extensive occurrences of airways like this will cause simulation inaccuracies, generally resulting in slower dispersion times than actual.

Chasm Consulting recommended increments of one second (or less) where possible, and does not recommend increments more than 10 seconds for most conventional models.

Frequency Airflow Simulation The frequency per increment at which airflow simulation will occur if selected. For example, a frequency of '10' will perform an airflow simulation every 10 dynamic increments. Airflow simulation is an intensive calculation and for larger models it is recommended to increase the frequency factor (which will decrease the actual frequency) of airflow simulation to reduce simulation time.

Frequency Log Data The frequency per increment at which data from the simulation will be collected for airways with a monitor in place. For example, a frequency of '10' will collect data once every 10 increments.

Frequency Screen Update The frequency at which the screen will be updated and graphically show the progress of the simulation. For example, a frequency of '10' will display the graphics every 10 increments iterations. Lower numbers will result in a smooth display update, but will slow down simulation, particularly for large models.

Maximum Data Logs The number of data points available for recording monitor location results during dynamic simulation. For length simulations or models with a large number of monitors, this may need to be increased. If a simulation exceeds the available number of points, it will ignore the

overflow.

Maximum Subcells The number of sub cell divisions that airways are divided into during dynamic simulation. Each sub cell moves independently through a model during simulation, collecting gases, heat, and contaminants. Cells movements and speed is controlled by the air simulation.

> Note : Ventsim will always target the maximum number of sub cells, however the number of cells cannot be more than the time it takes to travel one increment of time. Therefore, for example if an airway passes air from start to end in 10 seconds, and the dynamic increment is 5 seconds, then a maximum of only two sub cells could be placed in the airway. Smaller dynamic increments will generally allow more sub cells to be used, resulting in more accurate, but slower simulation.

Simulation Pause (ms) For small models, the simulation may progress too fast to visually track changes. A simulation pause (in milliseconds) can be entered to slow simulation down. For larger models, it is suggested to keep this pause to zero (0) to prevent unnecessary simulation delays.

Simulation Total Time The time period for a simulation to complete (in seconds). For example, 7200 is equivalent to running the dynamic simulation for two (2) hours. At the end of the simulation time, Ventsim will ask if the user wishes to continue the simulation.

12.4.1. Simulation Environment [ADVANCED]

The environment factors describe values used by physical items within the model. They are critical to identify the base starting points of a ventilation simulation, or providing default air or heat simulation parameters to airways that do not have specific values set.

Environment	
Air Density Network Environment	**1.20 kg/m3**
Airway Age	**5.00 year**
Current Year	**2010.63**
Geothermal Gradient	**2.5 C/100m**
Rock Density (optional if diffusivity set	**2,700 kg/m3**
Rock Specific Heat	**790.0 J/kgC**
Rock Thermal Conductivity	**2.00 W/m/C**
Rock Thermal Diffusivity	**0.938 m2/s 10-6**
Rock Wetness Fraction	**0.15**
Surface Elevation of MineGrid	**600.0 m**
Surface Pressure Barometric	**101.0 kPa**
Surface RockTemp	**30.0 C**
Surface Temp Adjust	Yes
Surface Temp Wet Bulb	**24.0 C**
Surface Temperature Dry Bulb	**34.0 C**

Figure 12-5 Simulation Environment Settings

Air Density Model Environment **Defines the default air density** to use in the model if incompressible flows are used (this is standard behaviour with Ventsim Visual™ Standard and optional with Ventsim Visual™ Advanced). All airways, resistance, friction factors and fan curves will be automatically adjusted to this air density. There is no requirement to individually adjust fan curves manually – any fan curves simulated will be adjusted from the fan database defined curve density, and will show the adjusted curve in the Edit > Fan form.

Ventsim assumes a standard density of 1.2 kg/m3 for predefined friction factors and resistances. Unless specified otherwise, these factors are adjusted to the density specified in this option.

Note that if Compressible Flows are used, the model air densities will be different through the model. Compressible airflow simulation ignores this value and uses the Surface Barometric pressure value as a basis to calculate air densities. Setting this value with Compressible Flow set to 'ON' will automatically set the surface barometric pressure based on the entered value and the wet and dry bulb surface temperature settings (below). The air density of the airways through the model is based on the barometric and fan pressure at each location, and the calculated heat temperatures.

Current Year **The calendar year at which the simulation takes place.**

Ventsim Visual™ uses this value to calculate the age of an airway underground, if the individual airway age is entered as a calendar year (such as '2005' in the EDIT box). Where an airway age is entered as a time value (such as '3.5' years), the Current Year value is ignored.

HINT Where true airway ages have been entered as a calendar year within a model, the Current Year setting is useful for 'ageing' a mine and determining future cooling requirements. Heat flow from virgin rock strata decreases exponentially over time as the rock is cooled, and future cooling requirements can potentially be lower than current cooling requirements as a result.

Geothermal Gradient **The rate at which rock increases in temperature at depth**. This is assumed to be a linear value. Geothermal gradients show significant differences at different points around the earth, and can be as low as 1 degree Celsius per 100m to more than 10 degrees Celsius per 100m. This value should always be adjusted to suit the conditions at or near your mine.

HINT In some cases, the temperature gradient may not be close to linear, particularly in near surface portions of the mine. The near surface rock temperature may be influence heavily by climatic conditions on the surface. The best approach is to calculate to gradient over the unaffected deeper underground portion of the underground mine (which a subject to the majority of heat influence), and project this temperature gradient to the surface elevation. Enter the 'Surface Rock Temperature' setting as this calculated value, not the true surface rock temperature.

Orebody Type	Degrees C/100m		Degrees F/100ft	
	Min	Max	Min	Max
Copper Ore body	2.5	7.7	1.4	4.2
Carboniferous	2.0	5.0	1.1	2.7
Clays	3.3	3.3	1.8	1.8
Limestone	1.8	1.8	1.0	1.0
Sandstone	1.7	3.3	0.9	1.8
Dolerite	3.0	3.0	1.7	1.7
Quartzite	0.8	1.5	0.5	0.8

Potash Low Grade	1.3	1.7	0.7	0.9
Potash High Grade	0.8	1.3	0.5	0.7
Halite Low Grade	1.4	4.0	0.8	2.2
Halite High Grade	1.0	1.4	0.5	0.8

Table 12-1 Examples of Geothermal Gradients found in areas around the world

Average Age **The Default Age of an airway opening in years**. Airways without a specified age set in the ***Edit Box***, will be assigned this default airway age. Establishing airway age allows Ventsim Visual™ to more accurately calculate geothermal heat flow into an airway. Geothermal heat flow decreases with airway opening age.

Wetness Fraction **The default fraction of airway rock surface that is wet**. Most rock surfaces underground have some degree of moisture. The wetness fraction defines what average portion of rock surfaces are considered wet. A value of 0.01 would define a very dry airway, while a value of 1.0 would define a fully wet airway. This value will be assigned to airways without a set wetness fraction from the ***Edit Box***, and directly affects the amount of moisture available to evaporate into the air passing the rock surface.

Rock Density **The default density of rock underground**. This value is applied to an airway, if it has not already been set in the airway Edit Box. Rock density is a property which describes the mass of rock per unit volume. Rock density is used by Ventsim to calculate the thermal diffusivity of rock material. Rock Density is not required if thermal diffusivity has already been set. If this value is changed, the user will be prompted to allow Ventsim to auto calculate the rock diffusivity.

Rock Specific Heat **The default Specific Heat of rock underground**. This value is applied to an airway, if it has not already been set in the Edit Box. Rock Specific heat describes how much heat must be absorbed or emitted to raise or lower the rock temperature.

Thermal Diffusivity **The default Thermal Diffusivity of rock underground**. This value is applied to an airway, if it has not already been set in the Edit Box. Rock Thermal Diffusivity is a property which describes the ability of rock to diffuse or transmit contained heat over a unit area per unit of time. Rock with high thermal diffusivity more rapidly adjusts its temperature to that of the surroundings, because it conducts heat quickly in comparison to its heat capacity or 'thermal bulk'. Because diffusivity is directly related to density, thermal conductivity and specific heat by formula, rock ***thermal diffusivity*** is required only if rock density has not been set. If this value is changed, the user will be prompted to allow Ventsim to auto calculate the rock density.

Rock Thermal Conductivity **The default Rock Thermal Conductivity.**. This value is applied to an airway, if it has not already been set in the Edit Box. Rock Thermal Conductivity is a property which describes the ability of rock to transmit heat through its mass.

Surface Wetbulb Drybulb **The Default Surface Temperature Conditions of air entering a mine.** All air intakes into the mine are assigned the default surface temperatures. The temperatures and Surface Barometric Pressure are used to calculate the surface air density.

HINT: In rare cases, a mine may have multiple intake airways with a range of elevations so great that different temperatures may be present at each intake. As the Surface Barometric pressure is defined for a single Surface Elevation, Barometric Pressures will be correctly recalculated for differing intake elevations;

however temperatures may need to be manually corrected. Temperatures can be adjusted by place a heat or cooling source at the inlet of intakes to produce differing temperatures.

Surface Pressure Barometric **The Barometric Air Pressure at the Surface Elevation.**. The surface barometric pressure is important as Ventsim Visual™ calculates mine air densities from the surface barometric pressure and wet and dry bulb temperatures.

Surface Elevation **The elevation (or 'reduced level') where a specified point in the mine exits the surface**. All other surface related settings (such as surface temperatures, pressures and rock temperatures) are assumed to be at this elevation.

If this value is set to zero (0), Ventsim will search and use the highest point in the model.

Surface Rock Temp **The temperature of virgin rock at the Surface Elevation.** All virgin rock temperatures underground are calculated from this base elevation by using the Geothermal Gradient.

12.4.2. Examples of Rock Properties

Rock Type	Thermal conductivity	Specific Heat	Thermal Diffusivity
	W/mC	J/kgC	m2/s 10-6
basalt	1.80	840	0.74
coal	0.33	1300	0.20
dunite	4.30	820	1.64
gabbro	2.10	800	0.97
gneiss	2.90	800	1.29
granite	3.00	790	1.41
limestone	1.30	840	0.64
magnetite	4.41	600	2.10
marble	2.60	880	1.18
potash	3.50	690	2.55
quartzite	5.25	800	2.43
quartzite	3.00	800	1.39
rock salt	4.48	880	2.04
sandstone	1.70	920	0.71
shale	1.23	850	0.55

Table 12-2 Metric Examples of Airway Rock Physical Parameters

Rock Type	Thermal conductivity	Specific Heat	Thermal Diffusivity
	Btu/h/ftF	Btu/lbF	ft2/h
basalt	1.04	0.20	0.029
coal	0.19	0.31	0.008
dunite	2.48	0.20	0.064
gabbro	1.21	0.19	0.038
gneiss	1.68	0.19	0.050

granite	1.73	0.19	0.055
limestone	0.75	0.20	0.025
magnetite	2.55	0.14	0.081
marble	1.50	0.21	0.046
quartzite	3.03	0.19	0.094
potash	2.02	0.18	0.099
quartzite	1.73	0.19	0.054
rock salt	2.59	0.21	0.079
sandstone	0.98	0.22	0.028
shale	0.71	0.20	0.021

Table 12-3 Imperial Examples of Airway Rock Physical Parameters

Warning – These are examples only. Rock characteristics vary widely for different rock types and locations. Where possible, characteristics should be measured by laboratory analysis.

12.4.3. Explosive

Contaminant Density **The gas density of the contaminant gas of concern from the explosive reaction.** For example, if Carbon Monoxide is the main gas of concern, then a gas density of 1.16 kg/m3 could be used. Ventsim uses this density figure to convert the yield mass into a volume.

Contaminant Yield Amount The **mass ratio of contaminant (of concern) produced per equivalent mass of explosive** detonated. For example, if Carbon Monoxide was the gas of concern in an explosive detonation, tests by Orica reveal that approximately 0.015 kg of carbon monoxide is produced for every 1.0kg of explosive detonated. Therefore the contaminant yield for CO is 0.015.

Further information regarding contaminant simulation can be found in the Run > Contaminant section.

12.4.4. Fire [PREMIUM]



Combustion Efficiency **The portion of fuel converted to heat** defined under the 'Heat of Combustion' of the fuel source.

> Note: The combustion efficiency of an underground fuel fire will generally be less than 100%. Combustion efficiency generally depends on the availability of oxygen to all parts of the fire and the heat generated by the fire. In many cases, the efficiency may be a little as 75% or less, although if this is not known, using 100% is considered a more conservative approach.

Equivalence Ratio Shift **The amount to shift the equivalence ratio towards or beyond the fuel rich** gas generating zone.

Equivalence ratio is the ratio of available oxygen to the fuel burn rate to produce a perfect stoichiometric reaction. An equivalent ratio of '1' would mean that there was exactly enough oxygen provided to perfectly burn a defined mass of fuel. An equivalence ratio of less than one would mean that the amount of oxygen exceeds the rate at which the fuel consumes it (oxygen rich fire). An equivalence ratio of greater than one means that insufficient oxygen is available to burn the fuel mass, resulting in incomplete combustion gases and pyrolised hydrocarbons (fuel rich fire).

> Note; For perfect combustion in an ideal environment, fires produce very little carbon monoxide where equivalent ratios are less than 0.5. The rate of carbon monoxide production increases as the equivalent ratio approaches 1.0, and the yield rate generally peaks at a ratio of around 1.3. Ventsim will alter the generation of CO2 and CO gases based on the equivalence ratio, and the combustion yield factors used in the preset.
>
> For an underground fire in a confined place at extreme temperatures, even in the presence of a theoretically excess amount of oxygen, a fire can produce significant amounts of incomplete or 'chemically reduced' combustion products. To force Ventsim to produce higher amounts of carbon monoxide, the equivalence ratio can be moved towards 'fuel rich' results by adding a shift factor. If in doubt as to the behaviour of the fire, it is suggested to use a shift factor of '1' or more to force the maximum amount of Carbon Monoxide to be produced.

Limit O2 Upper Lower **Ventsim will modify the defined fuel burn rate based** on the oxygen limits to produce a more realistic fuel burn profile.

For example, most open flame sources will diminish significantly below 15% oxygen, and continue diminishing as oxygen levels reduce further. Between the upper and lower limit, Ventsim will limit the fuel burn to proportionally less than the defined amount set in the airway, reducing combustion rates linearly between the upper and lower limits. Combustion of the fuel will cease below the lower oxygen limit.

To disable this behaviour, set both limits to zero (0).

Maximum moisture release rate **Controls the maximum flow of moisture to a rock surface** available for evaporative cooling in millimetres (mm) per second surface coverage. A default of 0.1mm is suggested.

Wetness fraction settings for rock influences evaporative cooling of airflow flowing past a rock surface. In the event of a fire, the rate of evaporation can easily exceed the rate at which water will replenish the rock surface. Therefore it is important to limit the flow of water otherwise the hot air from a fire will be artificially cooled at a rate much greater than would be possible in a real life scenario.

Residual Heat % **Maintains a minimum flow of heat from the fire source**, even if insufficient oxygen causes combustion rates to fall below this level.

Heat from a fire does not immediately cease if the combustion is reduced or ceased by lack of oxygen. Significant amounts of heat may be stored within the combustible structure mass and may continue to be released even without direct combustion. To ensure the simulation

continues to receive at least some heat during periods of low oxygen, this value can be set at a portion of the normal full combustible heat level.

Rock Absorptivity Age **The modified radial heat transfer age coefficient Ventsim uses for fire simulation.**

Normal steady state heat simulation requires a rock exposure age (in years) to modify the exposed rock mass to a temperature closer to the long term air temperature.

For fire simulation, the rock mass surrounding the immediate airway is assumed to have cooled close to a long term air average, and the fire simulation assumes a rapid transfer of heat from the hot air back into the cooled rock mass. To facilitate this rapid transfer, the rock must be assumed in the (Gibson's heat) transfer algorithm to be 'freshly' exposed again.

Note: A default value of 60 seconds is suggested, which provides rapid absorption for intense heat changes. Values lower than this can cause over prediction of heat absorption of very hot air.

For non-fire dynamic simulations, heat calculations can sometimes slightly exceed steady state estimates. If dynamic simulations are required to closely match steady state simulations, it is suggested to increase this value substantially (the second equivalents of days, weeks or even months).

Rock Boundary Heat Flux Limit **The thickness of rock which is directly influenced from short term dynamic heat changes.**

This method allows an exposed surface rock layer of 'skin' to both store and release heat from rapid heat changes.

While actual rock in this situation will theoretically build up a complex graduated heat profile based on changing heat and air velocity, this simplified method assumes a single homogenous rock mass skin that absorbs heat evenly, but beyond which no significant heat passes. For short term dynamic simulation, this is a reasonable assumption.

INFO : As this 'skin layer' heats and becomes closer to the temperature of the heated airflow, the rate of heat absorption will decrease.

Conversely, if the fire heat reduces and air temperatures fall below the heated rock surface, this rock skin layer can rapidly release heat back into the airway airflow during simulation.

12.4.5. Gas

Use Gas Density for Air Simulation. Uses the relative density of different gas compositions to apply natural ventilation pressures to airflow during simulation. Gas compositions may be set using the gas options in the EDIT box, or from VentFIRE™ simulations.

12.4.6. Heat [ADVANCED]

Adjusts settings which directly influence how the heat simulation performs.



Figure 12-6 Simulation Heat Settings

Diesel Efficiency The efficiency at which diesel engine mechanical output is derived from the total heat of combustion of the fuel source. Ventsim uses this value to convert diesel engine power sources into heat during simulation. Ventsim assumes by default all diesel engine output power AND wasted inefficiencies enter the airflow as latent and sensible heat. The heat calculated from a diesel engine is

$$HEAT\ Released = \frac{Diesel\ Power}{Efficiency}$$

Heat Divisions Min/Max **Airway segment divisions for heat calculations.**

The heat simulation process in Ventsim Visual™ progressively calculates heat along each airway by dividing it into smaller sections. Where airflow is very slow or an airway is very long, this allows the psychrometric process to continually adjust pressures, temperatures and moisture content, resulting in a more accurate simulation. Ventsim Visual™ automatically adjusts the number of divisions according to airflow velocity, airway length and heat inputs. The number of divisions used is restricted by the **min** and **max** values in the settings. Higher division values will theoretically give more accurate heat estimates but will increase the time required for simulation.

Multi Heat Iterations **Performs multiple airflow and heat simulations.**

When set to more than one (1) performs multiple heat and airflow simulations, adjusting densities and airflows between each simulation. Manually pressing the HEAT simulation button has the same effect.

Heat simulation in Ventsim Visual™ Advanced is performed as two discrete simulations, first as an airflow balance, followed by a heat balance simulation. While the mass flow balance from the airflow simulation is kept constant during heat simulation, the new temperatures and

air densities calculated after heat simulation, result in a theoretical mass imbalance of airflows. This can be corrected by a subsequent airflow simulation; however subsequent heat simulations will again affect the balance. This imbalance normally reduces with subsequent simulations, as temperatures and airflow changes reach equilibrium.

Multiple pass iterations can be set which will automatically force Ventsim Visual™ to simulate the model a number of times, to account for some of the potential imbalance. This will significantly slow down simulation time. Iteration values larger than one are usually unnecessary if a model has already been heat balanced, or if the HEAT simulation button has already been pressed a number of times.

HINT Performing a multiple pass heat simulation may have value if the model shows some heat instability (changes in temperatures between simulations). Heat instability is often caused by unstable natural ventilation changes driven by conflicting changes in airflow, strata heat and evaporation.

For example a heat source which causes an increase in temperature may cause an increase in airflow due to natural ventilation – in subsequent simulations, the higher airflow causes lesser temperature increase from the heat source, which in turn reduces the airflow due to natural ventilation. Evaporation from strata moisture may also causing conflicting density changes, with strata heat density changes offset by cooling evaporation. The process may then oscillate between solutions for each heat simulation. As a final pass performing a multiple pass simulation of 10 or 20 (which may take a long time) may help resolve this instability.

Heat Iterations **Limits the number of internal iterations** permitted by Ventsim Visual™ to converge and find an acceptable heat solution. Where recirculation occurs or high numbers of very low airflows are present, a simulation may take a large number of iterations to fully balance. In most cases, the main airflows will quickly balance, and even if the simulation fails to complete within the set number of iterations, this will usually be in the low flow airways which have little effect on the main flow airways. The status bar at the base of the Ventsim Visual™ window will show the progress of a heat simulation, including the number of iterations and the heat balance errors. Increasing the number of iterations may help resolved unbalanced models, but will take longer to simulate.

HINT A leading cause of heat flow convergence issues is recirculating airways in low flow airways due to natural ventilation pressures. Natural ventilation pressures can create internal 'eddies' of air in disused or low flow airways which can affect heat simulation convergence. To prevent this, and speed up heat simulation, either turn off natural ventilation simulation (if natural vent pressures are not significant) or block disused airways so they simulate as no flow

Water to Diesel Ratio For diesel heat sources, **this value defines the amount of water emitted to the air as latent heat** is per unit weight of diesel fuel consumed. Although the theoretical combustion reaction portion of water produced to fuel consumed is only around 1.1, the operation of a diesel machine in a mine environment results in a greater release of water into the air due to accelerated evaporation of water around the machine (from a wet roadway or walls for example), compounded by other sources such as handling of moist or wet material, wet exhaust scrubbers and cooling systems used by the machine, result in a much higher value. A value of five (5) or more is generally recognised as giving a more realistic result for water introduced to the air by mobile machines. Stationary machines may be closer to the theoretical value.

The default water to diesel ratio is used on all diesel sources in the model. To use values other than default, the sensible and latent heat will need to be entered separately instead of a single diesel heat source.

Diesel Particle Emissions **Describes the default amount of diesel particles emitted from a diesel engine, per unit of diesel engine power**. This value is applied to diesel heat sources placed in a model, to assist in diesel particulate matter (DPM) simulation for the model. The value is highly dependent on

the type of diesel engines, catalytic converters and scrubbers being used on the exhaust, as well as the type of diesel fuel used. In most cases, tests will need to be done on engine exhausts, or information gained from diesel engine manufacturers to find the correct value to use. Ventsim Visual™ will apply this default value to diesel sources which have not been assigned a specific emission rate. Specific rates for diesel equipment and airways that will override this default value can be assigned in the Presets or in the Edit box.

Temperature Limit **The temperature limit above which Ventsim Visual™ will halt simulation and display an error if it occurs**. Temperature limits can be exceeded when too higher heat input is placed in an airway with not enough airflow.

Heat simulation uses a number of empirical formulas which are designed to work within a specific temperature range. In general, temperatures above 70 degrees centigrade will start to result in a reduction of accuracy of heat estimation.

Mass Flow Limit **The minimum mass flow that Ventsim Visual™ will perform a heat simulation on**. Below this limit, Ventsim will assume the air is stationary, and adopt the local virgin rock temperatures as the air temperature. This value must be set above zero, as portions of the program which calculate heat and moisture derived from rock surfaces must have some airflow velocity to work. While there is some potential for heat imbalance errors by not taking into account low flow airways, it is generally small due to the limited heat energy flow able to be carried by these low flow airways.

Refrigeration COP **The ratio of output refrigeration power (kWR)** generated by the refrigeration heat exchange process, versus the input electrical power (kW) required to produce this heat exchange. This factor is not used by the simulation, by rather by the power and cost calculation of a model in the Summary section.

.

Temperature Accuracy **Sets the temperature balance limit** Ventsim Visual™ must achieve for all airway mixing at junctions in a model, to consider a simulation as balanced. If the balance is not achieved for EVERY airway and junction, iteration is performed until the iteration limit is reached or temperatures are resolved.

HINT The smaller the temperature accuracy set, the longer a simulation may take to complete. In most cases, the vast majority of airways will fall well under this limit, and any temperature accuracy issues will be limited by very low flowing airways which have little impact on the main model.

Maximum Heat Input **Limits the amount of heat** that can be put into a single airway. This is mainly included as a check to ensure excessive heat is not placed in an airway (such as a point heat source value accidently being entered as a linear heat value).

12.4.7. Recirculation

Recirculated Airway Limit [Advanced] The number of recirculated airways beyond which Ventsim will first ask permission to simulate exact recirculation amounts. The simulation routine to calculate individual airway recirculation is complex and time consuming. If there are more than (say) 500 airways, this may take a minute or two to simulate. Therefore the option will be given to abandon the simulation, or simply show the airway which recirculate without actual % amounts. On faster computers, it may be desirable to life this limit, to prevent Ventsim pausing and asking permission.

Recirculation Limit Volume [Advanced] The volume of air that is allowed to recirculate before the Check Recirculation routine flags a warning and initiates a full recirculation check.

12.5. Ventsim System Settings

Ventsim Program settings control over-arching settings which influence all parts of the program.



Figure 12-7 Ventsim Visual™ General Settings

Unit Type **The type of units to use in Ventsim Visual**. The program operates natively in SI Metric, with underlying calculations performed in metric units. To display imperial values and accept imperial input, set the unit type to *Imperial*. The imperial setting uses a conversion table to calculate the conversion from metric, and can be customised to suit mine preferences. The imperial conversion table can even be set to use a combination of Metric values by setting the program to IMPERIAL and then using the SETTINGS > UNITS menu to individually specify what units will remain ALWAYS METRIC.

Warning – the conversion table has set limits of decimal accuracy to convert from metric to imperial and back again. If the decimal accuracy is too low, some accuracy may be lost in the conversion process, and the value input as an Imperial number, may be returned slightly differently.

Use Mass Flow Replaces fixed flow input in airway edit forms, with a fixed mass flow option. Some countries utilise mass flows to specify air quantities in mine ventilation.

Chapter

13

13 HEAT ASSISTANT

The heat assistant helps in calculating thermodynamic inputs into the ventilation model. The calculator can quickly establish required cooling, heating or moisture loads, which can then be accepted in the model.

The assistant is also useful for 'pre-conditioning' airflow to a required temperature and humidity to more closely simulate observed conditions underground.

Pressing Accept after any calculation will insert the values into the model airway for future simulation. This will overwrite any existing heat values within the airway.

Warning : The assistant calculates estimates only. In some cases, the assistant utilises an iterative technique, with initial values sourced from the airway currently being edited. The initial values can be changed as desired. Because the simulation process utilises a more detailed, multiple pass approach, taking into consideration surrounding airways and rock heat transfer into the airway, the resulting estimates from the assistant may not always equal the values ultimately calculated in the simulator.

The assistant contains five (5) tabs.

13.1.1. Airflow # 1

Calculates the required heat loads to condition air from one state to another. The values are returned as sensible and latent heat estimates.



Figure 13-1 Airflow Calculator # 1

Values returned for sensible heat are generally (+ve) for heating or (-ve) for cooling. Values returned for latent heat are generally (+ve) for humidification or (-ve) for de-humidification or drying of air. The word 'generally' has been included as differences in pressure can influence the amount of sensible and latent heat available in the process.

13.1.2. Airflow # 2



Figure 13-2 Airflow Calculator # 2

Similar to the Airflow #1 calculator, this calculates the required heat loads to condition air from one state to another, but instead returns values as sensible and an evaporated moisture flow estimate. This may be useful for calculating moisture being evaporated from underground processes such as decline dust suppression sprays, drill machine activity or evaporative cooling chambers.

13.1.3. Diesel Engine

Diesel engine heat loads can be more accurately calculated by considering the environment and utilisation of the diesel engine within the model. The diesel engine calculator assists with this. The output of the calculator is return as an averaged diesel engine output. The corresponding sensible and latent heats are also provided as a reference, however are not transferred to the model as Ventsim Visual™ automatically calculates these values in the model from the diesel power value.



Figure 13-3 Diesel Heat Estimator

Diesel Efficiency The percentage of diesel calorific energy converted into mechanical energy. This diesel efficiency is an estimated value for a typical diesel engine and generally should not be changed unless specifically known for a type of engine or particular type of fuel. The value dictates the amount of heat placed in a model per unit of engine power used.

For example a 200kW rated diesel engine, will consume nearly 600kW in diesel fuel energy, initially rejecting 400kW of waste heat through engine friction and exhaust. In most cases, the remaining 200kW of mechanical power will also be converted to heat through further friction losses, except where the mechanical power may be partially passed to other energy absorbing processes (such as water or transfer of rock uphill). If required, this can be accounted for under the potential energy conversion item.

Utilization Diesel engines underground rarely operate at full power 100% of the time. It is important to consider the actual weighted percentage of time engines are operated at full power to gain the true heat input into the mine model.

For example, a load haul dump unit (LHD) operates continuously, but uses only full power (100%) while loading buckets and hauling up a ramp for 15 minutes per hour, operates at 50% maximum power tramming horizontally or downhill for 30 minutes per hour, and idles at 10% maximum power for the remaining 15 minutes per hour

$$\frac{(15 \times 100\% + 30 \times 50\% + 15 \times 10\%)}{60}$$

=52.5% peak utilisation

Potential Energy Converson In some processes, diesel mechanical engine power can be converted into other useful energies. For example a truck hauling rock up a decline will impart a portion of its mechanical energy into the potential energy difference of the change in elevation of the hauled rock. This can be calculated as a percentage of the mechanical output of the diesel engine, and will reduce the amount of heat input into the model. In most cases, this will only be a small fraction of the diesel engine power, and in most cases can be ignored.

13.1.4. Diesel Fuel

The diesel fuel calculator provides an alternative way to calculate engine power within a ventilation model, overcoming the need to estimate engine utilisation. It calculates diesel engine power by using the calorific heat value of fuel, and back calculating engine power using the diesel efficiency setting in Ventsim (by default 35%).



Figure 13-4 Diesel Fuel Consumption Assistant

By entering the average fuel usage of a diesel engine, Ventsim Visual™ can calculate the equivalent average engine output for use in the model. If this value is derived from actual engine diesel fuel usage of a particular unit in operation (many modern machines automatically record average fuel flow), this therefore already includes time the machine is not operating at full capacity.

As with the previous tab, a portion of the diesel engine power can be included as potential energy to another process. This reduces the effective diesel heat input into the model.

13.1.5. Electric

Similar to the diesel engine calculator, this allows the user to estimate the heat emitting from an electric motor, based on its duty cycle and conversion of work into useful energy.



Figure 13-5 Electric motor heat estimation

13.1.6. Water Flow

The water flow calculator estimates the amount of heat entered or removed from a model from water flow source. It can be used for both hot water and chilled water calculations.



Figure 13-6 Heat Assistant Screen

The Water tab may be useful for estimating;

- **How much cooling power a cooling tower or spray chamber** is producing from a refrigeration water source.. Ventsim Visual™ will calculate how much cooling is being generated from the flow and temperature change of the water into the airflow.

- **How much heat a geothermal water source** may be putting into a model. To calculate the heat input, simply input the average water temperature entering the mine (from a rock fissures for example), and enter the average water temperature and flow exiting the mine (at a pump station discharge for example). Ventsim Visual™ will calculate how much heat is being lost from the water most of which ultimately enters the airflow.

-

Chapter

14

14 FANS

Fans are an important part of the modelling process. Correct entry of data for fan curves describing the pressure and flow performance at different fan duties is essential for accurate simulation.

14.1. Fan Database

The fan database is accessible from the TOOLS > FANS menu. The fan database allows editing, adding and deleting of all fans in the model fan database. Up to one thousand (1000) fans and the associated fan curves may be entered into the fan database. A display for each fan curve and data will be presented when a fan is selected from the display list.

The Edit > copy and paste functions can be used to copy data to or from another program (for example a spreadsheet).





Caution should be taken when deleting or modifying a fan, as any model which may use the deleted fan number, will not simulate correctly.

The fan name is entered or chosen at the top from the pull down menu. To enter a new fan, select *File > New*

At a minimum, fan curve points for quantity and either fan static or total pressure must be entered for each fan. Other curve information such as efficiency and power can also be entered to assist Ventsim Visual™ in estimating fan power and heat.

Density is the air density that the fan curve is specified on the manufactures sheet. IT IS NOT necessarily the air density that the fan in the model will be operated at. In Ventsim Visual™ Advanced, fan performance is adjusted for density changes in the mine. Most manufactures supply fan curves at a standard sea level density (1.2kg/m3), however different densities can be entered for the fan curve if required.

Diameter **Diameter** is an optional parameter describing the exit diameter of a fan. This may be the diameter of the fan casing or an evasé if fitted. Ensure the fan curve entered is for the specific fan configuration (check with your fan manufacture for this). Adding or removing an evasé from a fan for example can significantly change the fan performance within Ventsim (although the fan total pressure curve will remain similar). Where only a static curve is available, the diameter can help estimate velocity pressure from the fan and the associated power consumption.

Where only fan total pressure is entered, the fan diameter can help estimate available fan static pressure, a consideration for the performance of surface exhaust fans. Finally, the fan diameter can also help estimate new curve points for the fan database, if either the fan static or total curve is unavailable. See the fan database section for more information.

> ***Hint: It is recommended that where fan pressure curves are provided without an evasé (which is normally how fan manufacturers provide the curves as mines may mount the fan in different configurations), any evasé effects can be independently modelled by using the edit box options to place an diffuser in the airway.***

Fan speed **Fan speed** is a manufactures reference to the normal speed of the fan operation for the specified fan curve. The number is not directly used during simulation and will not influence simulation outcome. The percentage fan speed can however be adjusted in the EDIT box.

Fan Reversal **Reverse P** and **Reverse Q** modifies performance for fans run backwards for an emergency situation. Most manufactures will not supply these figures as fans are not generally designed to do this (although some fans can be designed to perform better in reverse than others). These figures ideally need to be derived experimentally be measuring actual fan performance with blades running in reverse. Ventsim Visual™ initially defaults to 0.5 for both (50% of maximum pressure and 50% of maximum airflow).

Curve Estimation The method used to estimate curve data between specified fan duty points. The **cubic spline** method estimates a curved data path between fan points. If only a few points of data are available, this may produce a better estimate of fan duty, however the method may be limited by sudden changes in curve data point direction. Ensure sufficient points are available to produce a smooth non-reversing curve.

The **linear method** predicts a straight path between points. This method is slightly faster during simulation, and if the maximum number of fan points (10) are entered, it should provide sufficient accuracy in most cases.

> HINT: It is important that pressure on the curve is not permitted to bend over in a U shape (or upside down U), otherwise the simulation may oscillate between two pressure points. Stall regions of fans should be omitted for this reason.

Comments **Comment box** is included to describe more information about the setup or configuration of the fan. It is not used for simulation.

Point Table **Fan Point Table** : The table will allow direct entry of fan curve data. Fan curves will be constructed as data is entered. Points can be submitted non-sequentially, and will be automatically rearranged when the fan is re-loaded or saved.

As a minimum, Ventsim requires at least airflow, and a Fan Static Pressure or Fan Total Pressure point. Other information such as efficiency or power can be calculated by Ventsim using default settings, however it is recommended to enter one of these values if available to enable more accurate power and heat calculations.

To calculate fan power within a model, Ventsim Visual™ needs either a fan efficiency curve or a fan power curve. If neither of these curves is available, the default fan efficiency will be used from the Settings menu. If *both* efficiency and power curves are entered, Ventsim Visual™ will *preferentially* use the fan power curve to calculate absorbed fan power.

14.1.1. Entering Data

To construct a fan database from an existing fan manufactures curve, follow the steps below.

1. Identify the type of fan pressure curve used, the fan configuration and exit diameter, and the air density the fan curve is established at.

2. Divide the curve into up to ten (10) points. Do not include the STALL region of the curve in the fan database. Entering the stall region of a fan may result in an unstable model simulation at it oscillates between the two pressure and volume flow states..

3. Note that less than ten (10) points can be entered if desired, however this will increase interpolation errors between points resulting in a less accurate simulation. A minimum of five (5) points is recommended.

4. Enter the curve points and fan information in the Fan Database edit form.

5. To utilise the fan within the model, ensure the Fan Total Pressure method is selected in the Settings, and use the Edit Box to place a fan within an airway.

14.2. Fan Pressure Types

Where both Fan Static and Fan Total pressure curves have been entered for all fans in the database, Ventsim will automatically use Fan Total Pressures for simulation calculations. Unlike Ventsim 2.0, the simulation method is no longer selectable.

Ventsim will only use Fan Static Pressure for simulation if a fan does not contain a Fan Total Pressure curve.

14.2.1. Simulation Handling of Exit Velocity Pressure Losses

Exit Velocity Pressures occur on any airway or fan discharging air to the surface atmosphere. When considering fan pressure requirements, the exit velocity pressure loss is added to the mine resistance system pressure losses to calculate fan total pressure requirements. Fans must therefore provide sufficient total pressure to overcome both the mine resistance and the surface velocity pressure losses.

If only Fan Static Pressure curves are used in a simulation, the exit velocity pressure is ignored.

If some fans have only Fan Static Pressure and others have Fan Total Pressure curves, then Ventsim will simulate using a 'Mixed Pressure' method, where exit velocity pressure are ignored for all airways EXCEPT for surface exits that contain fans with Fan Total Pressure curves.

Total Pressure Method

The use of fan total pressures (fan static and velocity pressure) is considered the technically correct method for simulating airflows, as both static and velocity pressures contribute to airflow through an underground mine. Ventsim Visual™ can help predict a fan total pressure curve from an existing static pressure curve using tools in the Fan Database Editor.

The total pressure method assumes the full fan total pressure is available to 'push or pull' air through a mine. The method also considers system velocity pressure losses to the atmosphere (for example from exhaust shafts) and incorporates these into the simulation. The fan total pressure method relies on the user accurately considering fan exit losses with appropriate diffuser sizes, shock loss factors and resistances, as total fan pressure is never fully available to pressure the underground air flow. Fan outlet configuration, outlet flow direction changes and the inclusion of diffusers (which boost fan static performance and reduce exit losses) or other exit devices such as fan shutters need to be fully considered if they have not been incorporated into the fan curve, otherwise the model may over predict the available pressure and flow for the model.

To use the Fan Total Pressure Method, ensure all fans contain a Fan Total Pressure Curve. If any fans have only a Static Pressure curve, then the simulation will automatically switch to the Static Pressure Method.

Static Pressure Method

A more traditional approach is to use fan static pressure, which assumes that fan velocity pressure is wasted and does not contribute to the system ventilation pressure and flow. While this is not technically correct, this assumption removes some of the criticality of defining accurate exit losses, and while exit losses should still not be ignored, the resulting simulation will provide a more conservative result to simulation estimates of pressure and flow. The Fan Static Pressure (FSP) method ignores system exit velocity pressure losses and for a primary (surface) fan driven model systems, there is negligible difference between the FSP and FTP methods (as the FTP methods considers velocity pressure losses as part of the system pressure). However where underground booster fans contribute to a significant portion of ventilation flow, the difference between the two methods will increase.

To use this method, all fan curves used from the database should have a static pressure component. As with the FTP method, the fan database form has tools to assist the user in estimating FSP curves if not available.

Mixed Pressure Method

The mixed pressure method maintains compatibility with Ventsim Classic 3.9, which allows both pressure types (static and total) to be used for fans in models. The mixed pressure method is similar to the static method, in that it does not consider system velocity pressure exit losses. Fan pressure curve types can be specified for each fan location in the model. This may be of assistance if some static or total pressure curves are not available for the fan, and the user does not wish to estimate a curve. The mixed pressure method is considered to be the least consistent method to use, and should be avoided if possible.

Ventsim Classic 3.9 models will be automatically imported into Ventsim Visual™ as a 'mixed pressure model'. Ventsim 3 will automatically select the pressure simulation method based on the type of fan curve pressures available in the fan database for simulation. The type of simulation method used is stated in the RUN > SUMMARY.

Fans used in Auxiliary Ventilation Duct

Unless discharge losses are manually considered, only Fan Static Pressure curves should be used for duct pressure and airflow calculations, as the velocity pressure exiting the duct is considered wasted.

For this reason, when a fan is placed in a ventilation duct, Ventsim will only use the Fan Static Pressure curve. If only a Fan Total Pressure Curve is available, then Ventsim will attempt to calculate the Fan Static Pressure Curve, based on the fan diameter or area, or if this is not available, from the size of the duct the fan is place in.

Should I Use Static or Total Pressure?

Most fan manufactures supply one or both types of pressure curves. Ventsim Visual™ differs from Ventsim Classic 3.9 in it can use fan total pressures (FTP), fan static pressures (FSP) or a mixture of both.

Using FSP curves will ignore the fan velocity pressure (FVP) portion contribution to model pressures, but will also ignore any system exit velocity losses to surface throughout the model.

Using FTP curves will include the FVP portion, but will include system exit velocity pressure losses as part of the model system total pressure.

The case for Fan Static Pressure Simulation

It is technically correct for simulations to use fan total pressure (FTP) curves for fan installations. Fan total pressure however is not always converted into useful ventilation energy due to outlet losses from fan installation configurations.

Traditionally, Ventsim Classic 3.9 has encouraged users to utilise fan static pressure (FSP) curves for modelling. Using FSP curves excludes the velocity (dynamic) component of fan pressure curve which is therefore assumed not to contribute to the overall system pressures in a model simulation. To partly offset the lack of fan velocity pressure inclusion, the system exit velocity pressures (the velocity pressure loss to the model from air exiting from shafts or other exhaust airways) are also not included by Ventsim Classic 3.9 in calculating overall system pressure. While these two factors partially cancel each other out, using ***Static*** curves for underground fans is likely to give a slightly conservative system pressure and airflow if fan exit (shock) losses are modelled identically for both an FSP and FTP case.

When designing a model, this may be advantageous to provide contingency for design simulations. In addition, use of FSP curves is less reliant on accurately modelling fan exit shock losses, and provides a greater contingency for design airflow. In general, they may be more suitable to use for a less experienced user.

The case for Fan Total Pressure (FTP) Simulation

FTP Simulation will allow Ventsim Visual™ to utilise the full fan total pressure curve for model system pressures. Provided fan exit shock losses are modelled to consider the fan installation and exit airflow orientation, then this method should provide more accurate results. In addition, as Ventsim Visual™ will consider system exit velocity pressures allowing fan exit diameters, airway surface exhaust sizes or evasés sizes are adjusted to simulate the effect of on surface exhaust airways and mine system pressure.

Note: Increasing fan diameters or including diffusers in Ventsim Visual™ for underground installed fans will have no automatic effect on model simulation results, as it will not change the surface velocity pressure exit losses. It may however decrease shock losses at the fan exit, which if modelled in Ventsim Visual™ by changing airway shock loss will result in improved fan performance.

Evasé / Diffuser Hint: If the Fan Total Pressure Method is chosen, the effect of diffuser size on surface exhaust shafts can be examined. Simply click on the surface airway, and select 'diffuser' and place a size large than the fan or airway. Alternatively, you can construct a short enlarged surface connection airway which will produce a similar effect to including an evasé option in an airway.

In Summary

In most cases, if fan exit shock losses are modelled are modelled correctly, the Fan Total Pressure (**FTP)** method is the best option to use.

14.3. Fan Database Menu Items

Estimate Tools Menu The tools menu contains a number of functions to assist in estimating fan static or total fan curves as if either one is unavailable, as well as fan total shaft efficiency and fan absorbed power if either one is unavailable. This may be required if only a Fan Static Pressure (FSP) curve is available, and you wish to simulate the model using a Fan Total Pressure (FTP) curve.

Ventsim Visual™ will use the outlet diameter of the fan to calculate the velocity exit pressure of the fan, and thereby calculate the missing static or total pressure curve.

To estimate absorbed power, Ventsim Visual™ will calculate theoretical power using total pressure and airflow. Note that none of these estimation methods take into account shock losses, resistance and compression factors which will slightly affect calculated pressure and powers. It therefore should be used as a guide only, and is no substitute for an accurate fan manufactures curve if available.

Estimate Fan Curve Quickly estimates 10 evenly spaced points of fan curve duty from as few as 3 entered points. The estimation method will use the Cubic Spline method to add the additional points. This method should only be used if additional fan curve data is not accurately available.

Chapter

15

15 BUILDING A VENTILATION MODEL

A ventilation model must have a number of key components to successfully run.

Some Simple Rules for Constructing a Model are:

- *All airways in a model must be connected at both ends to another airway, unless connected to the surface or 'blanked' off as a closed end.*
- *A model must have a device(s) to produce pressure within the model and induce airflow. Pressure producing methods use in Ventsim Visual™ includes placing fans or a fixed airflow or pressure within an airway.*
- *Any fixed flow in an airway must not restrict another fixed flow elsewhere in a model, or be overly restricted by an impassable high resistance.*

Errors contributing to the above conditions account for around 90% of simulation errors and problems noted in Ventsim (from Chasm Consulting observations)

15.1. Overview

There are many different ways to build a computer ventilation model. Ventsim Visual™ (as the name suggests) utilises a visual approach to creating models, and the fundamental structure (shape) of models can be built either by hand with the mouse, or imported from a CAD program.

While a ventilation model can be built schematically in Ventsim, it is highly recommended building a true to scale 3D model if possible, to allow Ventsim to automatically use parameters such as size, length and depth for simulation. For compressible airflow models, this allows for automatic density adjustment and natural ventilation pressure application, resulting in more accurate and realistic results. In addition, rock temperature and autocompression can be automatically calculated for heat simulation.

15.2. Types of Models

A ventilation model must have a framework of connected airways or branches. For airflow to successfully travel along an airway, each airway must have a connecting airway at the entry and exit. Airways with no connection at either end will not carry airflow unless connected to the surface.

15.2.1. Model Types

A ventilation model can be developed as either a **closed** or **open model.**

Closed Model A closed model does not have any airways connecting to the surface. While this would be unusual for a real mine, for diagnostic purposes it is possible to build and simulate an entirely closed model, which continually circulates air around the modelled airways. To construct a closed model, simply connect and loop all airways so that they form a continuous path and all airway ends are connected to at least one other. Because a closed system is entirely self-contained, pressures and energies placed within the model to distribute flows are entirely consumed by the airways in the model. No ventilation energy is lost to outside sources.



Figure 15-1 Example of a Closed Model

Open Model An open model has at least two airways which connect to the surface, at least one of which is an intake airway, and another which is an exhaust airway. Most (if not all) mines will be established as open models. Airflow that exits an exhaust airway, in no way influences the pressure (or temperature) of the airflow which enters an intake airway. Airflow velocity pressures and energies lost from an exhaust airway are assumed lost to the model system. To link any airway to the surface, simply use the Connect to Surface function under the Edit Form.



Figure 15-2 Example of an Open Model

15.3. Initial Model Construction

Airways can be constructed in a number of ways.

- Manually draw scaled airways with the mouse using the toolbar functions.
- Manually draw schematic airways with the mouse using the toolbar functions.
- Import airway data from a formatted spreadsheet using the TXT import function.

  Import graphics data from a DXF/DWG/ Datamine / Surpac graphics file into Ventsim, and convert the data to airways. Most mine planning and CAD packages will have the ability to export data to one of these formats.

Regardless of the method used, in summary the recommended steps for constructing a ventilation model are as follows:

1. Construct the airways either manually using the DRAW function, or via the IMPORT function, ensuring all airways join correctly to each other. Filter tools are available in Ventsim to assist with ensuring airways are joined together.

2. Use the EDIT button to edit the airways that connect to the surface, and mark SURFACE option on the form.

3. Again, using the EDIT button, set the correct size and shape for all airways. Insert any ventilation controls or regulators in the model, and specify airway characteristics such as friction factors and shock losses.

4. Place a FAN or FIXED flow in an airway again using the EDIT button, and selecting the FAN tab of this form. This will provide pressure to drive the airflow through the model

5. Finally, press the SIMULATE button to show the result of the model construction. If everything has been constructed correctly, the airflow data and arrows should show the result of the simulation.

6. If some airways are dead ends, then simulation warnings can be prevented by setting the "CLOSED END" option in the airway EDIT form.

7. If any error or warnings show, then correct the mistakes individually or grouped as required.

15.3.1. Manual Scaled Construction

To manually construct airways, simply use the construction tools (the draw, move, copy and delete buttons) from the toolbar.

Airways can be drawn freehand on the screen with the mouse, using the coordinates displayed in the status bar to guide the airway location. Additionally, coordinates for airways can be entered manually using the coordinate entry function or by simply clicking on an airway end while in the draw mode.

This method is generally suitable for small models (less than several hundred airway segments). Most airway models are generally fairly tolerant of misaligned or slightly misplaced airways, providing approximate airway lengths are close to reality. In many cases,

to assist with clarity, airways can be deliberately moved aside, and a fixed length function used to override the automatic length calculation to set actual lengths.

If the model is required to be true to scale, then more accurate construction may be required, and it is often better to import actual mine designs from CAD programs into Ventsim to use as a template to constructing a true to scale model.

15.3.2. Manual Schematic Construction

In some cases, a model schematic can be constructed to simulate a model. A model schematic may look nothing like a real mine, but simply represent airways by a series of conveniently located two dimensional lines. Correct airway lengths can be entered by fixing the length under the Edit From.

Warning: Schematic Models, although convenient in simplifying mine airway models, have major restrictions which can affect their functionality in Ventsim Visual. Ventsim Visual™ uses true airway locations to calculate changes in air density and heat properties of rock and airflow, and as such, schematic models are largely unsuitable for Ventsim Visual™ Advanced models which simulate deep mines with compressibility effects or for heat simulation.

15.3.3. Spreadsheet Text Import

Where a list of airway coordinates and sizes may be available (from a database or another ventilation program for example), these can be directly imported into Ventsim Visual™ using the File Open Text Function. Data to be imported must meet a specific TAB delimited data format. This format can be loaded and saved by most office application software such as Microsoft Excel or Word. This format can be viewed by saving any existing model file as a TXT file format under the save menu.

15.3.4. DXF Graphics Import

For large models that need to be built to scale from existing mine workings or designs, the best method is to import line string data (AutoCAD Drawing Exchange Format DXF, DWG, Datamine or Surpac), and allow Ventsim Visual™ to construct a model from the imported data lines. The import function can be activated from the File Import menu.

Import DXF Graphics Line Data

STEP 1 – Create and Import a DXF file into Ventsim Visual



This method relies on passing line or string graphics data from a CAD or Mine Planning package to Ventsim Visual. The data may simply be the centre lines of surveyed mine floors or mine designs. To allow Ventsim Visual™ to efficiently use this data without excessive post import editing, the following criteria should be considered.

- Only import the minimum data required. Excessive detail or headings which do not form part of the ventilation model should not be imported if possible. In many cases, is may be quicker and more accurate to construct a skeleton ventilation model consisting of interconnected lines within the Mine Planning or CAD package, before import into Ventsim Visual. The skeleton lines should simply trace over existing mine workings or designs.

- Try to ensure the lines join into each other, so Ventsim Visual™ knows they are junctions through which air can flow. Lines that simply cross each other without a junction, or which terminate close to each other but not join, will not carry airflow,

and may result in a no exit/entry error in Ventsim which will need to be corrected in Ventsim.

When importing data, the lines can be converted to airways during the import process (by selected the option "Convert to airways'), or selectively after importing using the DRAW > CONVERT button to click or fence which lines are to be converted. The second option has the advantage of overlaying the updated DXF files with new development over the existing Ventsim airways, and selectively choosing where to update the Ventsim model.

Hint : To efficiently add DXF data to Ventsim Visual, keep a 'layer', 'object' or 'file' within your Mine Planning or CAD package dedicated to Ventsim Visual™ data, As new airways or designs become available, simply export the additions as separate DXF files, and import them into Ventsim Visual™ to add to the existing model.

Warning : Three dimensional solids (such as survey mine solids) will import into Ventsim Visual, but cannot directly be converted to airway. They can however be used as a guide to manually draw and construct new airways in the model



Figure 15-3 Imported DXF Lines



Figure 15-4 Conversion of DXF lines to airways

STEP 2 – Modifying and Validating Import Data

Once imported into Ventsim Visual, the program will assign default airways sizes and shapes to all the imported airways. Ensure you have default sizes and shapes set in the Settings menu that will approximate the typical sizes that are imported. This will prevent having to re-edit of ALL of the airway sizes and shapes (although this can still be quickly done using the group edit command)

Import DXF Graphics Solid or Wireframe Data

Unlike line string data, solid or wireframe graphics cannot be directly converted to airways. The data can still however be used to help construct airways, by either using the referenced (imported) graphics as guides to manually draw airways, or by using a special function in Ventsim to group the data and construct an airway of best fit through the data.

OPTION 1 – Turn on Edit > Lock on References menu option and select the DRAW button.

Simply use the mouse to DRAW airways over the top of the imported graphics. The airways will 'connect' to the same position as the reference graphics (providing the Edit > Reference Lock is enabled), allowing the ventilation model to be drawn in true 3D coordinates.

OPTION 2 – Convert ANY (references to airways). Use the Draw Sub-Option > Convert Any.

This option converts groups of referenced graphics to an expected airway path, and may be of use to attempt to convert large amounts of wireframe or multiple string (for example floor outlines) to an expected airway. It is likely that significant editing may be required after using this function to adjust airway locations and correct errors. For further information on this method see Convert Any option.

15.3.5. Correcting Errors

To quickly sort and validate (check) the imported airways, click on airflow simulation. While the model is unlikely to correctly simulate at this stage, this function will check the airways for duplicates and unconnected airway ends, which will speed up the process of establishing a working model.

In most cases, errors will result from airways not exactly joined into other airways, or remaining unconnected as dead ends, resulting in no exit or entry errors. If many of these can be corrected before starting an airflow simulation, this will improve the ease of creating a working model.

Filtering Tools

To help tidy up models and correct initial errors, a number of tools are provided in the TOOLS > FILTER menu, to bind disconnected airways, and find duplicated airways.

Alternatively, for airways which are disconnected use the toolbar move function to move the airway end onto the other junctions ends. If this is done correctly, moving the node after joining will then result in all airway ends moving simultaneously.

Under Tools > Utilities > FILTERING TOOLS

BINDING : **Bind Nodes** (use a value up to 4-5m or more to bind ends that are close to each other). Bind Junctions (Binds loose nodes that are close to a passing airway which has no corresponding node or junction). **Bind Intercepts** (find and/or join airways that cross each other, but have no joining nodes)

SIMPLIFY (removes a lot of the small airways and unnecessary detail). In many cases, importing a DXF files directly from a mine planning will create an overly detailed model file, which will slow down the system graphics and simulation, resulting in a more unwieldy model.

For example, a nice smoothly rounded decline airway which produces many airway segments is simply not required for accurate ventilation simulation and in most case can be designed with less segments and detail. The Simplify function in Ventsim Visual, will sort through a model, identifying unnecessary detail, which can be removed without adversely affecting simulation.



Figure 15-5 Example show the effect of the Simplify Function to reduce airway data

Alternatively, airways can be manually simplified by using the toolbar delete function to remove node junctions between airways.

DUPLICATES (find and/or remove any duplicated or overlapping airways)

15.4. Creating Pressure for Flow

To produce pressure within a model to motivate airflow, the following three methods can be used.

- **Fans** : Utilise and fan curve to establish accurate working flows and pressures in a ventilation model.
- **Fixed Pressures** : Use a consistent pressure to induce an airflow in a ventilation model. Airflow will vary based on resistance encountered by the pressure.
- **Fixed Airflows** : Use a consistent airflow to induced flow through a model. Pressure required will be adjusted to whatever is required to produce the airflow.

Without at least one of the above methods to produce model pressures, airflow will simply remain stagnant.

> In Ventsim Visual™ Advanced, a fourth method uses natural ventilation pressures to also induce flow, although this is entirely derived from heat and density air changes throughout the mine. It is possible to build a ventilation model with airflow driven entirely by geothermal heat or evaporative cooling, however the simulation results can sometimes be unreliable due to changing airflow and pressures continuously affecting natural ventilation pressures.

15.4.1. Fans

A fan can be selected to simulate flow in a model. Fan curves in Ventsim are automatically modified for local air density in a model, and therefore may not match the original curve which may be at a different density. Power, efficiency and the fan duty point are calculated and provided in the EDIT box. See the FAN section for further information.

15.4.2. Fixed Airflow

Fixed airflows can either be used to simulate the effect of a fan, or for forcing airflow into parts of a model to reproduce observed flows.

In general, unless estimating the requirements for a fan, the use of fixed flows to reproduce observable underground airflow is generally discouraged at it may adversely affect other parts of a model and does not provide a realistic behaviour for changes in underground model systems. In many cases it can mask real problems with the model construction.

A fixed flow will force Ventsim Visual™ to calculate a pressure required to induce flow to the set amount. This pressure can be substantial if the airflow needs to be pushed through a high resistance. Conversely, the pressure may actually be negative, if the fixed flow forces the airflow to be lower than would otherwise simulate, effectively resulting in the fixed airflow acting as a higher resistance.

> Hint : Ventsim Visual™ limits fixed airflow pressure build up to around 50,000 Pa. Pressures beyond this can result in serious model imbalances and heat build up, and in most cases are likely to be erroneous in nature anyway (for example, an airflow fix may be forcing air through a very high resistance). Ventsim Visual™ will raise a simulation error in this case to warn the user of unacceptable pressure build up. This can normally be easily fixed by finding the restricting airway.

In all cases, the results of a fixed flow can be observed from the Edit Box information function, which describes the pressure and power or resistance required to produce the flow. **This can be directly used to estimate a fan duty point** which would be required to produce the same results. This fix pressure can be equivalent to Fan Static Pressure or Fan Total Pressure, depending on the simulation type and location of fan.

Estimating Fan Pressure Requirements

Fixed Flows are often used to help estimate required fan pressures. The Pressure given for fixed flows will be an estimate of the **Collar Total Pressure – ie the total pressure of the airflow in the airway directy beneath the fan**. For a fan with an equal diameter to the airway, this equates to the Fan Static Pressure requirement, however caution should be used for this interpretation because differing fan diameters will alter fan static pressure requirements. A fan manufacturer will normally be able to utilise the collar total pressure value to an equivalent fan pressure. The Fan Total Pressure requirement will be a function of the discharge size and velocity of the fan, as well as any resistance and shock losses in the fan and structure between inlet and outlet. Thereofre the fan manufacturer will need to take this into account when selecting a suitable fan. Also note that the simulated pressures provided will be influenced by the simulated Fan or Airway Discharge diameter (evasé) so ensure this is noted and specified when quoting the duty point summary.

It is important to note that fixed flows contribute to model power consumption and heat, in much the same way as fans. The fixed power and heat within a model is summarised from the Run Summary menu item.

When calculating power and heat for a fixed airflow, the default fan/fix efficiency from the Settings Menu is used.

More information on fixed airflow and pressure is available from the Edit Box functions.

Fan Air Density

Finally, when specifying a fan duty point based on a fixed airflow, it is important that the air density the fixed flow was simulated in is noted. Fan performance varies substantially in different densities and a fan manufacturers will need to know the required density to the fan curve can be adjusted for the local condition accordingly.

For Ventsim Visual™ Standard, incompressible air is assumed and the air density remains constant and is specified in the Settings menu. For Ventsim Visual™ Advanced, this value varies throughout the mine, and may be significantly different from the surface or standard density value.

The Air Density is specified in the airway, or in the Fan or Fix summary page in the Edit Box.

15.4.3. Fixed Pressure

Fixed pressures work in much the same way as fixed airflows, but instead forces Ventsim Visual™ to calculate a resulting airflow to match the input pressures. As with fixed flows, fixed pressures consume power and produce heat, which again is summarised in the Edit Box information summary, or from the Model Summary menu item.

When calculating power and heat for a fixed pressure, the default fan/fix efficiency from the Settings Menu is used.

More information on fixed airflow and pressure is available from the Edit Box functions.

15.5. Simulating Airflow in a Model

15.5.1. Ventilation Pathways

A critical part of developing new models is ensuring air can move through new airways.

Place a Fan or a Fixed flow in the model to SIMULATE and start air moving through the model. This does not need to be accurate at this stage – it is simply a way to determine the connected paths where ventilation can flow, and where there may be errors.



Figure 15-6 Placing a fixed flow in an airway

Once a fan or fixed flow is placed, simulating the model will align all connected airways in the direction of airflow. Airways that are not aligned or show no airflow may be dead ends, or may not be connected properly to the model. Airways without flow should be closely examined for corrected airway ends.

If there are NO ENTRY / EXIT warnings, these will normally be caused by airways with dead ends. These can be selected and EDIT directly from the Warnings Box, and then closed using the "CLOSE END" function in the EDIT box.

If other warnings are present where airways are not connected correctly, run the BINDING tools again with a larger search radius, or just manually use the MOVE button to move the airways ends together.

The above steps should sort out most of the erroneous airways. Connected airways that show NO ENTRY OR EXIT errors may be because all of the airways do not travel in the same direction. Ventsim automatically establishes this direction where airflow is present, however this cannot be done for dead ends. The warnings can be fixed by either "CLOSE END" the airways with warning or by manually reversing individual airways with the REVERSE button.



Figure 15-7 Example of import error after simulation resulting from misaligned ends or unjoined nodes

15.5.2. Ventilation Ducting and Blind Headings

In most mines, a number of blind or 'dead end' headings will exist. By model definition, a blind heading cannot carry airflow, as it does not have a continuous path of airways leading to and from each end. In many real cases however, these headings are effectively ventilated by auxiliary ventilation duct, and often need to be simulated within a model. Auxiliary fans blowing into ventilation duct are moving air from one part of the mine to another and often much of the heat and moisture for a mine comes from auxiliary ventilated areas that need to be simulated as part of the overall mine heat balance.

To satisfy a model requirement for a continuous air pathway, ventilation duct needs to be included as a separate airway. For clarification, this airway is best placed outside of the mined airway, and sized according to true ventilation duct size. The ventilation duct airway will carry air to the blind heading face. The blind heading airways will carry airflow back to a model junction, and then join any other airflow beyond the blind heading.

The DUCT construction tool (in the drop down option box next to the DRAW button) will automatically construct a duct airway parallel to a SELECTED series of airways. Once constructed, a fan or fixed flow just needs to be added to one section of the duct to simulate flows.

Hint : Specify the air type of ventilation duct to a different type and colour. Airway types can be displayed independently, and the duct visibility can be turned on or off to improve visibility of the model.



Figure 15-8 Example showing ventilation duct into blind heading. Note the two leakage paths included to 'simulate' vent duct leakage

15.5.3. Interconnecting Mine Airways

In some mines, airways may connect to other parts of a mine which are not simulated or included in the model. The airflow to or from these other parts must be included into the local model. To include airflows to areas not simulated or included in the current model, simply run a single airway off the main model, assign a Connect to Surface attribute under the Edit Form and then enter either a fixed flow or fixed pressure to simulate airflow to or from the area. Ensure the direction of the airway is correct.

15.6. Utilizing Layers

Layers are a way to individually layer or identify and view parts of a model separately from other parts of the model. Some examples may include a stope system, an orepass or

ventilation raise system, a workshop area, or any other collection of airways. Note that there is no requirement for the user to utilise viewing layers. They are only present to allow easier manipulation and viewing of a model. The 'Metal Mine' example in the Ventsim > File > Demonstration menu shows an example of layers.

Layers work by allowing the user to 'overlay' multiple layers of airways or information on a screen. By doing this, unnecessary detail can be 'turned off' so only airways of interest are viewed.

Layers may be made active or displayed using the Display Manager. Layers names can be changed from the Edit Box by clicking the button adjacent to the layer name.

15.6.1. Primary Layers

Primary Layers consist of up to 250 layers. It is intended that the Primary Layers be used for identifying types of airways. For example, Layer 1 could be Primary Shafts, Layer 2 could be Main Airways, Layer 3 - Raises, Layer 4 - Stopes, Layer 5 - Minor Airways etc.

15.6.2. Secondary Layers

Secondary Layers, also consist of 250 discreet layers. It is intended that the Secondary Layers be used for isolating parts of a model that could be viewed independently from the rest of the model. As mentioned above, this could include working areas, stope, raises, declines or any other feature of interest.

There is no limitation on the number of airways belonging to a layer, however an airway can belong to only one secondary and one primary layer. Primary layers and secondary layers can be set and viewed independently of each other.

See the Metal Mine example (BLUE_SKY.VSM) examples that comes with Ventsim Visual.

> Hint : To quickly save and recall a 'layer state' use the Save View function to save and recall views with the Primary and Secondary Layers settings.

15.6.3. Using Layers

The easiest way to use Layers may be to create the model first (all airways will default to Layer 1 of both Primary and Secondary Layers, and then editing individual or group airways to change the layers to the desired number.

> Hint : The Edit Box has a function which will select and group all similar airways (for example all round airways with a diameter of 3.0m. This can provide a quick way to group edit and change layers for multiple airways.

New airways constructed will inherit the layer numbers of the airway they are constructed from. If no airway exists, new airways will use the default layers set in the Display Manager.

> Hint : Because primary and secondary layers can used together, this creates an opportunity to create a filter using both layer systems. If for example, primary layers were assigned as different regions of a mine (North, South, East and West for example), and Secondary layers was defined as different functions (Shafts, Ramps, Ore drives for example), then by individually setting the Primary and Secondary layers, the following examples could be easily viewed.
>
> - All ramps in the North Mine
> - All ore drives in the East and West mine.
> - All ramps and shaft in all mines.

15.7. Summary

The information in this Chapter explains only the basic techniques to establishing working ventilation models. To create a truly representative ventilation model, airway sizes and resistance must be accurately established; ventilation controls (such as doors or walls) must be placed in the model with correct resistances, and many other important factors such as shock losses considered.

For further information,

- See the Tutorial part of this manual
- Check the www.ventsim.com website for newsletters and forum information.
- Seek a suitable Ventsim Visual™ training course to undertake advanced training in the product.

Chapter

16

16 AUXILLIARY VENTILATION AND DUCTS

The auxiliary ventilation duct building function in Ventsim Visual provides an opportunity to model complex auxiliary duct arrangements in a mine model. Auxiliary duct in mines is essential to ensure quality fresh air reaches areas of the mine without flow through ventilation, which in most cases will be blind headings.

While auxiliary duct modelling is not a requirement for all models, the modelling of auxiliary fans and duct may be important to ensure adequate ventilation is delivered to key area, that the correct size duct and fan is used for a given length of duct, and that the impact of heat, humidity and fumes generated in auxiliary ventilated areas is correctly modelled on the remainder of the mine network.



16.1. Introduction

Simulation of contaminants through underground mines can be difficult to predict, particularly if simulations are required to take into account the complex

The vent duct builder box requires a number of values to be entered

Diameter The diameter of the duct

Friction Factor The friction factor of the duct. This can be directly overridden with a custom value, or additional friction factors can be added to the drop down list in the Preset > Friction Factor section of the program settings

Leakage Porosity A leakage factor representing the portion of the duct surface with holes, compared to the total duct surface. By default this measurement is in mm^2 / m^2, which could also be considered as 'hole parts per million'. Higher values represent higher leakage. Placing a zero (0) in this box represents no leakage. Modelling leakage will increase model size and simulation complexity, therefore leakage should only be specified if it is specifically required to be modelled.

Ventsim offers a number of default porosity factors in the drop down list, however these are subjective and can be altered in the Preset > Leakage section of the program settings.

During simulation, leakage will demonstrate reducing airflow further along the duct away from the fan. Fan pressures and duct diameter, together with leakage factors will influence leakage amounts. Leaked air is returned to the airway at the position it is leaked from the duct.

Leakage Intervals This specification is an internal instruction to Ventsim to build a leakage path (an invisible duct) into the airway at frequent intervals to allow air to leak back into the main airway. The resistance of this path is calculated automatically and is a function of the leakage factors and the leakage interval. In most cases it will not alter the simulation result significantly, however smaller leakage intervals will theoretically give more accurate results, but will increase the clutter and complexity of the display. For longer ducts, a minimum of 50m is suggested.

Offset Specifies where the duct will be built in relation to the airway. It is advantageous to build the duct outside of the main airway as it is easier to see and manipulate. For example, if the main airway is 5m high, then a Z Offset of 5m will place the duct at 5m above the centreline of the airway. Do not use an offset of (0, 0, 0) as this will overlay the duct on the airway centreline and will simulate correctly.

Build Duct starts the duct building process. A duct and leakage paths are place on a single group to allow the system to be selected with a single Select click in future.



Figure 16-1 Example of duct built

Modify Duct modifies existing *selected* ducting with any new factors entered into the duct builder. Note that the leakage intervals *cannot be modified*. If this is required, the duct should be removed and re-built.

Remove Duct deletes any existing *selected* ducting from the model. If normal airways are also selected, then this function will only delete ducting and leakage paths.

Hint – Things you may want to do next

Place a suitable fan at the start of the ducting airway

Consider placing an obstruction in the main airway if the duct is significant in size, and airflows along the main airway are high.

16.2. Applying Ventilation to Ducts

When duct is created, a pathway will be built into the duct to allow it to draw and deliver airflow to the underlying airway.

To ventilate a duct, simply EDIT the start of the duct airway with the EDIT toolbar button (do not SELECT the duct first as the entire duct will be selected) and then use the FAN tab to place a fan or a FIXED flow in the duct.





Figure 16-2 Auxiliary ventilation of duct

Pressurised or Suction Duct? The direction of the fan controls whether the duct is pressurised or in suction. To change the direction of the installed fan after placement, simply use the REVERSE toolbar button to change the direction of the fan section of the duct. The entire duct airflow direction will then reverse after the next simulation.

Inline Fans If a duct has multiple fans installed at different positions (a common practise for long lengths of rigid duct), then additional fans can simply be installed at locations along the duct, by using the previous method to install fans or fixed flows. If the duct is built with leakage, leakage can travel too or from the duct either way depending on fan and suction pressures.

HINT : Using the TOTAL RELATIVE PRESSURE colours, the user can determine if the duct section are under pressure or suction.



Figure 16-3 Colours showing the relative internal pressure of the duct

Multiple Ducts If more than one duct is to be built along an airway, then the OFFSET function can be used to ensure the ducts are separated and will simulate correctly.

For example, if two ducts are required, the first duct can be built with a HORIZONTAL offset of '-2' and the second duct can then be built with a horizontal offset of '2'. This ensures that either duct sits on opposite side of the airway and that they can be independently simulated.



Figure 16-4 Multiple Ducts

Multiple Sizes If ducts require different sizes midway along the duct length, then this can be altered by selecting the duct portion that requires a different size, and then using the EDIT toolbar button to modify the duct size. Because duct is automatically GROUPED when created, to select only a section of the duct, either use the SELECT fence function, or ensure the CTRL key is held down while selected to override the GROUP functionality.



Figure 16-5 Partially changing the duct size

Extending Duct To extend duct or create new tee-sections and junctions it is normally recommend to remove then rebuild the entire duct with the new section. Alternatively, it is possible to build only the new section of duct with the duct builder tool, however the connection section of the duct that join back to the airway will need to be manually removed with the DELETE button, to ensure the duct does not 'dump' the air back into the airway at the new join.

For example, in the picture below, a new auxiliary duct was created to extend into a new airway to the right of the main airway an duct. The duct builder created the duct with a connection back into the main airway. To ensure this duct is correctly joined, the connection must be DELETED and the remaining end of the duct MOVED back to the main duct and joined.



Figure 16-6 Extending an auxiliary duct

Chapter

17

17 CONTAMINANT SIMULATION (Steady State)

Steady State Contaminant simulation allows tracking the concentration of contaminants through a ventilation model. Ventsim Visual™ has a number of different types of contaminant simulations to enable users to predict the paths of any sort of gas, dust, smoke, stench gas or even fresh air through a mine, and may assist in emergency planning, production design, and to improve blast clearance times.



17.1. Introduction

Simulation of contaminants through underground mines can be difficult to predict, particularly if simulations are required to take into account the complex boundary and mixing behaviours of contaminants traveling through a three dimensional airway.

Ventsim Visual™ uses a relatively simple algorithm which distributes contaminants in a linear velocity fashion, and assumes perfect mixing at intersections. This method is considered suitable for high level studies through broad mine areas, but is not recommended for analysis of contaminant diffusion on a small scale level. In this case a computational fluid dynamic simulation may be better suited.

A number of different simulation techniques are offered to provide users with a host of tools to analyse the tracking of air and contaminants through a mine. Contaminants can either be specified as an in-line concentration of contaminant within the airway, or they can be injected into an airway using a surface connected airway to represent an external gas source (see the Gas Simulation section for further information on this method)

17.2. Contaminant Steady State

Performs a steady state (continuous) contaminant simulation based on the position of contaminant source(s) placed in the model.

Steady state simulation simulates the spread of contaminants until such time as the contaminant spreads through all possible pathways, and contaminant levels have stabilised to a 'steady state'. Where recirculation may be present, the simulation will continue until the recirculated air has reached equilibrium concentration. The simulation will only show result when 'steady state' conditions have been achieved.

Upon completion, the view will switch to a contaminant view of the final results with airways coloured according to concentration of contaminants. The contaminant spread time can also be selected as a colour or data text option, however this function will only provide the time that the contaminant first reaches an airway location, not the specific concentration of contaminant at that time. For calculating contaminant concentration at a particular time, the Dynamic Simulation function will need to be used.

Contaminant can be placed in a model by using the ***Edit*** toolbar function and selecting the **Contaminant Tab**, or the ***Contaminant*** toolbar button . Contaminant strengths are volume unit based and can be entered either as a proportional unit base, or a volumetric gas concentration.

> EXAMPLE Entering '100' as a concentration value may indicate 100% of the original contaminated source strength in an airway, and will result in the dilution of the value as uncontaminated air is mixed downstream. In this case, a downstream value of '25' downstream would indicate 25% of the original contamination strength.
>
> Another example of entering '2000' may indicate an initial value of 2000 ppm of CO gas. Downstream values would show diluted concentrations of this value. The units name does not need to be changed, however if desired can be changed in the Settings > Contaminant menu.



The contaminants may be cleared by pressing the *Clear* button at the base of the contaminant sub-menu.

17.3. DPM

Simulates a steady state flow of diesel particulates calculated from diesel heat sources placed in the mine. For further information on this function, see the DPM simulation section.

17.4. Gas

Simulates a steady state flow of multiple gases defined as sources in one or more airways. This is similar to contaminant simulation, but volumetrically simulates many different types of gases simulataneously. For further information on this function, see the GAS simulation section.

17.5. Reverse Contaminant

Determines the source of air at a specific location.

A sourcing simulation is similar to a reversed contamination simulation. It tracks airflow back from a placed contaminant source, and indicates the percentage of airflow which contributes to the airflow through the contaminant marker. This function is useful in determining where a location sources its fresh air from, or for analysing ways to reduce or increase airflow sources from certain areas (such as increasing airflow sourced from a bulk air cooler or decreasing airflow sourced from a hot production area.)

> EXAMPLE: Entering '100' as a concentration value and performing an 'air sourcing' simulation will show which airways upstream are carrying the relative amounts into the original airway. Back tracking the concentrations to the surface will show which surface airways are providing the airflow and may show values such as (for example) 25% decline adit, 60% main vent shaft, 15% hoisting shaft.

17.6. Find Source

Assists in finding the location of a contaminant source.

This simulation function was designed to assist in quickly identifying the possible locations of a fire or contaminant source (e.g. dust or production fumes) underground. As people report the status of air from different locations (for example smoky air or clear air), the simulation will colour airways upstream and downstream as either smoke (red), blue (clear) or yellow (possible smoke source)

Contaminant reports can be placed by selecting the location tool bar button under the contaminant button. A ***RED*** pin can be placed to designate a contamination report. Ventsim will assume that all airways downstream from this report will also be in smoke (coloured red) and all airways above the report will be a possible source of smoke (marked in yellow). The ***BLUE*** pin indicates clear air. Ventsim will assume that all airways upstream from this point are in fresh air (coloured blue). Once reports are place, select the location simulation function to simulate and colour the airways around the reports.

As more reports are received, the ***YELLOW*** possible smoke source areas will decrease and the location of a fire or contaminant source can be narrowed.

> EXAMPLE Mine Control receives a radio report that smoke has been smelled in a decline location. Checks reveal that other personnel further up the decline cannot smell any smoke.
>
> The vent officer places a 'REPORT SMOKE' tag on the airway where smoke was reported and a 'REPORT FRESH' tag on the clear airways. Pressing LOCATION SIM will show the likely paths of the smoke in RED, what areas are likely to be fresh in BLUE, and what airways may be the source of the SMOKE in YELLOW.
>
> After receiving two more reports of smoke in different areas and fresh air in other areas, the simulation suggests the smoke could only be coming from a workshop area in the mine. The vent officer directs emergency personnel to that area, who find a large number of smouldering rags in an industrial waste bin.



Figure 17-1 Example of contaminant sourcing narrowing down a smoke source.

17.7. Fire Simulation?

For intense or hot fires, it is not recommended to use the contaminant functions for fire simulation. Hot fires produce significant expansion of airflow and natural ventilation pressures which can change flow quantities and even directions, thereby rendering conventional contamination simulation models inaccurate.

For small fires, or perhaps the initial phases of a larger fire, contaminant distribution may still be a useful way to model smoke concentration and direction through a mine.

For larger fires, it is recommended to use the Ventsim 3.0 Premium VentFIRE™ function which has specific simulation methods for distribution of hot gases, smoke and heat from fires, and can assist in simulating the dynamic changes to the ventilation system.

Chapter

18

18 DYNAMIC SIMULATION (Advanced)

Dynamic simulation is a specialised simulation method that shows a time based simulation result that can be dynamically viewed and changed during the simulation. Dynamic simulation can be applied to contaminants, gases, DPM and heat.



The key difference between steady state and dynamic simulation is that changing ventilation conditions and contaminants can be tracked through the mine at specific times, and in most cases, the Ventsim model can be dynamically changed (for example different levels of contaminants can be changed, or the model airflows, resistances or fans can be altered) to see the effect on contaminant flow.

18.1. View Dynamic Simulation Results

Dynamic simulation employs two methods of observing results. The simulation will dynamically show the on screen results as the simulation progresses. Ensure the text and colours are showing the required simulation data type during the simulation to see the results.

Alternatively, a 'monitor' can be placed in an airway to observe and record the simulation changes historically.





To view the results contained in a monitor, simply click the VIEW button on the monitor to view a graph of results.



Figure 18-1 – Example of Blasting Gases at a monitor location

18.2. Contaminant Dynamic

Performs a dynamic contaminant simulation based on the position of contaminant source placed in the model.

The simulation will run a continuous time based simulation showing the track and concentration of fumes. The simulation can be paused at any time and the colour or type of data can be changed during the simulation.

> Warning: Dynamic contamination in Ventsim uses a simplified homogenous distribution algorithm which ignores the slower turbulent boundary effects of airflow along a rough passage and around corners, and the higher centre airflow velocities. Due to this leading and trailing effect, Ventsim may slightly underestimate the speed of gas distribution, and also underestimate the speed at which *all* gas is cleared from an airway. The simulation should only be treated as a guide.

Dynamic Contaminant can be applied and set in the EDIT – Contaminant box of any airway, or by using the SMOKE icon on the toolbar. There is no limit to the number of contaminant sources that may be simulated simultaneously in a model.



Figure 18-2 : Placing a contaminant in an airway

Dynamic Contaminant Sources may included

- Fixed Time Release
- Linear Decay Release
- Logarithmic Decay Release
- Explosive Gas Release

18.3. Fixed / Linear / Logarithmic Release

Selecting these options releases a contaminant for a limited amount of time into the airstream. The amount of time is set in the EDIT box. FIXED release emits the same contaminant level throughout the release time. Linear Decay releases a decreasing amount throughout the release time, starting at the original set contaminant levels, and reducing to zero at a linear rate by the end of the release time. Logarithmic Decay is similar to linear decay, but more rapidly reduces concentration at the start of release time according to a logarithmic power scale.

Time release dynamic contaminants are intended to be used for sudden or limited time release events, such as a stench gas release, gas burst or inundation or tracer gas release, or limited emission of smoke or other contaminants from a source. The simulation is useful for not only detecting the spread concentration, range and timing of contaminants, but also for establishing how long it will take to clear contaminated areas of contaminants.

18.4. Dynamic Explosive Contamination

Ventsim 2 utilised a throwback blasting volume method to calculate an initial volume of blast contaminated air that was fed into the mine atmosphere at a decaying rate. This method was

restrictive in that the throwback volume factor and the initial throwback volume contaminant concentration must be estimated for each blast.

Actual blasting tends to produce more concentrated initial contaminant volumes for large blasts compared to small blasts. As a result, there was potential to underestimate blast gas concentrations, or underestimated clearance times.

Ventsim 3.0 dynamic explosive contaminant simulation utilises a more automated method and works on the theory that any blasting source will initially produce a mass of pure blasting gases (based on a 'yield' factor for the explosives) that must be 'bled' into the surrounding atmosphere. Rather than trying to calculate an initial 'throwback' volume, the rate at which this pure gas is bled into the surrounding atmosphere is based on an adjustable logarithmic decay series which in the experience of Chasm Consulting appears more consistent with practical measurements of actual blast gas releases underground.

When explosve gas enters a mine airway, the ventilation system must then remove the contaminated air from the region through the rest of the mine to the exhaust. The rate at which the fresh air ventilation can initially remove the contaminant depends on the efficiency of the ventilation flow to access and remove all fumes from the blast zone (labeled the 'dispersion factor' in Ventsim).

For example, in an open free flowing drive with good airflow, contaminant would be expected to be removed quickly as the fresh air forces all pockets of fumes and gas quickly down the drive. A blind heading, ventilated by duct which may be damaged or some way away from the heading end will clear slowly as the fresh air cannot efficiently reach all parts of the drive and remove the fume.

The intial blast gas concentration mixing into the atmosphere is automatically calculated by Ventsim and is based on the blast size and the dispersion factor. This value is shown as an estimate in the EDIT box.

Results for Version3.0 in most cases should be similar to Ventsim 2.0, however for large blasts, initial gas concentrations may be higher than determined by the user, and clearance times may be shorter.

Dispersion Rate Ventsim uses logarithmic decay series to determine the portion of injection of blast gases into the atmosphere. The decay series uses a 'dispersion' factor of between 0 and 10 to control the logarithmic decay rate.

The dispersion factor is a unitless number that uses a square power series to describe the rate of gas removal. For example, a factor of '2' will initially release the explosive gases into the atmosphere at twice the rate of a factor of '1'. A factor of '4' will initially release the explosive gases at twice the rate of '2', creating an intially more toxic atmosphere, but clearing more rapidly. These factors are somewhat subjective (Ventsim describes '1' as very slow dispersion and very fast as '10')



and it is suggested that mine use a gas detection meter to gain an understanding of their dispersion rates for different blast and ventilation scenarios. Once Ventsim simulation are calibrated with the blast results, the factors can be more accurately determined and used with more confidence in other areas.

The contaminant and explosive concentration and amount can be placed with the SMOKE button and can be changed in the EDIT – Contamination box. A unlimited number of dynamic sources can be placed throughout the model, each with a different blast size and clearance rate (to simulate a number of development headings and stopes firing simultaneously for example).



Explosive Gas Release Settings

The yield rates of explosive gas release can be established in the Contamination Simulation settings. The default yield rates are based the number of kilograms of Carbon Monoxide release per kilogram of explosive blasted as measured by Orica. This yield factor can be changed or made to represent other types of gases. The concentration units entered can be changed to any concentration based unit (eg %, ppm, mg/m3 etc) in the settings. The unit name can also be changed in the Settings > Contamination menu section. The simulation is activated from the Run menu or from the Contaminant Simulation side button access.

EXAMPLE : Blasted development headings have been previously measured to initially have up to 2000 ppm of CO carbon monoxide immediately after blasting and a clearance time of 15 minutes. Therefore a dispersion factor is entered into the EDIT box to obtain a similar result (the setting unit can be changed to "CO ppm" if the user selects), and the explosive amount set to 200 kg. When dynamic simulation is chosen, the concentration of fumes (in ppm CO) is shown through the model second by second. Clearance times can be established when concentration falls below a specified limit (for example 25 ppm). At any time, the colour legend and limits can be changed to show the concentration as colours.

Warning : Dynamic contaminant simulation has many factors which can initially be difficult to predict. It is highly recommended users calibrate their models with actual data if they have the opportunity. The simulation does not replace real gas measurement or observation when entering blasting areas.

18.5. Dynamic Gas Simulation

Dynamic gas simulation simulates the time based spread of gases through a mine. Once again, the dynamic monitor functions can be used to record historical gas results from the simulation at different locations.

For further information see the GAS SIMULATION chapter.

18.6. Dynamic DPM Simulation

Dynamic DPM simulation uses diesel heat sources to calculate diesel emissions through the mine. The DPM levels are spread through the mine over time, and can be recorded with the dynamic monitors to show a history of results.

The DPM levels can be dynamically adjusted by PAUSING and editing or moving the machines around during the simulation, and then RESUMING the simulation.

For further information see the DPM SIMULATION chapter.

18.7. Dynamic HEAT Simulation

Dynamic Heat Simulation is a potentially complex function that can help determine transient or changing mine temperature based on changing conditions through the mine.

For example, surface temperatures, machines, refrigeration or mining activities can be changed during the dynamic simulation to determine the effect of the changes over time on the mine atmosphere at different locations in the mine.



To calculate the true dynamic effects on the mine atmosphere, the mine rock surface boundaries must be considered to have reached a stable boundary temperature so that short term changes in mine atmosphere temperatures can be released or absorbed by the rock at levels similar to the initial rock exposure receptiveness.

This creates a 'thermal' buffer or flywheel effect that effectively reduces the downstream impact of rapid temperature changes on the mine atmosphere. The thermal flywheel effect diminishes with exposure time; however for the short term dynamic simulation term that this function is designed for, the assumption of the rock boundary layer achieving a stable temperature produces reasonable results. To adjust for longer term exposure during dynamic heat simulation, Ventsim creates a boundary layer of rock of a predetermined thickness that is allowed to store or release heat during simulation.

The settings in the DYNAMIC > VENTFIRE™ section provide some level of control over the way this function works on the mine atmosphere.

For more detail on this function, see the VentFIRE ™ section of the manual. For complex dynamic heat simulation, the VentFIRE™ module is recommended as it allows pre-programmed heat and temperature changes to be included in the modelling, rather than manually pausing and changing the simulation.

For further information on steady state heat or dynamic heat simulation, see the THERMODYNAMIC SIMULATION chapter or the VENTFIRE™ section.

Warning : Due to the nature of short term dynamic heat simulation, it may not predict exactly the same results as steady state heat simulation. If this is required, the SETTING > DYNAMIC > VENTFIRE™ option for Dynamic Rock Age may need to be increased, however this will impact on the Thermal Flywheel effect during simulation.

Chapter

19

19 MULTI GAS SIMULATION (Advanced)

[Ventsim Visual™ Advanced]

Gas Simulation is a subset of contaminant simulation with some specialised properties to allow for multiple gases and air density estimation based on gas composition. This can have application for natural ventilation changes for simulation.

19.1. Introduction

Gas Simulation is based on the same linear spread algorithm as other contaminant simulations, however it allows for the simultaneous release and distribution of up to 15 different gas types, and automatically volumetrically balances other gases to ensure a 100% total concentration mixture is maintained. This function may be useful when tracking multiple contaminants of different levels from different sources, or when the density effects of different gas types need to be modelled in a simulation.

Gases can be placed in models using an injection method, an inline gas concentration method, or by using a gas emission rate. The first two methods use the same type of simulation, however the construction of the airways in Ventsim differs. The last method 'emits; gas along predefined airway routes.

19.1.1. Inline Concentration Method

Specifically sets the concentration of gases in an airway and distributes the gas concentration downstream. All air entering the set airway is reset to the specified gas concentration. This method would normally be used when a known or measured concentration of gas is present in an airway.



Figure 19-1 Inline Concentration (represented by the green icon)

19.1.2. Injection Method

This method allows the user to 'inject' a gas into an airway and observe the changes downstream. It does not reset the concentration of gas passing the injection point, and will therefore allow accumulation of gas concentration though the model.

This method involves constructing a separate dummy 'airway' to inject the gas into the model. The injection dummy airway should connect to the 'surface' to allow the injection to draw a quantity of gas separate from the model simulation. The injected gas should then be set to the actual concentration (eg 90% methane) and a fixed flow amount set to specify the rate of injection into the model. If very small fixed flow values need to be specified, the unit accuracy for airflow may need to be increased in the Conversion Settings.

The model can then be simulated to show the results downstream. To show the smaller concentrations of gas, the colour legend display may need to be manually adjusted to show the full range of colours over a much smaller range.



Figure 19-2 Example of Injected Gas

19.1.3. Linear Emission Method

This method allows the user to specify a rate that gas may be emitting from an airway surface into the mine atmosphere (for example coal seam gas). The emission is entered in litres per second per metre (l/sec/m) along the airway, and gradually replaces the atmosphere in the airway over time. Note that the method used is 'replacement' which is not strictly accurate as in reality the gas adds to the atmospheric volume causing a change in ventilation flows. In most cases however, the ventilation flow change is minute and can be ignored. If the emission rate is significant, and is likely to independently cause a change in airflows and perhaps push gas into other airways, then the more cumbersome 'injection' method should be considered instead.



19.2. Simulating Gas Sources

19.2.1. Placing Gas Sources



The EDIT form has a facility to fix the concentration of gas compositions in any airway (injected or in-line) in the ventilation model. All gas concentrations should be entered as a volume based concentration value (not mass based) and then 'FIXED' to instruct the simulation to use the specified amount.

If gas mixtures are to be commonly used throughout a model, it is recommended to establish PRESET gas mixtures, which can be defined in the PRESET table and will automatically apply the gases to the airway when set.

Gases which are not fixed will be automatically adjusted to ensure the total volume concentration of all combined gases remain at 100%. The adjustment is done proportionally so gases which are not fixed (for example Nitrogen at 79%) will be adjusted proportionally more than lower concentration gases (for example Oxygen as 21%)

19.2.2. Simulating Results

Pressing the simulation directly from the Edit form or the Contamination Gas Simulation sub-button on the toolbar will run a Steady State simulation. Alternatively, gas simulation can be performed dynamically, using the Dynamic Simulation > Gas button.



Figure 19-3 Run the gas simulation option

To display the results, the text or colour display may need to be changed to select the type of gas to be reviewed. The colour legend values may also need to be manually changed to show the full range of colours for the desired concentrations.



Figure 19-4 Change the text and colour to show gas concentrations

To clear the results of a gas simulation and reset the model back to a standard atmospheric gas composition, use the Clear Contaminants options.

19.3. Density Based Simulation of Gas

Ventsim Visual™ Advanced has the ability to simulate the effect of different air densities on airway resistance and natural ventilation pressures.

This ability is extended to include the effect of gas composition on total air density and natural ventilation pressures. To use this option, the following options need to be enabled in the Settings > Simulation > Gas

a) Compressible Airflows (available from Settings > Simulation > Airflow Menu)

b) Natural Ventilation Pressure (available from Settings > Simulation > Airflow Menu)

c) Gas Density for Simulation (available from the Settings > Simulation > GAS Menu)

Once enabled, provided Natural Ventilation Pressure (NVP) option is chosen, any gas distribution simulated in the model will result in changes to airflow simulation based on the effect of the gas density on air buoyancy, and the change in effective airway resistance.

For example, if 5% methane is simulated through an area of a mine with a Gas Simulation, then providing the Gas Density Simulation option is turned on, subsequent airflow simulation will predict the steady state buoyancy effect of methane through that region of the mine.

Another option may be to simulate gas drainage through pipe models, although this process has yet to be validated in Ventsim Visual

Warning : After completing simulation work using Gas Density simulation options, remember to restore the settings and turn off the option, otherwise future simulation will be permanently affected by gas through a model, until the gas it cleared out and removed with the clear contaminant option.

Chapter

20

20 THERMODYNAMIC SIMULATION (Advanced)

[Ventsim Visual™ Advanced]

Thermodynamic (or heat and moisture) simulation is a complex field of mine ventilation and environmental engineering. A comprehensive understanding of psychrometry as well as practical aspects of heating and refrigeration is recommended before using Ventsim Visual™ to assist with major infrastructure decisions for mine planning and development.

20.1. Introduction

Heat in mines is an inevitable part of mining in the earth's crust at depth. As mines become deeper, excessive heat may play an increasingly more important part in the consideration of a ventilation system design. Conversely, cold conditions, particularly in far northern mines can equally affect a mines performance, especially in winter where freezing of shafts and collars and worker discomfort underground become a problem.

The impact of heat on worker physiology is perhaps the key factor in designing a ventilation system for underground mining that is impacted by adverse temperatures. The exposure of excessive heat to workers impacts both on their work performance and output, and ultimately their health and safety.

When designing a ventilation system, in addition to providing ventilation to provide fresh air and remove noxious gases and dust, we also must design a climate for people to work in. Even if a mine does not have excessive heat concerns, worker performance will always be best where sufficient cool air is available to efficiently remove heat generated from human bodies doing work duties. Different ventilation strategies can impact on the underground climate, and this chapter discusses how Ventsim Visual™ deals with different sources of heat and moisture and explains tools in Ventsim Visual™ to analyse and apply design changes to improve underground climates.

20.1.1. Sources of Heat

Heat comes from a variety of sources in underground mining. If we begin with the heat provided initially in the fresh air entering the mine from the outside climate, the following sources are important factors in what happens while the air travels though the mine.

- **Rock Strata** – Dictated by the rock type and geothermal gradient, the temperature and heat flow from exposed rock increases at depth.
- **Autocompression** – As air travels deeper and is 'compressed' under gravity, the temperature increases theoretically by nearly 10 degrees C dry bulb per 1000m although this may be less if moisture is present in the airways.
- **Diesel Equipment** – A major source in modern mines, both heat and moisture are generated by diesel equipment.

- **Electrical Equipment** – Fans, pumps, winders, substation and electrical distribution system all distribute heat into underground workings.
- **Blasting** – Perhaps more of a transient heat source, blast can cause short term spikes in heat in a mine, and some heat can be retained in broken rock for some time.
- **Oxidisation** – Highly reactive ores can produce heat when exposed to oxygen.



Figure 20-1 Example of Heat in mine calculated by Ventsim after simulation

20.1.2. Source of Moisture

In addition, moisture can affect the comfort level of air underground. As moisture levels and humidity increase, this reduces the ability of the human cooling system (sweating) to adequately cool the body.

Strata – moist or wet rock surfaces from ground water results in increased evaporation.

Ponded Water – collection of water on the ground or underground dams can increase evaporation of water.

Diesel Equipment – generates additional moisture in the air through exhaust and by work activities by as much as 1.5 – 5 litres of water per litre of diesel consumed.

Dust Suppression / Sprays – used to settle the dust often on main travel routes, much of the additional water is eventually evaporated into the air.

It is important to note that the evaporation of water into the air does not directly increase the 'heat' of the air – in fact the dry bulb temperature is decreased and wet bulb temperature remains initially unchanged. However the decreased ambient air temperature makes the cooler air more receptive to collecting heat from downstream rock surfaces, resulting in increasing wet bulb temperatures. As a result, air quality and cooling power will more rapidly decrease and wet bulb temperature increase with the addition of moisture to the air.

20.2. Application of Heat

20.2.1. Model Environmental Settings

While Ventsim Visual™ analysis automatically considers heat from strata, autocompression and fans, the correct base assumptions or 'environmental' factors must be first entered in the Ventsim model settings to establish the conditions in which the mine is being simulated. See the Settings > Simulation – Environment section for further details.

20.2.2. User Inputs

All direct user specified heat into airways is entered via the EDIT box > HEAT. The most common user heat input source will be diesel heat or sensible (dry) heat, however the user can also input latent (water vapour) heat, refrigeratiion and oxidisation if applicable. In addition, the temperature of the air at a location can be specifically fixed to match actual data, or to provide simulated feedback from Ventsim Visual™ on what is required to achieve such temperatures.

Warning : Perhaps the biggest mistake in attempting to simulate heat underground, is trying to apply a heat source to an airway carrying small amounts of airflow. While this may be possible in real life due to perhaps only a short time of exposure, because Ventsim Visual™ uses a steady state thermal simulation, the heat is assumed to apply continuously and can result in extremely high air temperatures. As the thermodynamic equations are only optimised for a certain heat range (up to around 100 degrees), excessive heat will produce a simulation error.

20.2.3. Sensible Heat

Sensible heat is the application of heat to the air with no change in moisture content. The situation applies to dry heat sources such as electric motors from fans or pumps, radiating heat from hydraulic or working equipment or frictional heat sources from conveyor belts or crushers.

Note that all ventilation power underground such as fans and fixed flows or pressures are automatically assumed to be sources of heat in Ventsim. They do not need to be entered as separate heat sources.

20.2.4. Diesel Heat

Diesel engine sources underground are internally converted to a mixture of sensible and latent heat for simulation. Due to thermal inefficiencies, a diesel engine of a rated power will produce nearly three times the heat of the rated engine power, assuming no energy is converted to 'useful' work. Ensure when entering diesel heat sources, that only the engine power diesel equivalent is entered, not the engine heat output. The efficiency of a diesel engine can be specified in the Heat Simulation settings.

Diesel combustion results in the production of heated exhaust gases and water vapour, which is transferred to the surrounding air. In addition, additional water vapour source from engine cooling systems or the surround environment is added to the air in the form of evaporation. This ratio of diesel fuel to water is set in the Settings Menu, and is assumed the same for all diesel heat sources. If separate ratios need to be considered, the sensible and latent heat will need to be entered instead of a single diesel heat figure.

20.2.5. Latent Heat

Perhaps the biggest source of confusion in applying underground heat is the application of latent heat. In general, latent heat, which is essentially adding heat to the air in the form of water vapour, should rarely need to be considered as a separate user input. While latent heat is internally calculated by Ventsim Visual™ in the application of strata evaporation and diesel equipment, it rarely needs to be applied directly by the user. The only exception may be to 'condition' air to a required wet bulb and dry bulb temperature, or in the application of heating to a mine with propane or some other moisture producing fuel source.

20.2.6. Oxidisation

Oxidisation heat is included for completeness, but will rarely be required to be entered into a mine model. For most mines with reasonable ventilation flows, oxidisation will be generally insignificant in overall heat gain. The exception may be in highly reactive ores or where there is very low airflow. While there are formulas to estimate the reactive heat of certain types of

ores, it is generally unreasonable to try to calculate this value theoretically due to the variability of oxidising ores. In most cases, oxidisation heat can be estimated from empirical measurements from actual underground areas.

20.2.7. Fan and Fixed Flow Heat

All electrical fans generate heat which is dissipated into the surround airflow. The heat generated is equivalent to the input electrical power, and is dissipated into the airflow through a combination of electrical motor inefficiencies, blade inefficiencies and friction losses. Ventsim Visual™ automatically includes heat from fans (and fixed flow) in a model heat simulation, therefore there is no need to include fans as a separate heat source

20.3. Injection of Moisture

While Ventsim Visual™ automatically considers moisture derived from wet or damp strata surfaces, direct user moisture injection to air from underground sources is unlikely to be commonly used in most models.

It is important to note that moisture application to air does not directly alter the heat content of the airflow (providing the moisture added is the same temperature as the airflow). Instead, through the process of evaporative cooling, the dry bulb air temperature is decreased, while air moisture content in the form of water vapour increases (as latent head), resulting in net zero energy change. Once evaporation occurs however, the cooler ambient air temperature may be more receptive to heat transfer from rock surfaces resulting in increasing wet bulb and dry bulb temperatures downstream from the transfer point.

Examples of water addition to airflow may be:

- Dust suppression sprays
- Evaporative Cooling
- Conditioning of air for simulation
- Water can be injected into airflow using the Point or Linear moisture source function in the Heat input sheet on the Edit form.

20.3.1. Dust Suppression

Dust suppression sprays are often used on dusty roadways, at stope draw points or on conveyor belts or crushers. Water sprays directly increase the water content of air through increased evaporation from fine water particles, as well as wet surfaces around the sprays. In many cases however the uses of sprays is often sporadic and does not represent a steady state flow model. For sporadic sprays, a better solution to applying moisture to the airflow in a dust suppression area may be to increase the wall wetness fraction to closer to one (1). This will assume the area remains wet and also proportionately alter moisture addition depending on the airflow quantities in the area.

Caution: The amount of water capable of being applied to airflow will be limited by the amount of airflow in the airway. If too much water is attempted to be applied, the excess will appear as condensate in the simulation.

20.3.2. Evaporative Cooling

Another application for adding moisture is evaporative cooling, however these are not commonly used in mines unless very dry warm air is present. To simulate evaporative cooling, ideally a water balance should be undertaken to identify water being added to the air

from an actual installation. Alternatively, a temperature difference before and after the evaporative cooling chamber will allow Ventsim Visual™ to estimate the water balance in the Edit Box Heat Assistant.

20.3.3. Wet Material / Dam / Flooded airways

Water may be picked up via evaporation via any wet material or ponded water. Once again, the problem of directly applying a water flow volume to the air is that evaporation will change depending on the volume flow and velocity of the air. A better alternative to applying water over wet or flooded areas is to increase the wetness fraction of the airways.

20.4. Application of Refrigeration

The application of refrigeration for deeper or hot underground mines has become a routine requirement for many mines as they push deeper and environmental considerations become more pressing.

There are several different types of refrigeration processes used in mines. Refrigeration uses a heat exchange process where an amount of input energy (normally electrical or sometimes diesel) is used to create a heat exchange process where heat is removed from one medium (usually water or air) and exchanged as heat to another medium in a different location. If the refrigeration system is surface based and the heat from the refrigeration electrical input and exchange is rejected to atmosphere, then only the direct refrigeration component needs to be considered for underground and can be placed where it occurs (e.g. at a surface shaft collar for a bulk air cooler, or in an underground airway for a chilled water spray chamber or cooling tower).

If the entire refrigeration plant is placed underground however, then the heat rejected by the refrigeration plant needs to be placed separately as a (usually) SENSIBLE heat source. This heat source needs to include an amount of equal value to the refrigeration value used, PLUS the input electrical or diesel power to the plant. The ventilation design implications are of course that the heat should not re-enter the cooled airflow, and sufficient airflow should be available to remove the heat.

Refrigeration plant design for underground simulation can be summarised with 3 different methods.

1. BAC – Bulk Air Cooling, where all or part of the air entering the mine is cooled on or near the surface. The plant is based on the surface, and only the refrigerative portion needs to be entered into the simulation. BAC plants have the advantage of surface design and heat rejection, but the disadvantage of cooling air before it reaches the require location, thereby losing some cooling effectiveness along the travel route.

2. Underground Spot Cooler Plant. A refrigeration plant or machine placed underground normally only provides spot cooling for part of a mine. The simulation requires both a refrigerative and heat source to be separately placed in the model, representing the cooling produced and the heat rejected. The heat rejected must also include the input power to the plant. Spot coolers have the advantage of only cooling the air required, but the disadvantage of requiring a separate exhaust airway to remove the heat rejection. In addition, spot cooler tend to be smaller due to underground size restrictions and are more difficult to run and maintain.

3. Underground Chilled Water. The refrigeration plant is based on the surface, but the chilled water refrigeration exchange is location underground. In this case, only a refrigeration source needs to be simulation. Chilled water systems have the advantage of providing cooling only where needed, but the disadvantage of requiring potentially large volumes of water to be pumped and distributed through a mine.

Finally, the ratio of the refrigeration power (heat exchange) generated versus the electrical (or mechanical) input power is called the refrigeration coefficient of performance (COP) and is specified in the SETTING > HEAT. Although this factor is not directly involved in the simulation process (the final Refrigeration Exchange cooling kW is set by the user, not the input power), this setting helps Ventsim calculate the total electrical power a model consumes. COP normally varies from 2.5 to 5.0 (refrigeration power vs input power) and is dependent on the plant design and the input and output temperature parameters to the plant. Direct simulation of these parameters is beyond the scope of Ventsim simulation.

20.4.1. Placement of Refrigeration Sources

Ventsim Visual™ assumes any item placed in an airway is simulated at the icon location. For this reason, placing a bulk air cooler in the middle of a shaft, would assume the bulk air cooler is located half way down a shaft, which in most cases would clearly not be the case. This assumption would result in slightly differing air densities and air temperature than would be the case if placed on surface.

It is recommended that for fans and thermodynamic items, the icon be placed where the simulation is required to be performed, or alternatively a short airway segment (vertical or horizontal) is placed at the top of a shaft airway for the cooling infrastructure. This will force the program to use surface conditions for the device.

20.4.2. What portion of the air is cooled?

Ventsim Visual™ assumes ***all*** airflow within an airway is equally cooled by a refrigeration or heating device. If only part of the airflow is actually cooled (and the other part mixes downstream), because of condensation of the split portion the mixed airflow results may have substantially different psychrometric properties than air that was universally cooled.

While the two airflow cases will report similar heat reduction (consisting of sigma heat and enthalpy flow), the partially chilled airflow case may have the refrigerated portion chilled to much lower temperatures, resulting in an increase in condensation and subsequent removal of additional moisture. The resulting mixed stream will then be generally warmer, but dryer with a lower relative humidity, compared to the stream which is evenly chilled.

Whether the installation is on surface or underground, if a cooling device only chills part of the airflow, ensure a separate airway is included to represent this chilled portion. The example below shows the substantial difference in downstream temperatures between the two cases.



Figure 20-2 Example of an inline cooler chilling ALL airflow



Figure 20-3 Example showing same inline cooler chilling only 40% airflow

Discussion: It is important to note that in both cases, 3500kW of heat has been removed from the air. Downstream from the refrigeration unit, the difference in psychrometric properties of the mixed versus the whole chilled airflows will actually diminish. The dryer warmer air resulting from the mixed case, will actually enhance evaporative cooling from damp or wet airways, resulting in potentially cooler moister air,

while the case with the cooler moister flow will enhance geothermal heat transfer from rock surfaces and reduce evaporative cooling.

The resulting air temperatures some distance from the refrigeration source may be very similar.

What type of refrigeration plant is it?

The type of refrigeration plant will have subtle differences on the effect on air temperatures and humidity. A closed plate cooling tower versus a spray chamber for example may result in a different relative humidity due to the air to moisture contact mechanism, particularly if the dew point temperature of the air is not reached or the air is very dry. Additionally, the presence and location of electrical pumps and equipment required to run the installation may introduce heat back into the airflow for an underground installation, but not a surface installation.

Refrigeration Plant Performance

As Ventsim Visual™ only considers the refrigeration *output* of a plant, the plant performance in achieving this output is largely irrelevant to the simulation (although plants will perform differently depending on ambient temperatures to be cooled). The plant design to achieve this refrigerative output for the ambient working temperatures is an extra design criteria outside of the scope of Ventsim simulation. For detailed engineering studies it is important to consider plant design to establish overall economics and effectiveness for the proposed ventilation circuit. In addition, fouling and subsequent degradation of refrigeration plants should also be considered when allowing for contingency in sizing a refrigeration plant.

Chapter

21

21 DIESEL PARTICULATE SIMULATION (DPM)

[Ventsim Visual™ Advanced]

Diesel Particulate Matter (DPM) concentrations are a relatively new concern for underground mining operations. While prolonged exposure to high levels of diesel particulates has long been suspected as having potential to cause health problems, only recently have mining regulators started imposing strict atmospheric exposure limits for underground mines.

Ventsim Visual™ Advanced provides tools to assist in predicting the distribution and concentration of diesel particulates through an underground mine.

21.1. Application of DPM Simulation

Ventsim Visual™ Advanced uses simplified homogenous mixing methods (similar to contaminant simulation) to simulate emissions from diesel equipment exhaust entering the airflow and being distributed downstream. While real diesel output will always be variable, because regulatory limits are normally based on an 8 hour time weight average (TWA) exposure for a person throughout a shift, most of these variations can be averaged.

Tier Standards

Every diesel engine emits a certain amount of pollutants which include noxious gases and solid particulates. Regulators in many countries have introduced steadily decreasing emission limits on new engines, (known in North America as the Tier standard, or in Europe as the Euro rating). Generally speaking, the higher the rating the 'cleaner' the engine emissions should be. The recently introduced Tier 4 standard is being implemented over the period 2008 – 2015 and demands emissions be reduced by up to 90% lower than previous Tier standards. Engine emission results are tested and approved by the EPA in North America, and many of these test results are available online from the internet.

Composition of Diesel Particulate Matter (PM)

The makeup of quoted diesel engine particulate matter (PM) can vary depending on engine type and fuel used, however a widely accepted ratio range is around 50-60% elemental carbon, 20-30% organic carbons and 15-20% other matter. The two most commonly used standards are the elemental carbon value (EC) and the total carbon value (TC) which is the sum of the elemental and organic carbon components. Current North American guidelines suggest an elemental to total carbon ratio factor of around 1.3X. Unfortunately, most EPA test results are for total particulate emission (including non-carbon particulates) and do not state the different particulate composition.

Atmospheric Standards

Rather than introduce emission standards, mining regulators focus on atmospheric exposure levels in mining environments. The atmospheric concentration of a diesel engine emission is a function of the rate and concentration of the exhaust emission, and the amount of diluting airflow around the equipment. By placing an engine size and emission concentration in Ventsim Visual, the program can use simulated airflows to calculate the resulting atmospheric concentration.

Regulators have specified either an 'elemental' carbon limit or a 'total' carbon limit for allowable TWA atmospheric levels of diesel particulates. In North America (2008) a standard of 160ug/m3 Total Carbon (elemental + organic carbon) has been initially imposed, while Australia looks likely to adopt a 100ug/m3 Elemental Carbon limit.

Diesel Equipment emissions are usually specified as a particular matter (PM) level, normally factored to engine output (for example 0.15 grams per kilowatt hour of engine power). This level includes elemental carbon, organic carbon and other particulate matter such as sulphates. As the atmospheric limits relate only to carbon emission, care must be taken to either factor the emission rate to carbon levels accordingly, or factor the final atmospheric concentration limit so that only the desired carbon levels are used (elemental or total).

In the event the emission components are not known, it is suggested a factor of 50% can be applied to convert total particulates to an Elemental Carbon (EC) level, or 80% to convert to a Total Carbon (TC) level.

What is the actual released DP value?

Finally, the diesel engine emission outputs may in some cases be further reduced by the equipment manufacturer or mine utilising catalytic / regenerative converters and particulate filters. This can further lower the emission rate further (by 50% or more) and if present, should be considered in the final DP emission value. Conversely, worn or damaged equipment may produce significantly higher than expected emissions. Where possible, mine sites should measure actual equipment exhaust to obtain actual values, however if this is not possible, then equipment manufacturer advice should be gained, or a conservative approach from EPA data taken.

Application in a Mining Environment

Simulated atmospheric concentrations of particulates are only the first step in what must be a multi-pronged approach to controlling exposure levels. Operators of machines may be directly exposed to higher concentrations than predicted due to their proximity to exhaust emissions. Conversely, operators protected by filtered cabins may be exposed to lower concentrations that predicted. Also keep in mind that mine concentrations of DPM which are higher than the allowed standards still may be permissible if other control methods such as reduced exposure time or personnel protective equipment are used to control exposure.

Where control of exposure measures cannot be guaranteed to protect workers, the mine will need to consider implementing engineering strategies such as increased ventilation flow, or improved engine or emission control. Where increase ventilation flows are used, ensure that this has a cost benefit against improve exhaust emission or exposure control. The financial functions in Ventsim Visual™ provide useful feedback on the additional cost of ventilation – cost which may be better invested in exhaust emission reduction.

21.2. How to perform DPM Simulation in Ventsim

Ventsim Visual™ uses the diesel equipment placed for heat simulation to also simulate DPM concentrations. Emission rates can be entered either in the Heat Presets, or directly as a manual entry in the EDIT form. Once again, note that the atmospheric concentration will be given in the same composition units as the diesel emission assumption (emissions rates are entered as elemental, total carbon, or total particulate matter, therefore atmospheric concentrations will be of the same type)

21.2.1. Example

A diesel engine is listed as having a PM (particulate matter) value of 0.16 g/kW-hr. The mine is regulated under an Elemental Carbon limit of 100 ug/m3, and the user has assumed that Elemental Carbon is 50% of Particulate Matter (PM). Therefore the user must either convert the diesel emission rate to elemental carbon (50% = 0.08g/kw-hr) or keep in mind that their

actual simulated atmospheric limit is in total PM (200ug/m3) instead of Elemental Carbon EC (assumed 50% = 100 ug/m3)

The Ventsim user decides to convert the PM value to an Elemental Carbon value of 0.08g/kW-hr, and enters this value in the Heat Presets.

Next, the user must decide the **average diesel power output** of the engine during the shift. **DO NOT ENTER THE MAXIMUM** diesel engine power, as no typical diesel equipment will run at full engine power for the entire shift, and using this value will **over predict** DPM concentrations. The best method is to measure actual fuel consumption for the shift, and use the Heat Assistant in Ventsim to calculate average engine power output. In most cases, trucks and loaders will not exceed 50% of their rated power, and auxiliary equipment and light vehicles will be much less.



	Name	# In Use	Sensible Heat kW	Latent Heat kW	Refrig kW	Point Diesel Power kW	Linear Diesel Power kW/m	Diesel Emission g/kW.hr	Point Moisture ml/sec	Linear Moisture g/s/m	Linear Heat W/m	Oxidising Heat W/m
	Conveyor Heat	3									4000	
	Crusher Heat	1	150									
	Pump Station	1	500									
	Transfer Conveyor	1	250									
▶	Loader 16m3 50% rati...	4				125		0.08				
	Truck 50 T 50% rating	4				145		0.07				
*												

Figure 21-1 Diesel Equipment with DPM emissions in Preset Values

The user has five loaders with rated diesel engine power of 250kW each. After observing fuel usage for the shift, the user specifies the machine put out an average of 125kW of diesel power and enters this value in the Heat Presets.

The five (5) loaders are then placed in typical airways around the mine and the DPM SIMULATION function is activated.



Figure 21-2 Diesel heat and DPM source placed in airway

The DPM levels can be actively viewed around the mine, and the colour ranges adjusted in the Display Manager to view areas of potential concern. Further changes or increases to air flows will require a re-simulation of the diesel particulates to recalculate new values.



Figure 21-3 Example showing DPM simulation colouring through mine

Chapter

22

22 STAGING – (All Versions)



22.1. What is Staging?

Staging is a term representing the ability of Ventsim to create multiple versions of similar models in a single simulation file. Examples of this may include creating ventilation models representing different phases or timelines of the mine design, or alternatively it could be used for representing different options and variations for a ventilation design.

Up to 24 different stages can be developed in a single model. Each stage can 'share' common airways with other stages, or can have unique airways that are only valid for a particular stage or stages.

Staging is a great alternatively to creating multiple different Ventsim files that can quickly become out of date. Because staging shares common airways, then changes to shared airways on one stage will flow automatically to other stages.



Figure 22-1 - Example above showing a single model divided into four (4) different stages.

22.1.1. Example 1 – Multiple Stage Time Line

A user may want to build a model showing the initial decline development phase of the mine (complete with ventilation ducts and auxiliary ventilation from the surface). Next an intermediate phase is required, show decline development complete and primary shafts in place (with the surface auxiliary duct now removed), but no production activities shown. Finally a model is required representing all production activities.

For this example, the user can create three stages. Every airway in the model can belong to one or more of the stages. For example, the surface ventilation auxiliary duct system would belong only to Stage 1 (initial development), however the initial main decline would belong to all three stages because it does not change.

The second stage would include the main shafts (which belong to both Stages 2 and 3, but not Stage 1). Finally the production development and activities would belong to only Stage 3.

Different stages can be selected and displayed from the stage menu in Ventsim



22.1.2. Example 2 – Multiple Options

A consultant wishes to show a client three (3) different ventilation options for a mine design. Option 1 has a large shaft design with a single high pressure fan. Option 2 has two smaller shafts located in different areas, with two smaller fans. Option 3 has the two smaller shafts, and also the large shaft design but with a lower pressure fan. The ventilation design connecting the shafts in all three options is similar.

For this example, three (3) stages can be used to represent the three different options.

Because the horizontal mine design connecting the shafts is similar in all cases, then the airways for the horizontal mine design can be shared and set to belong to all three stages.

The Option 1 large shaft is also used in Option 3, however in this case a different fan is intended to be used for this shaft airway. Therefore the large shaft IS NOT common between Stage 1 and 3, and can only be set to belong to Stage 1.

Stage 3 will require an identical duplicate of this large shaft airway, but with a different fan (low pressure) that is only set to belong to Stage 3.

The two smaller shafts are utilised by Stage 2 and 3, and therefore must be set to belong to each of these stages (providing the same fans are used for these shafts in both cases)

22.1.3. Example 3 – Totally different models

A user wishes to design two totally different ventilation models with very few (if any) shared airways between stages.

For this example, each stage can be a totally new set of airways. When changing to different

stages, new airways will (by default) only belong to the stage they are constructed on (unless extended from other multi stage airways).

The user is welcome to construct new independent (non-shared) ventilation models on each stage. If a common 'skeleton' of airways will be used and modified between each stage, then the airways can be 'copied' from one stage then 'pasted' in the same position on a different stage. Using this method, any airway can be modified without fear of changing airways on other stages.

22.2. Using Stages

HINT : Please ensure you understand staging before create multiple stages with shared airways. There is a danger that a user may make changes to shared airways, forgetting that it may unintentionally affect other stages (unless the modification is done to a unique airway only belonging to that stage)

22.2.1. Setting up Stage Names

By default, Ventsim calls stages names 'Stage 1', 'Stage 2' etc. Up to twenty four (24) stages are available. It is helpful when using stages to give stages meaningful names.

Staging names can be directly typed into the combo box on the main screen by pressing the RIGHT MOUSE button on the list.

To enter more detailed Stage names and descriptions, the TOOLS > STAGES menu in Ventsim can be used instead to change names. This tool also allows detailed descriptions to be entered in the lower Stage window.



In addition, the order of stages can be moved up or down in relation to other stages by selecting the ROW and using the keyboard arrow key. Click on the Sim Air and/or Sim Heat to simulate the models when switching between Stages. By default, simulated airflows are not updated when changing Stages. Therefore, airways that are shared with other stages may contain data belonging to simulations from other stages, unless a new simulation is performed for the current stage.



22.2.2. Selecting Stages

Stages can be selected from the main stage combo menu. Once a stage is selected, ONLY airways that are assigned to that stage are shown on the screen. All other airways not belonging to the selected stage will be hidden, and will not form part of the error checking, simulation or summary.



You cannot view ALL airways on ALL stages simultaneously, and at this time to prevent confusion, all Windows opened in Ventsim will display only the selected stage.

22.2.3. Assigning airways to different stages.

Airways can be assigned to different stages from the EDIT box function. Simply use the SELECT button to select the airways, then use the EDIT button to change one or more airways to a new stage selection.



A horizontal series of boxes representing each available stage is shown in the EDIT box. Three different colours represent the current state of the selected airways. If the mouse is hovered over any of the boxes, a tool tip will show the name of the stage.

- Clear White shows that the edited airways do not currently belong to that stage.
- Blue shows that the edited airway all belong to that stage.
- Grey (when multiple airways are being edited) shows that some of the edited airways belong to that stage, and some do not.

To assign an airway to a particularly stage, simply click on the box representing the stage you wish the airway to appear in. The box will turn BLUE, and the airway will now appear on the screen when any of the set stages are selected from the main screen.

To REMOVE an airway from a stage, click the box again, and it will turn WHITE. The airway will now NOT appear in the model when this stage is selected.


A 'shortcut' key is available that will quickly cycle between

- ALL stages selected, only the CURRENT stage selected,
- ALL current and FUTURE stages selected, and
- ALL Current and PREVIOUS stages selected.

This button fills in the required boxes automatically, although the same result can be achieved by individually clicking each stage box.

-

22.3. Creating a Unique Version of an Airway for a Stage

Whenever a variation is required of an existing airway for a particular stage (for example an extra or different fan added, a different airway size, a different resistance or preset value, a different heat source or event, etc) then a 'copy' or 'duplicate' of the airway must be made for use on that stage only. There are several ways to do this.

Option 1 - Edit Box Auto Create Button

Ensure the airways you wish to create a unique version of (duplicate) are set to show on the stage where the change is required. Select and change to the required stage from the pull down menu on the main screen (the airways should still show), the SELECT and EDIT the airways with the EDIT box.


Use the stage Duplicate button to create a unique version of these airways. This button will REMOVE the selected airways from the current stage, and then create a duplicate of the airway that are set to only the current stage. The edited airways can now be modified without affecting the same airways on another stage.

Option 2 – Create a copy of the airways

While still on the old stage, select the airways you wish to appear on the new stage. If the selected airways are already shared with the new stage, EDIT the airways and deselect the new stage box so these airways will not show when switching to the new stage.



While the airways are still selected, choose EDIT > COPY AIRWAYS menu, switch to the new stage (the airways should not be displayed if they have been correctly switched off for this stage), then choose the EDIT > PASTE AIRWAYS TRUE (same position) menu. A copy of the airways should now appear in the new stage, which can be independently modified without affecting the same airways on other stage.



Option 3 – Construct a new airway

Simply drawing a new airway with the ADD button, or converting a DXF centreline will add an airway unique to the currently selected stage (unless an airway is drawn from an existing airway, in which case it adopts the existing airway stage settings). These airways can remain on this particular stage only, or can be later selected and set to appear on other stages.

22.4. Suggested Tips for Developing Staged Models

There are many ways to utilise staging, and users are encouraged to use methods that suit their design techniques.

22.4.1. Independent Models

While not recommended, it *is* possible to simply copy an entire model onto a new blank stage using the previous method. Because all airways are copied, then any modifications can be done in either stage without affecting the other stage.

While this method is probably safest for beginners, it has the disadvantage of creating duplicates of *every* airway for *every* stage (which can reduce available program memory – particularly for large models). In addition, if a common fundamental change on one model is made (for example the decline size is changed), then as none of the stages share airways, then the same change would have to be manually made for all the decline airways on all the stages.

22.4.2. Shared Models

A smarter way is to ensure common airways are shared. This creates a smaller model file, requires less memory, and ensures changes to common airways are reflected in all stages automatically.

- The FILE > LOAD DEMONSTRATION > METAL MINE example shows a progressive stage design (with four (4) different stages).
- A useful technique in creating such a model is to start with a full final ventilation design with ALL airways belonging to ALL stages.
- Then work backward towards the initial stages of a ventilation design and progressively remove the airways that do not belong to particular stages.

Work Backwards Technique

For example, assuming that by STAGE 4, all airways have been established then while displaying STAGE 3 (which currently has all airways included);

- Select and EDIT the airways that do not belong to STAGE 3 by removing the selection of the STAGE 3 box in the EDIT form.
- If the same airways do not belong to STAGE 2 and 1, then clear these boxes as well. Press OK - these airways will disappear from the STAGE 3 design.
- Do the same for STAGE 2 and STAGE 1. Finally create specific changes for each stage to create viable workable designs using the copying techniques described in the previous section.
- Or if a ventilation design such as a duct is required just for one stage, ensure that when the duct is created, it is edited to only belong to the stage it is required for.

Work Forwards Technique

Alternatively, start with the initial model design (on Stage 1 for example). Once this design is working, select ALL the airways and set the airways to show on Stage 2.

- Switch to Stage 2, and continue creating further airways (either drawing or by using DXF centre lines). New airways will be automatically set to belong only to the currently displayed stage (unless an airway is drawn connected from an existing airway – in this case it will adopt the stage settings of the connected airway).
- If any airways from Stage 1 do not carry over to Stage 2, then SELECT and EDIT to remove the airways from the Stage 2 design. If any airways from Stage 1 need to be modified for Stage 2, then select these airways and use the EDIT BOX > Auto Create option described in the previous section to ensure that a unique copy is made for the new stage.
- Once Stage 2 design is complete, select ALL of the airways on Stage 2, and set them to also belong to Stage 3. Switch the display to Stage 3, and then repeat the previous step to continue working on successive stages.

22.4.3. Other Uses for Staging

Even if models designs remain largely the same, staging can be used to run different heat, gas or contaminant scenarios.

In this case, each stage will have mostly shared airways, with the exception of airways containing the changed heat, gas or contaminant parameters. In this case, these airways are made into a unique copy for the required stage (using the EDIT box AUTO COPY button), and the parameters are changes accordingly.

The stage names can be changed to descriptively describe the changed parameters, and the stage description (available from the TOOLS > STAGES menu) can contain more information if required.

Chapter

23

23 VENTFIRE™ –Scenario Simulation (Premium)



23.1. What is VentFIRE?

VentFIRE™ is a module that uses dynamic simulation techniques (time based) to simultaneously model heat, gas and airflow changes on a mine environment over a period of time. While the heat source could be a fire, VentFIRE™ is also designed to work on other heat or cooling sources such as (for example) diesel machines and refrigeration plants. In addition, VentFIRE™ allows a ventilation model to be dynamically modified during simulation (for example doors may be opened or closed, or fans may be turned on or off at certain times). The result is that a complete scenario may be modelled over a period of time, and the atmospheric changes observed at different points in the mine.

23.1.1. Example 1

It is necessary to model the results of a large truck fire in the main decline, in particular the spread of gases and change of ventilation. The mine would also like to test of scenario to see what effect closing some doors and turning off fans will have on the fire and smoke spread at a pre-determined time into the fire.

A VentFIRE™ simulation can be easily established to

- Calculate the gases, temperatures and change of airflows (and whether they reverse) produced by the truck fire
- Show the atmospheric gas levels at various points through the mine including areas such as crib rooms or refuge bay where people may congregate.
- What will happen if fire doors are closed 15 minutes after the fire starts, and some fans are turned off, and whether this will limit smoke spread or gas concentration through the mine.

23.1.2. Example 2

A mine would like to model the effects of reducing mine refrigeration output during cooler night time hours to reduce power consumption.

Even though this has nothing to do with fire, a VentFIRE™ simulation can be established to

- Dynamically vary the day and night time air temperatures flowing into the mine.

- Dynamically vary the refrigeration output at different times during the day and night.
- Monitor the effects of these changes on air temperature and humidity deep in the mine at different locations.

23.1.3. Example 3

A mine would like to model the heat from intense diesel engine activity that occurs during various mining cycles to see what range of temperatures will be experienced in different parts of the mine, and for how long those temperatures may exceed a certain threshold.

Once again, VentFIRE™ can be used to

- Dynamically vary the location and output of diesel equipment during the day.
- Dynamically modify what auxiliary or booster fans may be turned on or off.
- Monitor the effects of these changes on air temperature at different working locations around and downstream from the activities.

23.2. Preamble on Fire Simulation

No underground hazard has greater potential for large loss of life than a mine fire or explosion. The smoke and gases produced by such an event in a confined space quickly creates a lethal atmosphere for any underground workers exposed to the event.

For this reason, there is great interest in being able to predict the effects of underground fires and utilise the results to establish emergency response procedures and systems to ensure the safety of people working underground.

Unfortunately, the prediction of fires before the event is extremely difficult; not only the location (which to some degree may be predicted using risk assessment techniques on possible combustible sources), but also to the nature, size and behaviour of the fire.

For example, a 'truck' fire could be caused by engine / turbo failure, hydraulic line failure onto hot exhaust, electrical short circuits or a 'hot' tyre. In each case the fire may be contained within the immediate portion of the truck, or it could spread to the entire unit. Numerous fuel types are present including diesel fuel, rubber tyres, hydraulic oils and cabin plastics, an each could burn at a different time and rate. The rate of combustion depends on available airflow and oxygen, confinement of the fire, exposure of the fire source and numerous other environmental considerations. Poisonous gas emissions from the fire are highly dependent on surrounding airflow, temperature of the fire and types of fuel burning.

It can be seen that trying to accurately predict all of these factors would be extremely difficult – the range of possibilities is endless. Therefore it is important to consider that 'Fire Simulation' in software should not necessarily be about trying to accurately simulate the fire itself, but rather to simulate the range of effects that different sized fires may have on the mine environment. By considering a range of possibilities and the resultant potential effects on the mine environment, an idea of the impact of a fire can be assessed and emergency response plans and mine ventilation design changes can be put in place.

23.3. How it works

VentFIRE™ uses a discrete sub-cell transport and node mixing method to simulate moving parcels of heat and gas around a mine.

To dynamically model mine ventilation and accurately take into account continual changes in atmospheric concentrations of gases and heat including recirculation, VentFIRE™ breaks the model into small independent 'cells' which move freely around a model, mixing with other cells at junctions. Each airway may be broken into dozens of cells (creating potentially hundreds of thousands of cells for a large model), and each cell independently contains information on gases, heat, moisture and density at that location within the airway. The cells are moved around at directions and speeds calculated by the global airflow simulation (a Hardy Cross simulation based on compressible flows and density driven natural ventilation).

Because simulations for VentFIRE™ are assumed short term (normally less than 24 hours) heat transfer to and from each cell from rock strata is calculated by the radial heat transfer method, but with strata heat transfer modified by the assumption of exposed rock boundary temperatures at a long term aged average, coupled with a very short time Gibson's algorithm constant to accelerate heat transfer to and from the immediate rock boundaries during the fire simulation. A 'shell' of exposed rock at a customisable defined thickness is allowed to heat or cool during the fire event from the airflow however heat transfer beyond this exposed shell volume of rock into the greater surrounding rock mass is ignored during the short term simulation.

As each cell of air passes over a fire, oxygen from the cell is consumed (based on defined fuel properties) at a defined combustible fuel burning rate. Heat from combustion (also defined in the fuel source properties) is added to the cell. If oxygen is reduced below a predetermined concentration the fire is throttled if excess fuel is available, and heat and gas output is limited. Other gases are added to cells based on the yield (y) rates specified in the combustible fuel properties. For critical gases such as carbon monoxide, an upper and lower limit can be specified to simulate the carbon monoxide emission effects of an oxygen or fuel rich fire; however this can be overridden to produce maximum carbon monoxide if a cautionary ('worst case') scenario is desired.

Airflow simulation is done periodically (period set by the user) to recalculate the flow amounts and flow direction in the model. The airway natural ventilation pressures are modified each time by collecting the aggregate air density of the cells within the airways. In some cases this may change the direction of flow of air within the model.

Information is entered into a VentFIRE™ simulation using 'Events' an event describes a change in input parameters such as a fire size, or a change in diesel machines (moving around), fans (stopping or starting) or resistances (such as a door opening or closing). An unlimited number of events can be entered into a simulation at different locations and times. An airway with multiple events can be sequenced to show changing conditions over time. For example a fire may initially grow rapidly in size, plateau at a maximum defined combustion rate, and then die slowly to nothing. For heat and combustion sources, the event scale can be made to linearly interpolate between a starting and ending value.

23.4. Use the VentFIRE™ Function.

23.4.1. Adding Events

The VentFIRE™ simulation requires 'Events' to drive the inputs into the simulation. Events may be entered into any airway by EDITing the airway, and selecting the DYNAMIC tab

option.





To create a new VentFIRE script, click on the configuration  button, enter a name for the script, the add events for the script and enter the required information for each event. Try to provide a descriptive name, and enter a time frame (in seconds) for the event. During this time frame a number of changes can be made to the airway.

- Up to three combustion source types can be added for a fire
- A preset heat source or defined range of preset temperatures can be used.
- In addition, a preset resistance (such as a 'DOOR') can be added (for this time frame only – it will revert to the original resistance outside of this time frame)
- An existing fan can be turned ON or OFF or the speed changed – providing it is present in the original airway.
- A gas source (such as a GAG or inertisation unit) can be added during simulation.

Where a 'starting' and 'ending' value can be entered in the dynamic event, the simulation will linearly range the values between the starting and ending time during the simulation.



Multiple events can be added to the same airway, by subsequently clicking the '+' button, or by right - clicking on an existing event to duplicate and modify it. Events can be added in any order or out of sequence, as long at the time ranges specified for each event are correct.



23.4.2. Adding Monitors

A 'monitor' is like a sensor that records a range of data during the dynamic simulation such as airflows, temperature and gases.

Due to the huge amounts of data generated by a dynamic simulation, only information at specific preset monitor locations is recorded. While instantaneous simulation results for the entire mine can be viewed during the simulation, only locations installed with a 'Monitor' can show the complete historical range of data collected during the entire simulation.



A monitor is automatically placed on airways that have predefined dynamic events, however to place monitors elsewhere in the model, use the toolbar button (shown above left). Once selected, simply click on an airway to add or remove a monitor. Monitors can also be removed using the DELETE button. Be aware that the amount of recorded data is limited, and more monitors will consume greater amounts of recorded data space. For lengthy simulation with many monitors, the amount of monitor recording memory can be increased in the Settings.

Once placed on an airway, a monitor will appears as follows.



23.5. Establishing Simulation Parameters

23.5.1. Dynamic Simulation Settings

A wide range of settings can be adjusted for dynamic simulation, including the time steps, air simulation update frequency, and screen graphics update frequency. In addition, variation parameters for changing the performance and behaviour of the fire can be changed. Please ensure you are aware of the effects of these changes before experimenting. A list of

definitions and explanations is available in the Settings section.

23.5.1. Resistance

Resistances can be added or changed during the simulation. Any resistance set before a simulation starts and not defined by an Event will remain in place.

> For example, a resistance called a 'Mine Fire Door' could be applied 20 minutes into a Ventfire simulation, to simulate a scripted mine emergency response procedure and test the effect on the airflow and atmosphere during a fire.

23.5.2. Gases

Gas addition during dynamic simulation is designed for adding or changing gas compositions independent of the fire source. Gas mixtures can be defined in the PRESETS which can be directly accessed by pressing the MIXTURE button. Gases can be added to a VentFIRE before the simulation (in which case this function is not necessary), or dynamically during the simulation.

The function can be used in two ways;

(1) If the Linear Emission IS NOT checked, then the gas mixture will be applied to all air passing through this airway. The air will be changed to the specified FIXED gas mixtures and all unfixed concentration will volumetrically balance to the remaining volume.

(2) If the Linear Emission option IS checked, then the atmosphere in the airway will gradually be replaced at the rate defined in the linear emission boxes (litres / metre / second).

The first option is designed to allow users to either change the gas composition of the air at a point in a mine (perhaps because the user may have some sensor data they can apply), or to specify the gas content of air that may be injected into a mine (for example a GAG unit, or NITROGEN inertisation system).

> For example, if gas is injected into a mine during a fire, then the VentFIRE simulation will show a decrease in the output of any fires that are flooded with inertisation gases (provided the oxygen levels drop low enough), regardless of the original user specified fuel burn rate of the fire.

The second option is designed to simulate the buildup of gases, particularly in areas of low ventilation flow.

> For example, if fans are slowed or stopped during a coal mine emergency, then the release rate of methane could be specified, and the dynamic simulation would show how long it would take for gas to build to explosive levels.
>
> Note this option mimics gas buildup by a volumetric replacement method, where a portion of the atmosphere is periodically replaced by the emission gas. This is suitable for relatively slow emission rates, however for very high emission rates which may create a significant flow and push gases into areas without emissions, a 'gas injection' method using fixed flows of defined gases is recommended instead.

23.5.3. Fuels

Up to three burning fuel types can be added to the event and the estimated rate of burn for the total fuel amount can be specified at the start and end of the time period for the event. The different fuels can be proportionally varied by a percentage % of the total amount specified. The rate of fuel burn and heat output may be limited to less than specified if there is insufficient oxygen passing over the fire source. The fire behaviour at low oxygen level can be defined in the VentFIRE settings page, in the main Simulation Settings form.

For example, if a truck fire is to be simulated, then the total mass of combustible material on the truck can be estimated (eg tyres, fuel, oil etc) and assumptions can be made as to the rate of burning (for example a previous incident may suggest a truck will completely burn within 2-3 hours). The combustible material could be combined into a single fuel type (in the Preset) which combines by weighted average the heat and gas output of all the materials, or alternatively, the fuel mixture could be converted to an equivalent amount of an existing fuel type (such as diesel), to give total similar heat and gas output.

For a very large fire, such as a coal fire, the total amount of fuel burn rate may not be that critical if insufficient oxygen is present. VentFIRE will only burn the amount of fuel relative to the amount of oxygen present. Therefore, overestimating the fuel burn amount will make no difference to the simulation if insufficient oxygen is present.

23.5.4. Preset Combustible Fuels

Up to 250 different types of combustible fuels can be added to the Ventsim preset database (from the SETTINGS > PRESETS menu). Each type of fuel can have defined Heat of Combustion outputs, oxygen consumption rates, and emission yield rates of various gases per kg fuel burned. Ventsim comes with a standard series of simple fuels with laboratory estimated heat and gas yields. The user is welcome to make 'combination' fuel types where the heat outputs and gas yields from different products are mixed proportionally to create an equivalent mixed fuel.

Note that because of the complex chemistry of fire reactions, these values may significantly change in a real mine fire, particularly if intense temperatures (>1000C) result in further chemical reactions to combustible products and pyrolised fuel (solid or liquid fuel converted by heat into hydrocarbon vapours).

For example fire tests in some experiments have demonstrated significantly greater portions (2 – 3 X yield of laboratory experiments) of carbon monoxide that can be generated during intense fuel or tyre fires due to the chemical reduction of CO2 to CO gas over hot surfaces. The user is welcome to change the typical laboratory value used by Ventsim to other values if they have information which may provide improved accuracy for their conditions.

As discussed in the introduction however, due to the wide range of assumptions used, the simulated gas values must not be used as an absolute determination of likely gas levels in a mine, but more as a guide to the extent of gas contaminants, and the likely variation between different parts of a mine.

23.5.1. Heat Sources

Heat sources are defined by existing heat presets. They could represent diesel machines, conveyors, electrical equipment, refrigeration plants or any other heating or cooling source. In addition, the Heat Source option allows the temperature of air to be specified passing through the airway. This could be used for setting the temperature to known measurements, or to specify days and night temperatures entering a mine through the total period of dynamic simulation.

23.6. Simulating Events

23.6.1. Establish Settings

- Make sure all events and monitors have been set and placed. If they require modification, then the simulation must the halted and restarted after the changes have been made.
- Ensure the simulation dynamic settings and combustible presets have been established.

- For FIRE simulation, ensure that both COMPRESSIBLE FLOW and NATURAL VENTILATON simulation options have been selected.

- If simulation of GAS elemental density is required (for example you want to simulate the relative buoyancy of methane or the heaviness of CO2), then ensure that the setting SIMULATION > GAS > Use Gas Density for Air Simulation is set to YES. For most fire simulation this is not necessary.

- Ensure the simulation settings for Dynamic and VentFIRE simulation are set correctly. The number of sub-cells or the dynamic simulation increment should be set according to the accuracy of the required simulation output. In the event that the base program settings are lost, Chasm Consulting recommend the following parameters be used as a base.

    - Dynamic Increment : 1 second
    - Maximum SubCells : 8 (or more)
    - Time Delay : 0 (unless the model is very small)
    - Display Update Frequency : 10
    - Air Simulation Frequency : 10 (if required)

-

23.6.2. Before Each Simulation

- Ensure your model is properly balanced and simulating correctly (both steady state air and heat simulation) before fire simulation.

- Optionally, the model can be 'stripped' of previous simulated results by selecting RESET EVENTS. Note that Ventsim will automatically remove previous gas and contamination results before a new simulation anyway.



-

23.6.3. Running a VentFIRE FireSim Simulation



Once all events and monitors have been placed, a simulation can be performed by pressing the button for VentFIRE™ simulation, or selecting the RUN > VentFIRE > FIRE SIM option from the main menu.

A 'Fire-Sim' simulation will perform simultaneous dynamic simulation on airflow, heat and gas. Other combinations of simulation can be selected from the Multi-Sim option. The simulation type performed will default to the previously selected simulation type, so ensure the sub option has selected 'Fire Sim' simulation if this is the type of simulation required.

A dynamic simulation will provide a time based simulation result, with screen updates showing the simulation result at a displayed time.



The screen graphics will show the current results on the simulation with colours and text showing simulation progress. During a dynamic simulation, the graphics view can be changed to show different location, and colours and text can be changed to show different types of data.

At any time the simulation can be paused to allow the user to examine areas of interest, or to check the results currently stored in the Monitors.

To significantly increase simulation speed, turn off the 'Update Graphics' option to prevent the screen from updating after every simulation step. The update number can also be increased to reduce the number of screen updates.

23.6.4. Multi-Sim Simulation

VentFIRE also has an option called Multi-Sim where the user can select a number of different types of simultaneous simulations from the Multi-Sim options. Unlike the Fire Sim option, Multi-Sim allows a defined series of simulation types to be selected.

> For example, a dynamic heat and DPM simulation may be required to analyse heat and diesel fume build-up in parts of a mine during mining activities. In this case, the Multi-Sim Options of HEAT and DPM would be selected, and the Multi Sim simulation option selected to perform the simulation.

23.6.5. Explosive Pressure Simulation

This is an experimental function to briefly inject large pressures into a mining region (defined in the airway > contaminant edit tab) to analyse pressures on regulators caused by a gas, explosive or dust explosion.

Likely pressure distributions relatively to the original overpressure estimation are shown through different parts of the model colour or text, and any preset resistances (such as door or regulators) are tested for strength capacity and whether they will fail under the overpressure calculated. If the preset resistance is calculated to fail, the pressure distribution will be recalculated assuming the resistance is no longer in



as

place.

Please note that this function is experimental only and not currently supported by Chasm Consulting.

23.6.6. Program limitations during simulation

A number of rules MUST be observed during dynamic simulation.

- Airways must not be deleted or added during simulation.
- The normal steady-state simulation buttons must not be used.
- Events cannot be changed, added to or removed during simulation.
- Airways CAN be modified with changed resistances or fans provided the simulation is paused and none of the above conditions are violated.

Failure to follow the above rules may produce unpredictable results or program errors.

23.7. Viewing Results

23.7.1. Instantaneous Results

The dynamic simulation will show the results (every update time interval) on the screen, so gas, temperatures and airflows can be tracked through the mine during simulation.



23.7.2. Historical Results from Monitors

Any monitor can be viewed during or after a simulation by pressing the EDIT or VIEW toolbar button, and left mouse clicking on the monitor icon.

A graph will show allowing the user to view a wide range of ventilation conditions at that location in the model.



23.7.3. Storing a static graph image of results

Simply press the 'camera' button on the graph form to make a static copy of the currently displayed airway monitor results at that location. This will not change for subsequent simulation and can be used (for example) to compare the graph results between two different simulations.

23.7.4. Exporting simulation data

To export this data to a spreadsheet or other document, use the CLIPBOARD icon on the graph for to copy the data to the Windows Clipboard. Then (for example) open an Excel Spreadsheet, and PASTE the data into the spreadsheet. All available data for that location will be copied into the Excel spreadsheet cells.

23.7.1. Smoothing Data

Data results can be filtered to smooth and average rapid changes. If the Log Frequency of data is greater than '1' then Ventsim will automatically smooth the data during simulation by averaging the data collected during every dynamic increment period.

Data results can also be smooth after simulation by selecting the 'Smooth Data' option in the VentFIRE menu. The smoothing factor entered collates and averages the defined number of data events around each data point. This function can also occur automatically after simulation if require, by setting the option in the Simulation > Dynamic settings.

23.7.1. Video Recording

VentFIRE simulation can take a long time, particularly for large models. The Video Recording option will record a video of the VentFIRE simulation progress over time to play back at a future date. The speed of video recording will play back at 25 frames per second. The number of frames recorded depending on the Dynamic Screen Update frequency in the Simulation – Dynamic settings.

> For example, if a dynamic screen update frequency of '10' was chosen, and a dynamic increment of '1' second was used, then the video would be recorded at 1 frame per 10 seconds, and would play back at 25 x 10 = 250X real time speeds.

23.8. Interpreting Results

23.8.1. Overview

Simulations can generate large amounts of data. While in many cases, temperature and gas may build up as expected and the simulation will show the extent and concentration of heat and gases through the mine as different times, sometimes a large fire can generate significant disturbance to primary airflow, particularly on sloping airways such as declines and shafts.

Rates of airflow can also impact on temperature and gas build-up within air passing the fire. A fire will expand the volume of air due to heat addition and the expanded gas and resultant increased downstream airflow can cause additional frictional pressure loss downstream from the fire. This can slow the airflow past the fire, causing a 'choking' effect, which can then compound the heat and gas build up further reducing airflow.



Figure 23-1 - Chart showing a complex buildup of Carbon Monoxide complicated by reversing and recirculating airflows

23.8.2. Airflow reversal

In addition if the fire occurs on a sloped airway, the buoyance of the low density air can provide natural ventilation pressures that act against the normal airflow direction, eventually slowing or even reversing the airflow. Airflow reversal is shown on a graph as a 'negative' airflow, and the time at which it reverses can be determined by examining the point at which it crosses the zero airflow axis.



23.8.3. Choked and Alternating Airflows

It is interesting to note however that if the fire consumes all available oxygen before airflow is reversed, then the fire effectively becomes constrained by the lack of oxygen, and heat output decreases, which reduces the potential for natural ventilation buoyancy to reverse ventilation. Even if airflow is temporarily reversed, the reversed airflow which is already low in oxygen may not provide for enough fire heat output to continue reversed airflow, and the airflow may switch backwards and forward between normal and reversed airflow.

In many cases, equilibrium may be reached where the fire receives sufficient airflow oxygen to choke most airflow, but not enough to provide the additional heat required to reverse the airflow. Additional heat is absorbed by the surrounding rock mass of the airway very quickly, and this can contribute further to a choked balance condition.

In the case of a choked airflow, this is a complex and potentially unstable scenario which in reality may or may not reverse in a mine. It can be dependent on complex three dimensional fire behaviour that can only be analysed using computational fluid dynamics (CFD) type analysis. For example, a fire that produces zero net airflow in Ventsim will be quickly assumed by VentFIRE™ to be 'throttled' with insufficient oxygen. In reality a bidirectional flow pattern may be established where fuel rich / oxygen deficient hot air travels in one direction away from the fire near the roof, while oxygen rich fresher air continues to travel to the fire at floor level in the other direction.

Such behaviour is beyond current VentFIRE™ capabilities, however to test this scenario in VentFIRE™ the user is welcome to change the 'oxygen dependent' setting in the EVENT sheet, that will prevent the fire from being throttled in the event of insignificant oxygen. Another less extreme option is to adjust the 'residual heat' setting in the SETTINGS > DYNAMIC simulation to provide a continued source of heat (eg 50% of maximum combustible rates) in the event the fire is throttled below this point.

Finally. A further option is to decrease the frequency of air simulation during a fire simulation (again from the SETTINGS > DYNAMIC) to allow the air to travel a certain distance (airflow momentum) before a change of airflow is established.

23.9. VentFIRE™ Limitations

A number of limitations need to be recognised when using VentFIRE.

23.9.1. Fire effect simulation, not fire chemistry simulation

Fire chemistry is not simulated (apart from oxygen deficiency). Simulated results are only as good as assumptions entered into the program. Gas levels are highly dependent on assumed yield rates of combustible materials and should not be generally used to indicated 'safe' gas level and 'dangerous' gas levels. ANY abnormal gas level simulated by VentFIRE™ should be considered potentially hazardous.

23.9.2. Rollback

VentFIRE™ does not currently consider 'rollback' where heat and fumes can travel along the roof in the opposite direction to the airflow for some distance back from the fire. Rollback distances are highly variable and depend on fire intensity, the slope of the airway, and the velocity of the opposing airflow.

23.9.3. Choking Limitations

The initial expansion phase of the fire will produce a 'non' mass balanced model where the mass flow of cold air exiting an airway may be greater than the mass flow (of hotter air) entering the same airway. In other words, for a limited time the lower mass-flow of hotter air pushes out a higher mass-flow of cold air. Because airflow simulation in VentFIRE™ is based on a mass balanced Hardy Cross algorithm, even though this takes into account the greater pressure losses and choking effects of airways produced from higher volume flows of hot air, it does not take into account the short term periods were greater masses of cold air are being

pushed out. The 'net' effect is that VentFIRE™ may temporarily underestimate the choking effect of the fire.

Chapter

24

24 LIVEVIEW™ (Premium)

LiveView™ is an extension of Ventsim Visual™ software, and will operate in conjunction with the main Ventsim Visual™ license.

LiveView™ provides a number of additional functions to enable the software to connect externally to data sources and display the data within the Ventsim model. Examples of this may include airflows, temperatures, gases or pressures, or even machinery such as diesel or electrical equipment.

LiveView™ also provides an interface to simulate ventilation models using captured sensor data, offering an ability to display downstream simulated results from actual data.

24.1. OVERVIEW OF LIVEVIEW™

LiveView can connect to multiple different data sources, and extract data from those sources to display (and optionally use) the data in the 3D Ventsim model.

Because of the large number of different types of sensors and communications systems, Ventsim LiveView does not attempt to connect directly with sensor hardware. Most sensor communication system will have hardware and software interfaces that record and store sensor data within an industry standard SQL database or similar. Ventsim LiveView is designed to access the data from the databases or data files, not directly from the sensors.

For example, sensors located in an underground mine will send data through a network to a data collection computer which will store the sensor data in a database. Ventsim LiveView can then query the database and extract the data values as soon as they are stored in the database, or even extract historical data if available.

In cases where companies may not like third party programs (such as Ventsim) accessing databases directly, the database can also be set up with read only SQL 'Views", or alternatively could periodically dump a data file into a TEXT or EXCEL format file for Ventsim LiveView to access.

Once the data is extracted into LiveView, the sensor data can be 'mapped' and displayed onto individual airways. The sensor data can be assigned to hold specific types of data (for example airflow, gases or temperatures). If the data assigned a 'type', then it is also possible for that data to be automatically used in a simulation.

For example, a sensor gas value can be used to simulate the likely downstream gas concentrations from the sensor location. With enough sensor values, an entire mine gas distribution could potential be simulated and displayed in realtime.

Ventsim LiveView allows multiple different data sources to be used simultaneously. For example two (2) different SQL databases, and a Text file could all be used together to import and show data in a Ventsim model.

24.1.1. How Does Ventsim LiveView use the data?

- The data representing all the available different sensor values is imported into Ventsim
- The user selects what sensor data records are to be made available for display and use in the Ventsim model.
- If the imported data does not contain information describing the type of data (for example airflow, velocity, gas, temperature etc), then this information must be set for each individual sensor data item (The selected data records and sensor information are stored in the Ventsim model for future reference so this does not need to be done again)
- If the data source does not contain the airway location, then the airways must be individually edited and the sensors assigned to the correct airways.
- Finally, the data can be displayed, and if required simulated in the Ventsim model.



24.2. Creating LiveView Data Connections

24.2.1. Step 1. Connect to a Data source.

A LiveView™ data source connection is a database or a file which contains external sensor information to import into Ventsim. The data from sensors may be sent to Ventsim in a number of different ways including Microsoft SQL servers, MYSQL servers, Microsoft Access, Microsoft Excel, CSV and TXT text file.

Please note that Microsoft Access and Excel are proprietary Microsoft licenses formats, and require drivers to be installed in Windows to access the file types. If you have Microsoft Office 2010 or later installed, your computer may have these drivers already. If not, you can install the drivers from the free Microsoft download "Microsoft Access Database Engine 2010 Redistributable" from

http://www.microsoft.com/en-au/download/details.aspx?id=13255

Please ensure the correct 32 or 64 bit version of the drivers are installed (if running Ventsim 32 bit, install the 32 bit version, if running Ventsim 64 bit, install the 64 bit version).

Warning : If Microsoft Office has already been installed, the version of the Microsoft connectivity drivers will correspond with the Office version installed (32 or 64 bit). It is currently common for end users to install 32 bit versions of Microsoft Office on 64 bit Windows computers. In this case, only the 32 bit installation of Ventsim will work with these drivers. **This issue only relates to Excel and Access type files.**

To access LiveView, click on the CONNECT > LIVEVIEW > SETTINGS in Ventsim.



Data Sources can be added to the LiveView connection list from the icons located on the RIGHT side of the list box.



SQL Database Connection.

Many sensor systems use an SQL database system to collect and store sensor data. Ventsim Visual™ LiveView™ can directly connect and obtain sensor data from such systems.



- Enter an optional generic name describing your connection. If no name is entered, the connection server name will be displayed in the connection list instead.
- Enter the Server web or IP address location, the name of the database, and the name of the Table, View or Query which contains the sensor data.
- If Windows authentication is not enabled on the database, a valid user name and password will be required.
- An optional data format field is available to assist in the import translation of data, however if the data is typed correctly in the database, this should not be necessary.
- The data connection can be turned on or off at any time with the STATUS button.

Access, Excel or Text files.

In some businesses, companies may not want LiveView™ to connect directly to the sensor database for security or performance reasons.

Instead a 3rd party macro can be written in many systems for the data collection system to periodically dump the sensor data into a file which Ventsim can read.



- Enter a generic name describing your connection. If no name is entered, the file name will be displayed in the connection list instead.
- To connect Liveview™ to the file, simply click on the file type Tab (Access, Excel, or Text CSV or TXT) and enter the file name. The input forms will differ slightly depending on the data type.
- The MS Access option will require a table name (and password if required), and Excel options will require a worksheet name.
- The data connection can be turned on or off at any time with the STATUS button.
-

24.2.2. Testing the Data Source



To test the raw data connection, click the SOURCE button on the Settings sheet to ensure a valid connection has been made. Ventsim Visual™ LiveView™ should display a table spread sheet listing all available data. If no information is shown, or an error is displayed, check the input parameters and try again.



To find out more about what settings and values Ventsim Visual™ LiveView™ will accept, use the menu FILE > EXPORT > SENSOR DEFINITIONS and SENSOR UNIT SCHEMA in the Setting Form, to view a copy of different codes that can be used when importing sensor data. Including additional sensor codes (for example Sensor Type numbers) in your data source can reduce the amount of editing required after importing the sensors.

For example, the UNIT SCHEMA export option, shows what code numbers can be used in the UNIT TYPE column in the sensor data. This column is used to specify the type of data the sensor is providing to

LiveView™ and will automatically be shown correctly when imported. If the information is not present, the user will need to specify the type of sensor data manually after importing.

24.2.3. Step 4. Mapping the Sensors





It is unlikely that the sensor file or database will have column names that correspond to names that LiveView™ expects. LiveView™ needs to know the column formats and names (Schemas) so it can correctly import the right kind of data into the correct fields.

For example, LiveView™ needs to know which column contains the date/time and which column contain the sensor data . To assist LiveView™ , the user must link or 'MAP' the LiveView™ names with the external data source names.

- At a minimum the Sensor ID NAME and Sensor VALUE (true value) needs to be mapped to LiveView™. Sensor values should be numbers only, and must not include text such as unit names.

- Other items such as sensor time, location, data type, and sensor type can also been mapped if present in the data source, however these items can be defined later if they are not defined in the data source. If LiveView™ has not found an equivalent column name in the source data, the item will be left blank. This item can be mapped by clicking the combo box and selecting which column name in the imported data file is matched with the LiveView type. If there is no equivalent column this item can be ignored for now.

Single Sensor value per row.

If the data contains a single sensor data value per row (in addition to other sensor attributes such as time, sensor type etc), then choose the "Single Sensor Value per Row" option. This will allow other attributes in the row to define different characteristics of the sensor.

Multiple Sensor values per row.

In this case, each record entry in the data source may have multiple sensor values per row. Select the "Multiple Sensor Values per Row" option. For example a single recording sensor station may list multiple gas sensor values (eg O2, CO2, CO, H2S etc) on the same row. The columns containing the data values will then be split by LiveView on the sensor import and individual sensor types can then be defined after importing the values in the same way as single row data. Note that in this case, other sensor attributes (such as sensor types) cannot be defined in the data source tables, and must be manually assigned after importing the data.

24.2.4. Testing the Sensor Data Import

To TEST the mapped connection to see what sensor information will be imported, click the SENSORS button.





24.3. Managing Connections

Once the LiveView connections have been established, they will be displayed in the connection list in the main LiveView form. You can edit, delete and make duplicates of the connections using the appropriate button at the base of the list. You can also edit the connection by double clicking the name in the list.

The connections can be simultaneously tested by clicking the VALIDATE CONNECTIONS button. Any issues will be reported in the results box, and the combined data imported with be shown in a datasheet. If a connection has failed, edit the connection data, and test the mapping and sensor data for more specific error reporting.





24.4. LiveView Settings

24.4.1. Set Sensor Simulation Options

LiveView™ can be set to periodically read and display sensor data in the model. The sensor data can also be used to simulate conditions in the model, and a number of simulation options are provided on the settings page. It is recommended the sensor information first be observed for valid data, as incorrect or unreasonable data may cause the simulation to fail or show unpredictable results.



- Date From / To: The date fields can be checked to import only data from a specific time and date. This assumes that multiple identical sensor readings are available in the data file from different dates. If this remains unchecked, then only the most recent sensor data will be shown.

- **Manual / Auto Update**. The sensor data can be set to import into the model only once, or periodically at set time intervals. If Auto Update is selected, then the user may note that Ventsim will pause momentarily whenever the data is imported.

Simulation Options. The data can be used to simulate conditions within the Ventsim model. Use these settings with caution as incorrect sensor settings can seriously affect simulation results and invalidate the Ventsim model with incorrect data. The sensors must be set to allow simulation individually, otherwise these settings will be ignored.

Simulation Update Frequency. If simulation of sensors is required, this can be done with steady state simulation, or dynamically over time. Steady state simulation can be done either manually (by running a simulation from the normal toolbar), automatically after every sensor update, or at set time intervals. Dynamic simulation is performed continuously and uses the most previous sensor values as base values for each location. Dynamic simulation is computationally intensive and may slow computer response, however it provides a more realistic spread of sensor data through a model.

24.4.2. IMPORT and MODIFY SENSORS

LiveView data cannot be directly used in a Ventsim model, until the individual sensors within the data source are identified and modified if required. This is because some of the imported data may be invalid or unnecessary. In addition, some of the imported data may be missing basic attributes.

Ventsim LiveView keeps a copy of these modified sensors settings within the model, so that future data imports are automatically correctly modified.

To define the sensors in the imported data, click the "Import and Modify Sensors" button, and then select the sensor you want to be able to access within the Ventsim model and transfer them into the "Included Sensors" list.



The included list will contain **GREEN** values if the data source connections still contain these sensor names. If the data source no longer contains these sensors names, or is temporarily offline or unavailable, then the included sensor names will be shown in RED. If sensor names in **RED** are included in a Ventsim airway, the LiveView display will not update the values.

Once the sensors are included in the list, they are available to assign to individual airways. However if they are missing important information such as the type of value, or alarm levels, they may be of limited use. Therefore it is important to assign attributes to the sensors to help Ventsim understand more about the sensor.

Assigning Attributes to Sensors

To EDIT a sensor and assign attributes, select the sensor or sensors from the list, and click EDIT. Normally a sensor must at least be defined with a type (eg velocity, methane gas etc). If these items are not defined in the Imported Data, then they must be manually set using the Sensor Editor.

Other attributes such as alarm levels, metric/imperial units and whether the sensor should be activated or simulated in the model can also be set.



Specifying the Sensor Location

If the imported data contains either the Airway unique number or columns for the X, Y, Z coordinates of the sensor then LiveView™ will automatically place the sensor information against the airway when imported.

If the sensor location is not defined in the imported data, then the user must specify which airway the sensor belongs to.

- The EDIT SENSORS OPTION under the LiveView™ menu also allows the user to specify the airway the sensor belongs to, by entering the Airway Name or Number.

- An alternative option to placing a sensor on an airway is to use the EDIT selection box, to click on an airway where the sensor(s) is located, and select the sensor name directly. The Sensor option is currently a sub-option of the GAS tab in the edit box.



- An option is provided in either the Sensor Editor form, or the Airway Edit form to specify whether to sensor will help simulate the model data, or whether it should be only passively displayed.

24.5. DISPLAYING THE SENSOR DATA

Once the sensor information is imported and the sensors assign to airways, the data can be displayed by clicking the Connect > LiveView > Update Once or Update Continuous menu. Clicking "Update Continuous" will continually update the model with sensor data at intervals defined in the LiveView Settings page. If the automatic simulation option is chosen, the downstream result of the sensor will be displayed on other airways. For example, if the sensor is an AIR VELOCITY sensor, then the airflow in the sensor airway will be restricted to the sensor velocity, and all airway leading to an from this airway will be adjusted accordingly.

> WARNING: Using Sensors to simulate model airflows may not necessarily correctly predict ventilation conditions in other airways. For example, if a change in airflow is transmitted by the sensor, then this may be because a fan has been turned off, or a door has been opened or closed.
>
> If these other ventilation items are not also input into Ventsim (although Ventsim LiveView™ can accept regulator and fan operational sensor data as well), then the simulated airflow activity may not be correct.

Airways with sensors will display a sensor icon, and a show a box describing the sensor data.





The sensor data boxes can be shown or hidden by selecting the Text Display Icon and hiding the Ventlog / LiveView text display option.

24.6. COPYING LIVEVIEW CONNECTIONS TO ANOTHER MODEL FILE

To copy your LiveView connections and settings to another file, load the other file in Ventsim, the use the FILE > INHERIT function. Select the Ventsim model file that contains the LiveView settings, choose the LIVEVIEW option in the Inherit setting box, then click OK. The LiveView connections and settings will now be available in the new file.

Chapter

26

25 RADON SIMULATION (Premium)

Radon simulation is a separate type of simulation that differs from normal gas simulation in that the hazardous nature of the gas is not directly the concentration of radon in the airways, but radiation exposure from the radioactive decay of the gas into the various radon daughter elements.

25.1. Introduction

Radon gas can emitted from many types of rock. While usually associated in higher concentrations with the mining of uranium ore, radon gas can also be present in lower concentrations in any type of mine.

Radon is released from rock surfaces along mined tunnels, and from broken rock or ore during the mining process. The amount of radon released is usually in proportion to the presence of uranium ore (U3O8) in the rock, however this can vary between mining operations and orebodies.

Hazardous exposure to radon gas results when the Radon element decays into lower order elements (called Radon daughters) during which radiation in the form of alpha and beta particles, and gamma radiation is released. The formation of these Radon progeny potentially exposes mine workers to harmful levels of radiation that can increase the risk of radiation related diseases such as lung cancers. Most countries have strict guidelines on the amount of radiation that workers can safely receive over a period of time.

25.1.1. Radon Concentration

Because of the small volumetric portion of Radon in mine, emanation into the atmosphere is instead normally specified in Becquerels (Bq) or Picocuries (pCi), which represents the potential decaying radioactive capacity of the Radon gas presence. Once into the atmosphere, the concentration is normally specified in Bq/litre or pCi/litre of air. The release of the radon gas in Ventsim can be introduced in two ways; either by the average emanation of radon per second over a m2 of exposed rock surface, and/or alternatively by an emanation rate of radon (Bq or pCi) per second (from ore piles for example) that can usually be derived using a factor based on the volume of broken source ore material.

25.1.2. Radon Progeny

The formation of Radon progeny (Radon daughters) causes the harmful exposure of radiation to workers. The Radon progeny calculation in Ventsim utilises a number of factors, including the exposed rock surface area, existing and newly emitted radon gas, and existing Radon progeny activity in the atmosphere. The result shows the potential radiation exposure in the atmosphere at different locations in the mine.

Because the decay of Radon gas into its various daughters can take some time after the gas enters the atmosphere (Radon gas has a half-life of 3.82 days), the radiation emanation of Radon progeny is highly dependent on the time that Radon and its daughter particles are present in the atmosphere, hence the higher progeny exposures can be some distance from

where the Radon enters the atmosphere, or where air is stagnant or slow moving. For this reason, it is highly desirable to limit the time that Radon loaded atmosphere spends in the mine.

Radon progeny levels are normally specified in uJ/m3 or air, or more commonly in North America as a Working Level (WL) (which was originally devised as a representation of an acceptable working level concentration of 100 pCi/litre, although this level has been substantially reduced since it was devised).

25.1.3. Threshold Exposure Limits

The harmful effects of Radon progeny are generated by exposure over time. The current method of assessing mine worker dosage is based on time weighted cumulative exposure to Radon progeny. For example, an exposure to one (1) Working Level (WL) for one (1) working month (consisting of 170 hours) equals 1 WLM cumulative exposure. A typical recommended limit for a standard year of 2040 hours exposure is 4WLM, which would be equivalent to continuous at work exposure of 0.33WL.

An alternative SI exposure level unit is mSv which can be calculated by the uJh/m3 progeny level where 1 hour exposure at 1uJ/m3 equals 0.00141 mSv. Therefore, an annual exposure of 2040 hours at 10uJ/m3 would be a dosage of 28.8 mSv. A typical recommended limit is 20mSv for a standard 2040hr year, which is equivalent to continuous at work exposure of 6.9 uJ/m3. Standards may also exist for higher short term exposures.

Ventsim also provides an annual exposure dosage calculation, however it must be remembered that actual exposure and dosage will be the weighted average of all regions of the mine accessed by a mine worker, and this calculation is based on 2040 work exposure hours per year, which may need to be adjusted for different rosters or time spent in the mine to give actual individual dosage estimates.

25.2. Using the Radon Simulation Feature

Four (4) different inputs can be specified for Radon and progeny concentration in an airway.

25.2.1. Radon Emanation

Typically, the Radon emanation will be specified based on the exposed area of the surface of the airway.

In addition, if broken ore or rock is present, the user may elect to calculate an extra Radon addition into the airway. This is normally calculated by estimating the emanation of radon from the exposed ore surface (based on the area exposed m2) and also from within the ore pile (based on the m3 present). The additional Radon calculated can be added to the airway in the second field (Radon Addition).

25.2.2. Radon and Progeny Fixed Settings

Alternatively, the levels of Radon concentration and progeny levels can be specifically set in the airway using the FIX options in the 3rd and 4th setting. These factors will override any calculations derived from the emanation settings and will ensure any airflow exiting the airway contains these values. These settings should only be used where there is a known concentration as they will override any prior estimates of radon activity travelling through these airways. The emanation settings should not be used simultaneously with the fixed settings in the same airway.

25.2.3. Activating Radon

The Activate Radon checkbox will ensure the radon settings of the airway will be included in the Radon simulation. Deselect this box if the settings are not required to be used in the

simulation.



25.2.4. Simulating Radon Radon simulation can be performed as a Steady State simulation by simulating directly from the EDIT form, or from the Contaminant Simulation sub option.



Radon can also be simulated using the Dynamic simulation options, although because of the simulation technique, results may slightly vary.

Radon simulation results will show Radon and progeny levels distributed through the mine as colours and data. As will most other Ventsim units, the different Radon results can be specified in the colour and data menus under the separate Radon data category.

Radon units and decimal accuracy can be altered in the TOOLS > UNITS main menu. In addition, the standard year work hours for calculating dosage can be adjusted in the RADON section of the TOOLS > SETTINGS > SIMULATION menu.

Chapter

26

26 FINANCIAL OPTIMISATION (Advanced)

Ventsim Visual™ provides many useful tools to analyse and develop strategies to save money. While the total ventilation cost for most mines is significant, in many cases much of the cost of ventilation may remain largely hidden or ignored.

The total cost of ventilation in mines should be considered as a combination of costs;

- A direct operating cost (such as power consumed or maintenance and upkeep of ventilation system), and
- A direct capital infrastructure cost (which includes the development and infrastructure mined and fans purchased); and
- An indirect cost which factors productivity gains and losses due to good or adverse ventilation conditions.

When ventilation costs are viewed as an integral part of all production activities, the cost of poor ventilation becomes even more substantial and can be used to justify additional investment in the ventilation system. Ventsim Visual™ includes a number of tools to quickly analyse and help reduce ventilation costs.

26.1. Financial simulation

[Advanced Versions]

This function is designed to quickly estimate optimum ventilation infrastructure size, by considering mining costs as well as life of mine ventilation operating costs.

Financial simulation can help optimise airway sizes and save substantial money over the life of a mine. Keep in mind however, when using estimated mine life to optimise an airway size, that in many cases mine life extends far beyond initial estimations as further ore resources are found.

Many mines are stuck with an inadequate ventilation system that is stretched far beyond its useful life, because the possibility of mine extensions or expansions was not considered in the early stages of ventilation design.

Ventsim has three (3) different options for financial optimisation.

Option 1 – Quick Select This method is based on variable airways size costs based on fixed and variable parameters and formulas. While this method considers an infinite number of different sizes, the formula assumptions used must be estimated from actual mining costs and therefore will vary between different sizes.

Option 2 – Selected Airways This method is based on defined airway costs and parameters for a number of discrete sizes, and will construct graphs showing different size options.

Option 3 Global Optimisation This method is based on the Quick Select method, but considers every single airway in the mine model for optimisation. Optimisation is only considered for larger than original size airways, as recommending smaller sizes often ignores the reality that mining sizes are designed for minimum sized passage of men or equipment. A list of potential airways that can be optimised will be provided at the end of the simulation.

26.1.1. Graph Select Financial Optimiser

Option 2 - The selected airways method - allows for the definition of size and costs of up to ten different airways sizes and shapes. These are defined in a table, which is then used to calculate various ventilation costs for each size. After calculation of each size, a graph is drawn showing the three major ventilation costs (mining, power and fan purchase). The lowest combined cost is normally the optimised point in sizing.



Figure 26-1 : Financial Simulator Output showing life of mine airway costs

Increasing airway size is the easiest way to reduce frictional pressure losses and decrease ventilation costs in a mine. Increasing airway size however creates additional mining costs, and this is further exacerbated by the 'time value of money' which dictates that a dollar saved in mining costs now is worth more than a dollar saved in ventilation costs in the future. Another factor to consider is how long the airway is required to carry air, which affects how much ventilation cost can be saved in the future.

The financial simulator takes all this into account, and simulates up to 10 different airways sizes for an airway or group of airways, reporting the effect on mining cost and ventilation costs as an NPV (net present value cost) adjusted overall cost.



Figure 26-2 Example of a Financial Simulation Table

The system relies on the use of accurate mining costs to estimate the costs of different airway sizes and shapes. The correct power cost must also be placed in the Settings.

Maintain Flows Simulation Performs a financial simulation and maintains identical flow through each size to ensure the airway size is optimised for the required flow. Note that once a size is selected in the final model, then unless a fixed flow has been chosen, adjustment to fans or flow elsewhere in the model may be required to achieve the desired flow through the new shaft size. This is the method that should be generally chosen when optimising shaft sizes for new or extended mines.

Adjust Flows Simulation Performs a financial simulation and allows the simulation to adjust the flow through the airway (unless using fixed airflow) based on the resistance of each size. This option should only be used if it is understood that by allowing the airflow to adjust, the basic economics of the shaft also adjusts, and may place additional costs elsewhere in the ventilation model.

The function is useful to establish shaft or airway size performance where existing fans or infrastructure is in place, but should not be used when designing a new mine or shaft and fan system where an optimised size is required for a specific airflow.

Using ***FAN*** curves on selected airways, will result in decreasing flow for smaller airways, which in turn, despite increasing fan pressures, may actually result in a decrease in ventilation costs. There is no point in establishing an economic airway size if it does not deliver the required airflow.

Input variables required **Airway shapes:** Round or Square. A set of 10 airway parameters is stored for each shape type. More complex shapes or fixed areas are not supported at this time.

Life: The life in years required for the airway to be in operation. This directly affects the ventilation operating costs of the airway, and the effect of time value of money.

Discount % : The time value discount of money per annum. The value of money will diminish over the life of project, meaning costs saved up front (in most case mining and fan purchase costs) are worth more than costs saved in the future (in most cases ventilation costs). Other similar names associated with factor include the discount rate, project hurdle rate, rate of return or NPV (net present value) discount rate. To use a value of money not diminished by time or to estimate undiscounted future savings, use a zero (0) rate. To evaluate projects

however, most mining companies will use factors ranging from 5% to 15%, depending on the cost of money and the competing project values to be gained elsewhere with that money.

Fan Cost : The capital (purchase) cost of fans required to provide ventilation power for the mine simulation. Note that this uses an approximation of $/unit power cost approach which is only an estimate of actual fan costs, and may vary substantially when compared to real fans of different sizes. Nonetheless, it provides an important adjustment to different airway sizes that in most cases will be accurate enough for selecting suitable sizes.

Sim : Check this box to include the airway size in the simulation. Airway sizes that are not reasonable or which do not deliver sufficient airflows should not be included for use as they can distort the graphs to excessive ranges.

Fixed Cost : Many airways, such a shafts have an initial setup cost to establish the mining method. This option is included to allow this to be factored in to the overall airway mining costs. It is applied only once for the airway, or group of airways selected, not applied to each individual airway. In most cases, horizontal development will not have a fixed cost applied against it.

Variable Cost :The cost per unit length of development or mining. Using this value, Ventsim Visual™ calculates total mining costs based on the length of the airways selected.

Financial Simulator Outputs

Mining Cost : Total cost of mining the airways

Fan Cost : Cost of the capital cost portion of fan infrastructure required to produce the ventilation flow. Note only the portion of fan cost related to providing ventilation for the selected airway will be used.

Selected Annual Vent Cost; Cost of ventilating selected airways for one year. Note this is only the frictional cost of the airway, not the power cost of distributing air through the model.

Selected Lifetime Cost : Total cost of mining and ventilating selected airways for the life of the airways.

Model Annual Vent Cost: Cost of ventilating the whole of model for one year

Model Fan Cost : Combined cost of all fan purchase costs based on the required ventilation power for the entire model.

Model Lifetime Cost : Combined cost of mining selected airway plus cost of ventilating whole of model for life of the airways.

Sel Airflow (avg) : Average airflow through each selected airway

Net Airflow (total) : Airflow through entire mine model.

In most cases, only the Selected Airway costs and graphs will be relevant to the simulation results, however at times it is important to consider the effect of changing airway sizes on the rest of a mine.

For example creating a large shaft to deliver more airflow to a mine, may simply increase the cost of the airflow through other parts of the mine, offsetting some of the expected ventilation savings. For this reason, Total Model ventilation costs are included as a separate column and graph, and should be considered if the project is an addition to a mature mine.

26.1.2. Quick Select Financial Optimisation

Assists in choosing the most economical airway sizes for the ventilation required.

This function can help optimise the size of vertical or horizontal airways by considering a variable cost of mining based on airways size, and then optimising airflow power costs through potential different sizes. The variable mining costs are defined in the Settings. This function can only be used on a single airway (such as a shaft), or groups of airways with the same size (for example a decline system).

26.1.3. Financial Simulation Global 26.1.4. [ADVANCED]

Checks and reports on all airways within a mine model on their size suitability to carry the simulated air.

This is a broad function which utilises the default cost settings to determine to cost of airflow through each airway for the life of the mine. The cost component costs are a relative mining cost, and fan capital cost component and a lifetime discounted power cost to provide the ventilation.

The simulation will only report airways which are over-restricted and potential cost savings exist by making the airway larger. While smaller airways could also be more economical, Ventsim ignores this option as this type of airway is usually sized for a certain means (eg truck access), and it would be distracting to report all possible size reductions. To check individual airways for size reduction options, it is suggested the Quick Select, or Graph Select Financial optimiser be used, or the Suggest (?) button in the Edit airway form.



Figure 26-3 Global Optimisation

26.2. Cost Data Function

The program contains a number of data types which show ventilation costs per annum for airways. These are located under the colour and text ENERGY category and include fan/fix power costs, friction losses per airway and friction losses per unit length.

Perhaps the most useful way to consider ventilation costs is not to look at the cost of running fans, but rather look at the cost of pushing ventilation through individual airways located throughout a mine.

Of all the cost data function, perhaps one of the most useful is the friction cost per unit length. This describes the friction pressure loss along an airway length, and is directly proportional to the ventilation cost per unit length of development.

For example, if a particular airway reports a ventilation operating cost due to friction loss of $800/yr per metre, then over a mine life of 10 years, the total cost of pushing ventilation through the heading is $8000 per metre. It is not hard to see that increasing the mined airway size slightly for (say) an additional mining cost of $500 per metre will quickly pay dividend in reduced ventilation costs.

By using the Ventsim Visual™ Display Manager, and colouring data to the ventilation cost per annum per unit length, high cost airways will be highlighted, and can be quickly identified and analysed for potential different sizes.

26.2.1. Example

In the 'Blue-Sky' example presented below, the data colour display is set to Head Cost/L (friction pressure cost per metre). The colour sliders are adjusted to show airways costing greater than $2 per metre per year. Airways below this are made transparent to clarify the display.

The data clearly shows in particular two air shafts with extremely high costs per metre, one in particular at over $600 per metre per year, as well as a horizontal connecting airway costing nearly $300 per metre. If the mine life was substantial, it would not be hard to justify enlarging or installing a second shaft system to reduce overall ventilation costs.

In this case, increasing shaft size from 3.0m to 3.5m reduced per metre annual ventilation costs from $600 per metre to $250 per metre. Over 10 years, this would result in a saving of $400,000 for this relatively short airway.



Figure 26-4 High Cost Airways coloured to show clearly

26.3. Ventilation on Demand.

An increasingly popular method of reducing ventilation costs is applying ventilation only when and where it is needed. While simple in principle, this fundamental approach provides significant challenges when applied to complex models. Changes or reductions in ventilation flows can significantly impact other areas of the mine, resulting in recirculation and heat and gas build up.

Using Ventsim Visual, different scenarios can be easily examined by simulating potential changes, such as reducing or turning off fan flows or reducing refrigeration.

The model summary will predict savings made in ventilation costs and power for the change.

The recirculation checker in Visual Advanced will quickly check for any recirculation resulting from the change.

The contamination and diesel particulate tools (in the Advanced version) will estimate any change to exhaust and potential fume.

The thermodynamic simulator will identify any unacceptable changes to temperature

Doors, fans and stopping can be quickly placed to control model airflow to acceptable levels and provide useful information as to what automatic controls may be required to achieve the ventilation changes.

26.4. Fan Optimisation



Correctly sized fans can significantly reduce operating costs.

Ensure airflows are not significantly overdesigned, and fan curves and duty points are closely matched to run efficiently. Many fan curves rapidly lose efficiency away from the central duty points, resulting in poor performance and excessive power consumption.

The fan efficiency and power consumption can be examined under the Edit Box fan menu. Ideally, the fan efficiency should have the operating duty point close to the maximum fan efficiency.

A further way to boost fan flow and efficiency is to ensure an evasé is fitted to surface exhaust fans. Fan evasés reduce surface velocity pressure losses, increasing available fan static pressure to overcome mine resistance. The overall effect is improved airflow at a similar cost.

Finally, overall model efficiency is largely influenced by the configuration of fans throughout a model. The use of 'in-series' booster fans underground for a single primary ventilation circuit should generally be avoided if possible, as fan efficiencies are compounded as the same airflow travels through each fan (booster fans may however be useful in directing airflow into parts of a mine which would otherwise require

inefficient regulators on the primary vent flow to do so). The result compared to a single pass fan system is higher power for similar airflow. The overall model efficiency is available from the model summary function.

Chapter

27

27 TUTORIAL - MODEL EXAMPLES

Several model examples are included with the Ventsim program. The first example below describes the method used in creating the model file EXAMPLE1.VSM

27.1. Example 1

An underground mine is to be designed from near the base of an open pit that is 100m deep. A decline will extend down some 140m below the pit floor, travelling adjacent to a sub vertical orebody. Three drilling / production sub levels will branch off the main decline every 40 vertical metres, starting at 60m below the pit floor. Main production will be from the bottom two levels. A ventilation shaft some 400m away (outside the pit boundary) extends from the mine base to the surface, connecting all sub levels. An exhaust fan on the shaft will need to pull 150m3/s to supply the mines production needs. Fresh air is supplied to the mine via the main decline.

1. Conceptually design a mine ventilation model incorporating the three simple sub levels. Ensure air is supplied equally to each level.

2. Due to power restrictions, main exhaust fan power must not exceed 300kW. What diameter shaft should be mined?

3. Emergency plans require stench gas to be delivered from the decline portal to all parts of the mine. What is the maximum time for the stench gas to be delivered to all areas of the mine?

27.1.1. Suggested Steps

4. Select the toolbar ADD function , and set the view to Plan.

5. Establish an initial working elevation by using the Set Edit Centre function under the View menu.



Figure 27-1 Set the starting edit location



Figure 27-2 Enter the starting elevation of the drawing (edit) plane

6. Draw a decline loop, using the Construct Ramp function in Ventsim

7. 



Figure 27-3 Construct an initial ramp decline

8. From the ramp base, use the ADD button (looks like a pencil) to draw horizontal airways across to a 'shaft' location. Add some additional detail if you like.



Figure 27-4 : Draw horizontal airways from the ramp base

9. To create a shaft, the easiest way is to CLICK the end of the airway while in the drawing ADD mode. This will allow the coordinate or offset of the shaft to be entered. For example, to create a 200m high shaft, simply enter '200' as the Z offset.



Figure 27-5 Construct a shaft to the surface

10. To create additional sublevels, simply draw new airways across from the ramp to the shaft.



Figure 27-6 Draw multiple levels for the mine

11. Edit the shaft airways and set them to a required size. Label the airway, and set the airflow as a fixed airflow to the desired amount of 150m3/s. **Ensure** the airway has the 'Surface Connection' checked. Click on the top decline ramp airway, and also ensure the 'Surface Connection' is checked. Click on Air Simulation to ensure everything works correctly.





Figure 27-7 Edit the airway to set the airway size

12. Click on the sublevel entries to the exhaust shaft. Use the LIMIT FLOW function to set the 1st and 2nd sublevel airflows to 50m3/s. The lower sublevel will automatically simulate to 50m3/s to balance the 150m3/s total airflow into the shaft. Clicking on the Edit Box info will show the required resistance to produce this airflow.



Figure 27-8 Add a fixed airflow to the airway



13. Adjust the shaft diameter until the required power constraints are met. Ensure you simulate the model between each adjustment. In this case, a shaft size of 2.5m was found to produce the desired result. The required duty point is 976Pa Total Fan pressure, 150m3/s with a fan motor size of 288kW and an electrical power consumption of 303kW.



Figure 27-9 Use the Edit – Info to view airway flow, pressure and power

14. To perform a stench gas simulation, place a contaminant in the upper decline with the Edit Box. Set the contaminant to a strength of 100, and run the contaminant simulation. The colour display will initially show a strength of 100 is spread all through the mine, which is to be expected as the decline is the only source of fresh air. Change the Display Manager to show 'Spread Time'. The lower corner will show spread times of up to 600 seconds or around 10 minutes.



Figure 27-10 Colouring showing contamination spread time in seconds

If you got this far, congratulations!

The complete example is available from the Ventsim Visual™ installation folder under Examples.

27.2. Example 2

A skeleton model has been created in a mine planning package by tracing over the existing and planned development and exporting the file as a DXF format file. Import this file into Ventsim and adjust it to create a workable model. Note that the decline is 5.5m x 5.5m, the sub level drives are 4.0m x 5.0m and the ventilation shafts are 2.4m diameter.

1. Create an RL (reduced level) elevation database that separates the mine into each sub-level. Create a RL that also displays the entire mine.

2. Create three PRIMARY Layers, and set the DECLINE, SUB-LEVEL and SHAFT airways to these Layers.

3. Divide the mine into fresh & exhaust air with the DECLINE carrying fresh air, and the SHAFT and the upper sub level carrying exhaust.

4. Create some saved views showing the;

   - whole mine with exhaust and fresh air showing.
   - decline by itself.
   - two upper sub-levels and corresponding shafts.

27.2.1. Suggested Steps

5. Initially set the default airway sizes (in the Settings>General>Airway Defaults menu) to 4.0 x 5.0m. This will set all imported DXF airways to these defaults sizes, and therefore the majority of airways will not need to be adjusted after importing.

6. File > IMPORT the DXF file into Ventsim, converting the dxf centrelines directly to airways (import option). Another method is to import the lines as a reference only, and then selectively choose or fence which lines to convert using the Airway > Convert Centreline toolbar button option (next to the ADD button)



Figure 27-11 Initial imported DXF strings in Ventsim Visual

7. Create an RL database with the RL MIN & MAX covering each sub-level range. Use the TOOLS > LEVELS menu option for this.



Level Number	Level Name	Range Min m	Range Max m
1	Surface	1340	1400
2	Level 1	1340	1280
3	Level 2	1280	1210
4	Level 3	1210	1180
5	Level 4	1180	1154
6	Level 5	1154	1100
7	Level 6	1100	1080
8	Level 7	1080	1052
9	Level 8	1052	1030
10	Level 9	1030	980
11	Level 10	980	910
12	Level 11	910	840
13		0	0
14		0	0

Figure 27-12 The Level Elevation database

8. Create the new Primary layer names by utilising the Preset Value forms. Select this from the SETTINGS > PRESETS Menu, or click the Primary Layer button on the colour toolbox.



Figure 27-13 Set airway layer names

9. Use the group edit function to select the decline airways

10. Use the select toolbar button to select all decline airways
11. Use the edit toolbar button to edit all selected airways.
12. Change the primary layer name to Main Decline
13. Change the air type to Fresh
14. Change the airway dimensions to 5.5m x 5.5m
15. Apply the changes to the selected airways



Figure 27-14 Initial selection of all decline airways



Figure 27-15 Select and edit the decline airways

16. Repeat the above actions to set the other airways parameters for shafts and sub-levels.

17. Finally, add fans, ventilation controls and stoppings to direct airflow through the model.



Figure 27-16 Fresh and Exhaust Air Type colouring

18. To limit the view to the decline or shafts only using the layer control in the display selection to control which layers are displayed.







Figure 27-17 The final DXF import result showing the decline and the exhaust shafts displayed independently with layers.

27.3. Example 3 – Import a Complex Mine Design

A centreline model of an entire existing mine has been created in a mine planning package and

exported to Ventsim. Import this file into Ventsim and adjust it to create a workable model.

Import the DXF model into Ventsim. Do not convert the centrelines to airways at this stage. The imported model will show as a collection of line strings.

Select the Tool button DRAW > CONVERT CENTRELINES. Draw a fence around the centreline strings (in this case all the strings) to convert to standard size airways.





Figure 27-18 Resulting conversion with colour levels reset

Many airways will have complex curves or may not connect properly. To tidy up the import we need to "Simplify and Bind" the new airways. Use the **TOOLS > FILTER function** to activate this option.

Click on SIMPLIFY. This will remove unnecessary detail, allowing for a simplified and easier to work model.



Click on BIND, increasing the bind search distance to 8m to ensure broken airways are joined together. Press the BIND button several times to ensure all optimisation have been found.

Establish the surface connections. Ventsim needs to know which airways connect to the surface; otherwise the program will consider them as dead ends where no air can flow.



Establish airflow by placing a FIXED FLOW on one of the major surface connections. At this stage we are not trying to simulate an actual fan installation, but just trying to establish that air can travel through all airways in the model.





Press SIMULATE. Many warnings will show indicating airway dead ends which are not closed off or connected to other airways. Ensure that airflows are travelling through parts of the mine where is should travel. Use the flow animation and/or airflow colouring to indicate good and bad flow areas. If areas are not flowing air and that should be flowing air, check for any breaks in airways through the region and SIMULATE again after any changes.



Once airflow is correctly established (at this stage we are not interested in establishing accurate airflows, just making sure air has an open connected pathway to follow), then SELECT all of the airways which are still showing NO EXIT / ENTRY warnings, EDIT the airways and select CLOSE ENDS in the Edit Box.

Figure 27-19 Airways coloured by airflow



SIMULATE again. No errors or warnings should show. If they do, repeat the search for airway error and simulate again.



The model is now ready to be correctly sized, with all fans and ventilation controls established. Select and change the airways and set them to the correct size. Insert fans and control in proper positions. If desired, use LAYERS and text names to help improve accessibility to your model.

Chapter

28

28 APPENDIX A – GLOSSARY OF TERMS

28.1. A glossary of commonly used terms

28.1.1. Airway An section of underground tunnel defined by two end points.

28.1.2. Branch An airway; a tunnel or shaft that carries airflow.

28.1.3. TXT TAB Separated Value file - a text file format used by Ventsim when saving uncompressed files. This format can also be read into Spreadsheets, Word Processors and databases.

28.1.4. DXF Drawing Exchange Format - An AutoCAD graphics file format that can be imported and exported by most CAD and Mining Software packages. Ventsim can also import or export data in this format.

28.1.5. Endpoint / Start point The start or end of an airway, defined by an x, y and z coordinate, which gives its position in space in three dimensions.

28.1.6. Friction cost Similar to friction power, with the kilowatt value converted to a dollar cost per annum, based on the default power cost.

28.1.7. Friction factor or k factor Atkinson's friction factor, describing the roughness or unevenness of a wall. It directly affects the resistance of an airway. Friction factors are measured to a specific air density, normally normalised to 1.2.kg/m3

28.1.8. Friction loss A component of pressure drop along an airway caused by the airway resistance.

28.1.9. Friction power Derived from the friction loss, this estimates (in kilowatts), the amount of energy lost due to the resistance of an airway on the airflow.

28.1.10. Hardy- Cross Method The simulation method used by Ventsim Visual™ to perform the calculation of airflows in a model. It uses an iterative estimation method that adjusts the airflows through a model until the estimation errors lie within acceptable limits. Ventsim Visual™ Advanced uses a modified method which takes into account density changes and mass flow balances.

28.1.11. Junction A point defining where two or more airway ends share the same position. Airflow at this point can split or join, depending on airflow direction.

28.1.12. Load (Pressure) Estimation of how much load or weight an airway pressure loss would develop across a resistance. It is often used for determining load on a vent door or bulkhead and is calculated by the pressure loss times by the drive or resistance area.

28.1.13. Network An interconnect series of airways that together form the model of an airflow design.

28.1.14. Node A point defining the end or junction of an airway(s)

28.1.15. Pan The action of sliding the model graphics to a new screen position by using the right mouse button.

28.1.16. Pressure loss The loss of air pressure along a length of airway due to friction loss, fans, fixed pressures or fixed quantities etc.

28.1.17. Resistance A value describing the difficulty air will have moving down an airway. It is derived from a combination of airway size, friction factor, length, shock losses and air density.

28.1.18. Shock loss A factor that estimates the effect a change in drive direction or size has on airflow. Any such change will increase turbulence in an airflow, and hence develop energy losses that can be equated to an increase in airway resistance. Ventsim Visual™ uses shock loss as an extra length added on to the original drive length (i.e. the higher the shock loss, the greater the equivalent length), which in turn increases the overall airway resistance.

28.1.19. Thermal Diffusivity Thermal diffusivity is the ratio of thermal conductivity to volumetric heat capacity. Substances with high thermal diffusivity rapidly adjust their temperature to that of their surroundings, because they conduct heat quickly in comparison to their volumetric heat capacity or 'thermal bulk'

28.1.20. Thermal Conductivity Thermal conductivity, k, is the property of a material that indicates its ability to conduct heat. It appears primarily in Fourier's Law for heat conduction.

28.1.21. Wetness Fraction The ratio of area of wet airway surface to dry airway surface. A fully wet surface is defined as '1.0' while a fully dry surface is defined as '0.0'

28.1.22. Relative Humidity Relative humidity describes the amount of water vapour that exists in a gaseous mixture of air and water. It is defined as the ratio of the partial pressure of water vapour in the mixture to the saturated vapour pressure of water at a prescribed temperature. Relative humidity is normally expressed as a percentage

28.1.23. Density The density of a material is defined as its mass per unit volume. The density of air influence many psychrometric properties. Te density of rock influences heat transfer and thermal capacity behaviour.

Chapter

29

29 APPENDIX B – SUMMARY OF DATA TYPES

29.1. Summary of the major data types

Available from the data selection menus in the menu bar. Note that additional data and data subsets are available in the spreadsheet view.

29.1.1. Air types

Airtype The type of category of air in the model. Originally designed for specifying fresh, exhaust and undetermined air within a model, Ventsim Visual™ allows custom catagories for air types, set from within the Edit menu. When specified in the Display Manager, airtype will show different colours for different air types.

29.1.2. Airflow

Quantity The volume flow rate of air through an airway

Velocity The average speed of airflow through an airway across the cross sectional area

Density The average (wet) air density along an airway. For vertical shafts, this is the air density mid way along the shaft.

Mass Flow The (dry) mass flow of air through an airway. This is a function of volume flow and air density. Note that this will not necessarily be equal to the quantity x wet density value, because the mass flow does not consider the moisture component that is included in the density value.

29.1.3. Pressure

Pressure Boost The increase in pressure provide to a model system by an external source, such as a fan or fixed flow.

Pressure BoostStatic The fan static pressure equivalent of the pressure boost.

Pressure Regulator Load The pressure or force against an airway resistance converted to an equivalent 'weight'

Pressure TotalLoss The total pressure loss along and airway between entry and exit. Pressure loss may consist of airway friction pressure losses, due to wall friction factors and additional resistances placed

in the airway

Pressure Relative The relative pressure differential between underground airway and the surface, standardised to the surface elevation. A relative pressure differential of zero, would result in no flow from a connecting airway to the surface. A negative relative pressure would see air flow from the surface to the underground airway if a path was present. A positve relative pressure would see air flow from underground to the surface if a path was present.

Pressure Absolute The pressure reported in atmospheric units of an underground airway, corrected to surface elevation. The correction removes the effect of elevation on pressure, and permits a relative assessment between airways at different elevations.

Pressure Barometric The true pressure reported in total atmospheric units including the elevation effects on total pressure. Barometric pressure increases with depth, where no other pressure influences are present.

Pressure FrictionLoss The loss of pressure along an airway due to wall friction. This ignores any other resistances in the airway such as doors or stoppings.

Natural Ventilation Compares density differences of a column of mine air with an equivalent column of atmospheric air and applies a pressure differential. Every airway with a different entry and exit elevation has potential to have some natural ventilation. Ventsim Visual™ uses a +(ve) number convention to describe upwards (buoyant) natural ventilation and –(ve) to show downward (sinking) natural ventilation.

Note that by default, atmospheric density is adjusted for temperature gradient (lapse) rate, in much the same way as auto compression can drive changes in underground temperature at different elevations. Inlet airways at different elevations will have different temperatures which are derived from the standard elevation and default surface temperature. This function can be turned off (surface temperature adjust) in the settings if desired.

29.1.4. Airway Attributes

Resistance Total airway resistance along an airway. The resistance is standardised to the surface density, and includes any additional resistance added by the user such as doors and stoppings.

Resistance Wall Resistance due to airway wall friction along an airway. It does not include any additional resistances added.

Shock The shock value reported as either a shock factor (X) or an equivalent airway length. Both factor types add additional resistance to an airway, and increase pressure loss due to air turbulence caused by a bend, change of size or other obstruction. The shock length type can be set in the setting menu.

Friction Factor kfactor Atkinsons friction factor describing the uneveness of an airway wall, resulting in near surface turnulence and increase airway resistance. Friction factors are standardised to the surface density.

Dimensions The size of an airway width and height as the centre section.

Perimeter The perimeter of an airway, calculated from the centre height and width, taking into account the airway shape profile. The perimeter can also be set directly from the edit menu.

Area The area of an airway, calculated from the centre height and width, taking into account the airway shape profile. The area can also be set directly from the edit menu.

Length The true length of an airway, used to calculate airway resistance and heat transfer. It does not include additional shock lengths if specified.

Coordinates Report the coordinates of an airway in eastings, northing and elevation.

29.1.5. Energy, Power Cost

Power Loss The friction loss along an airway converted to an equivalent theoretical work load. This value does not include power efficiencies which would result if the pressure loss was to be overcome electrically.

Power Loss/L The friction loss along an airway converted to an equivalent theoritical work load per unit length. Because the loss is standardised to a unit length, this value is independent of the actual length of the airway.

Power Input The electrical input power into a model to generate pressure and airflow. The power input includes efficiency losses due to fan blade efficiency but does not include motor efficiency losses.

Head Cost The theoretical cost of the power loss due to friction converted to an annual electrical cost, based on the power cost set in the Settings.

Head Cost/L The theoretical cost of the power loss per unit length due to friction converted to an annual electrical cost, based on the power cost set in the Settings. Because the loss is standardised to a unit length, this value is independent of the actual length of the airway.

Fan/Fix Cost The electrical input power by a fan or theorectical fix flow into a model to generate pressure and airflow. The electical input includes both fan or fix efficiency factors and an electrical motor efficiency factors specified in the Settings.

29.1.6. Thermo - dynamics

Wet bulb Psycrometric properties of air decribing the temperature a volume of air would have if cooled adiabatically to saturation at constant pressure by evaporation of water into it.

Dry bulb Psycrometric property of air describing the temperature of air measured by a thermometer freely exposed to the air but shielded from radiation and moisture.

Effective Temperature An older index of heat stress still commonly used. Ventsim Visual™ uses Basic Effective Temperature. Wet or Dry bulb temperatures below 20 degrees celcius or above 36 degrees celcius should be treated with caution as the Effective Temperatures are not normally calculated beyond these limits, and Ventsim only provides a correlated estimate. The Effective Temperature is defined as the temperature of still saturated aur which would give the same

thermal feel as the actual environment being consdered. The Air Cooling Power methods described below are generally considered to provide a better index of cooling.

Dew point The dew point is the temperature to which a given parcel of air must be cooled, at constant barometric pressure, for water vapor to condense into water.

Cooling Power cooling power of mine air determines the capacity of the ambient atmosphere to dissipate the metabolic heat generated by humans. The cooling power is measured in W/m2 (amount of heat removes from the human body per second per unit surface area) to keep skin temperature (ACPM method) or body core temperature (TWL method) below safe limits. It is dependent mainly on the wet bulb temperature and the air velocity.

TWL Method. Developed in Australia and based on body core temperature limits, the Thermal Work Limit method has been developed from a physiological basis and ratified by the Australian Institute of Occupational Hygienists (AIOH). It has been adopted by many Australian mines, and uses standard clothing and sweat factors. The method ideally requires globe temperatures for accurate resutls. As these are not available from a simulation, the TWL may be underestimated for workers around radient heat sources such as machinery or hot rock.

ACPM Method. Developed in the USA, the Ar Cooling Power (M scale) method is based around limiting skin temperature factors as an indicator to body core temperature. The method is in use in most North American mines. Results are highly dependent on clothing and work output factors. Ventsim Visual™ defaults to standard light clothing. Again the method ideally requires globe temperatures for accurate resutls. As these are not available from a simulation, the ACPM may be underestimated for workers around radient heat sources such as machinery or hot rock.

Kata Method. Developed in South Africa, the Kata cooling method uses the wet bulb and air velocity to develop a heat stress index representing cooling ability of the air.

Sigma Heat The sum of sensible heat and latent heat in a substance above a base temperature, typically zero (0) degree Celcius or 32 degrees Fahrenheit. Sigma Heat is independent of dry bulb temperature, relying only on wet bulb temperature and pressure to derive it value.

Enthalpy Similar to Sigma heat, it is the sum of the total heat content of a unit weight of air (including the water vapour) at typically zero (0) degree Celcius or 32 degrees Fahrenheit. Unlike Sigma Heat, it does not however take into account the adiabatic saturation process, and is therefore not as useful pscrometrically.

Energy Flow The sum product of air 'mass' flow and Sigma Heat along an airway. The value is useful to determine the amount of heat an airflow has gathered or lost along an airway.

Relative Humidity Relative humidity describes the amount of water vapour that exists in a gaseous mixture of air and water. It is defined as the ratio of the partial pressure of water vapour in the mixture to the saturated vapour pressure of water at a prescribed temperature. Relative humidity is normally expressed as a percentage

Moisture Content The unit mass of moisture per unit mass of dry air

Condensate The volume flow rate of moisture condensed from an airflow (normally due to refrigeration or pressure drop up a shaft)

Heat Added/L Sensible plus Latent heat from all airway heat sources per unit length

Sensible Heat/L Sensible heat from all airway heat sources per unit length

Latent Heat/L Latent heat from all airway heat sources per unit length

Sensible Heat Sensible heat from all airway heat sources

Latent Heat Latent heat from all airway heat sources

External Heat Heat added or removed by the user, excluding strata heat input.

29.1.7. Descriptors



Airway Number The internal array number of an airway, reference by Ventsim Visual. Ventsim Visual™ will report this number during error description. The airway number may change as airways are added or removed from the model.

Airway Name The name of an airway branch. The name can be entered in the airway EDIT box. The name does not affect simulation but may assist the user in identifying or finding airways.

Node Name The name of an airway junction. The name can be entered in the airway EDIT box

Unique ID Number A unique number assigned to every airway, that does not change when airways are added or removed. As a result, the numbers may not be sequential and may have large gaps in the sequence.

Shock Name The descriptive name of the shock loss on the airway

Airway Type The descriptive name of the airway type set in the EDIT box.

Profile The descriptive name of the profile if set.

Friction Factor The descriptive name of the friction factor.

Primary Name The layer nane and number of an airway primary layer

Secondary Name The layer nane and number of an airway secondary layer

29.1.8. Contaminants

Spread Mix Contaminant simulated concentrations through a model. The value is unit independent and is normally relative in concentration to the original set values.

Spread Time The time in seconds that contaminant takes to appear in airways downstream from the source. The time is calculate by an average cross-sectional speed along all airways. It does not take into account the changing velocity profile, or incomplete mixing at junctions. As a result, it is likely in most cases, that a smaller portion of the contaminant will arrive at an airway location ahead of the predicted time.

Source Mix The portion of a contamination that has tranvelled along upstream airways to the location of the set contaminant. The value is a ratio of the airflow that contributes to the total volume of air flowing through the contaminant source airway.

Sourcing Tool The category of air simulated in the sourcing tools simulator. The sourcing tool simulates fresh air, contaminated air, and potential source of contaminated air.

Diesel Particulate Matter Weight per unit volume of diesel particulate matter in a volume of air.

Recirculation The portion of air that has recirculated through the airway

Recirculation Stream The maximum portion of air that has recirculated through any single airway upstream from the airway. This may assist in determining the quality of air travelling through an airway if it has undergone recirculation at some point upstream from the airway.

29.1.9. Rock Properties

Conductivity Thermal conductivity of rock in the airway.

Density Density of rock in the airway.

Specifc Heat The specific heat of rock in the airway

Wetness Fraction The fraction of wet to dry surface of the rock in the airway. A fraction of one (1) represent fully wet, while zero is dry.

Age The age of the rock since exposed by mining in either decimal years (eg 2005.5 = end June 2005) or by a fixed relative age (eg 4.5 = 4.5 years or 4 years and 6 months)

Thermal Diffusivity The thermal diffusivity of rock within an airway.

VRT The virgin rock temperature; the rock temperature before the airway excavation and airflow may have cooled the surrounding rock mass.

29.1.10. Measured

Unused at this time in Ventsim Visual™ version 3.0

29.1.11. Gas

The gas contamination levels of a wide range if gases. During simulation, Ventsim volumetrically balances non-fixed gases to ensure 100% total volumetric concentration.

Note that RADON gas at this time is NOT simulated for radon daughter decay.

Chapter

30

30 APPENDIX C – ICON PICTURE GUIDE

30.1. Airway Icons

A number of **icons are used in Ventsim Visual™ to represent various airway attributes**. The icons are displayed on top of the airway solid or wireframe, and indicate the presence of a specific item. Multiple attributes in an airway represented by icons are shown side by side.

Icons can be turned off or on from the Display Manager or from the right mouse button context menu.

Icons can be MOVED along airways by selecting the MOVE function from the toolbar and dragging the icons along the airway with the left mouse button.

Icons can be COPIED to other airways by selecting the COPY button function from the toolbar and dragging the icon to a new airway.

30.2. Customized Icons.

Fan, resistance and heat icons can be customized in Ventsim. Providing the icon is established with a PRESET name (for example a resistance could be labeled in the preset list as a 'steel door'), a picture file can be dragged on to the icon externally from a Windows file windows or manager. The picture file can be formatted as a jpg, png or gif file. In addition, the GIF format also supports animated pictures which will be displayed as an animated icon in Ventsim



Figure 30-1 Customised Truck Picture

30.2.1. Fans



Fan icons are used to **represent the presence of a fan**. Fans can be shown in four different colours.

Green – normal operating fan

Blue – fan turned off and not operating

Yellow – fan operating in reverse

Red – fan stalled and air being forced backwards through fan

30.2.2. Blocked Airway



Blocked icons indicate an airway blockage or very high resistance has been placed and air cannot travel freely through the airway. Blocked resistance values are set in the preset menu. If blocked resistance values are above the maximum resistance specified in the Settings, then absolutely no airflow will be permitted along the airway.

30.2.3. Airway Resistance



Indicates the presence of an airway resistance, above the normal airway resistance calculated from the size, shape and wall friction factors. An airway resistance normally represents an inputted resistance feature from the Edit Form, which may be a door, stopping or some other airway restriction.

Yellow – normal operating resistance setting with a preset value

Green – a custom resistance value entered specifically for that airway

Red – a preset resistance operating on a reversal resistance value, which has been activated by a reversing airflow and a 'restrict reversal' option specified for the airway in the EDIT form.

30.2.4. Fixed Airway


Animated

Fixed airflow placed in airway.

Green – once simulated, green indicates the fixed airflow is acting as a positive pressure, i.e. it is contributing towards overall pressure in the mine model

Red – once simulated, red indicates the fixed airflow is retarding normal airflow, and reducing pressure – i.e. it is acting as a resistance and contributing to overall pressure loss in the model.

30.2.5. Fixed Pressure


Animated

Fixed pressure source placed in the airway.

Green –green indicates the fixed pressure is acting as a positive pressure, i.e. it is contributing towards overall pressure and flow in the mine model

Red – red indicates the fixed pressure is negative and retarding normal airflow – i.e. it is acting as a resistance and contributing to overall pressure loss in the model.

30.2.6. Contaminant Report



Indicates a contaminant report has been placed within the airway. A Contaminant Find simulation will use this report to indicate pathways of contaminants and potential sources of the contaminant.

30.2.7. Fresh Air Report



Indicates a fresh air report has been placed within the airway. A Contaminant Find simulation will use this report to indicate pathways of fresh air through the mine.

30.2.8. Contaminant

 Animated

Indicates the presence of a contaminant in the airway. A contaminant simulation will predict the path and concentration of the contaminant downstream. A sourcing simulation will predict the paths and relative amounts of sourced air travelling to the airway.

30.2.9. Gas

 Animated

Indicates the presence of a gas mixture in the airway. A gas simulation will predict the path and concentration of the gases downstream.

30.2.10. Thermo- dynamic Heat or Moisture Source



Indicates the presence of a positive heat or moisture source in the airway. A Thermodynamic simulation will mix the quantities and distribute the changes downstream. A **grey** colour indicates the preset heat or moisture has been turned off in the Edit box.

30.2.11. Thermo- dynamic Cooling or Drying Source



Indicates the presence of a negative heat source (cooling or refrigeration) or a moisture removing source in the airway. A Thermodynamic simulation will mix the quantities and distribute the changes downstream. A **grey** colour indicates the preset heat or moisture has been turned off in the Edit box.

30.2.12. Airway Notes



Indicates text notes have been made for the airway. Text notes can be viewed by clicked the airway with the Edit Form, and selecting the Notes Tab.

30.2.13. Surface Connected Airway



Indicates an airway is connected to the surface. Surface airways can draw or discharge mine airflow to or from the atmosphere.

30.2.14. Unknown Airway End



Defines the end of an airway in construction that has neither been flagged as a surface connection or a closed (dead) end. Headings with these symbols may raise a warning during simulation, and will be assumed to be a dead end.

30.2.15. Orifice



Indicates an orifice restriction is present in the airway. Orifices indicate smaller opening in a wall such as a regulator and may be used to apply additional resistance to an airway.

30.2.16. Backfill



Indicates the presence of backfill in an airway. Backfill will obstruct the airflow by narrowing the airway passage. In addition, backfill will insulate a portion of heat transfer into the airflow from the surround rock strata during heat simulation.

30.2.17. Obstruction



Indicates an obstruction is present in the airway. Obstructions reduce the area of the airway for the length of the airway. They can be used to simulate pipes, compartments or structures that limit the airflow cross sectional area available.

30.2.18. Sensor



Indicates the presence of one or more sensors in an airway. A sensor can feed an external data source into a Ventsim model. It is used by the LIVEVIEW™ module to show external live data in a model.

30.2.1. Shock Loss



Indicates the presence of shock loss in the airway. The shock symbol (representing swirling air) is generally shown at the beginning where air enter the airway.

Chapter 31

31 APPENDIX D – DISPLAY PROBLEMS

Occasionally the user may find that the graphics displayed on the computer screen are not as intended. The following section will step through some common problems and resolutions

31.1. Hardware Problems

A large variety of graphics cards exists on the market today. While each type of card should perform in the same way (although some faster than others), there are many different manufacturers and software drivers that may cause differences in expected performance.

Chasm Consulting tests a wide variety of different cards to ensure optimum performance where possible.

If an issue exists, often updating the software driver from the card manufacture can help resolve issues. Due to the low price of 3D graphics cards, if the computer or graphics card is very old (greater than 5 years), it may be better to upgrade the computer or replace the graphics cards with a newer type.

31.1.1. Screen fails to display after coming out of 'sleep / hybernation'

The screen remains blank, or shows corrupted data when resuming from screen savers or hybernation. This is caused by the graphics card failing to send the correct message to Ventsim to enabled Ventsim to reset the card and restore the graphics.

Resolution In most cases the screen can be recovered by using the VIEW > REFRESH menu items. In extreme cases the software may need to be shutdown and restarted.

Updating the graphics cards software drivers can often help in this case. Alternatively, disable the screen saver / hybernation, and allow the computer to simply turn off the monitor instead.

31.1.2. Anti-aliasing does not work / is very slow

Only newer graphics cards fully support this image smoothing feature. Older graphics cards, particular INTEL motherboard types, do not support it. Low power graphics solutions from ATI or NVIDIA may support it, but graphics performance will slow.

Resolution No solution. Install a newer vidia card which supports full screen anti-aliasing or turn off anti-aliasing in the settings.

31.1.3. Custom Icons cannot be used

Only newer graphics cards fully support custom icons. Older graphics cards (particularly INTEL) may not have sufficient memory pointers to support the placement of potentially tens of thousands of icon images on the screen, therefore support for these cards has been disabled.

Resolution No solution. Install a newer vidia card.

31.2. Software Problems

Occasionally, the screen will not display graphics as expected. This can stem from a wide range of settings in Ventsim which may not be set correctly to display the desired graphics.

31.2.1. No Graphics Shown on Screen

The airways may be hidden or invisible, or located off the screen.

Resolution Use the VIEW > FIT ALL command to make sure the grpahics are relocated to the screen. If no graphics show, use the VIEW > SHOW ALL, to turn on all hidden layers and levels. If still no graphics show, ensure that airways are still present in the model, by running the RUN > SUMMARY menu option and ensuring a number of airways are present.

Finally, make sure that options such as VIEW > HIDE ZERO FLOWS, and VIEW > HIDE EXCLUDED AIRWAYS are not turned on.

31.2.2. I can see airways, but no text / arrows / nodes

The screen may only display the raw airways, but no other information.

Resolution The option to display text or arrows may be turned off (press 'T' or 'A' respectively to turn back on), or use the sidebar toolbar menu. If this does not work, the LIMIT command may be turned on. This command hides text / nodes / arrows if the airways is not specifically set on the EDIT form to show DATA. Turn the LIMIT option off using the 'L' button.

Chapter

32

32 APPENDIX E – SIMULATION ERRORS

The following messages may be shown if errors are present during model simulation. To select and view an airway with an error, simply click the error value in the Error List Box at the lower right corner of the screen. The select multiple airways for editing in Ventsim, click on the items (hold CTRL to select multiple items) and click SELECT.



32.1. Warnings

Warnings can generally be ignored, as the simulation will complete despite the warnings. They may however be a sign of a more serious problem, and should still be investigated.

32.1.1. no entry airway or surface connection There is no airway entering the airway, therefore no airflow can occur. The airway is not connected to the surface or marked as a 'closed end'. The program can be set to ignore these warnings in the Settings – Airflow Simulation menu.

Resolution Simply connect an airway to the entry, connect the airway to the surface, or marked as a closed end in the Edit Box.

32.1.2. no exit airway or surface connection As with no entry warning.

32.1.3. no entry or exit As with no entry warning description.

32.1.4. airway stopping redundant An airway stopping has been placed in series with another airway stopping. Only one stopping is required.

Resolution None required, although a stopping can be removed if desired.

32.1.5. fan interfering with another fan A fan has been placed directly in series with another fan. The pressure imbalance between the fan curves may cause difficulty in resolve the model, partiulcarly if one fan is operating outside of its specified fan curve.

Resolution. Recommmend removing a fan, or ensuring an alternative airway path is available to help

'bleed' pressure between fans.

32.1.6. Fix requires pressure

A 'limit flow' option has been place in an airway to slow down airflows, however the unrestricted airflow has been placed directly in series with another fan. The pressure imbalance between the fan curves may cause difficulty in resolve the model, partiulcarly if one fan is operating outside of its specified fan curve.

Resolution. Recommmend removing a fan, or ensuring an alternative airway path is available to help 'bleed' pressure between fans.

32.1.7. temperature balancing issue

Thermodynamic simulation is having difficulty resolving temperature balance between two airways. This may happen at extremes of temperature or pressure.

Resolution. Investigate what is causing high / low temperatures (eg high heat or refirgeration loads, coupled with low airflows). Resolve problem if possible. The Settings menu can be set to ignore this program, but this is generally not recommended.

32.1.8. stalled fan

The fan is operating at too higher pressure / low volume, beyond the limits of the fan curve.

Resolution None required, however fans should not be made to run outside the curve. Ventsim Visual™ must 'guess' a result, which could lead to errors.

32.1.9. low pressure fan

The fan is operating at too low pressure / high volume, beyond the limits of the fan curve.

Resolution. None required, however fans should not be made to run outside the curve. Ventsim Visual™ must 'guess' a result, which could lead to errors or air balancing issues. To remove the warning, increase the resistance the fan operates at, or extend the fan curve down to zero pressure.

32.1.10. negated fan

The fan offering no additional pressure to the model, and may actually be retarding airflow.

Resolution. None required, however fans should not run as negated. Ventsim Visual™ must 'guess' a result, which could lead to errors or air balancing issues. In most cases, fan negation occurs as a result of other fans drawing air through the fan at a flow above the maximum fan curve quantity. To remove this warning, consider removing or switching off the fan.

32.1.1. Water suspension velocity

The airflow in an upcasting shaft fall between the critical velocities that may cause the water to be suspending in the shaft.

Resolution. None required. This warning shows when the Settings > Airflow Simulation > Water Suspension checking is set. From a design point of view, this situation may not be desirable and the airflow may need to be increased or decreased to ensure velocities fall outside of the critical range.

32.2. Errors

Errors will generally halt a simulation process, and must be corrected before a valid simulation can occur.

32.2.1. airway attempted to reverse

An airway set as 'restricted reverse' in the Edit box was attempted to be reversed by the simulation. As a result, the simulation is halted.

Resolution This function is designed to warn the user about airways which should not have reversed airflow. To remove this error, simply unclick the option in the Edit Box for the airway.

32.2.2. Anomalous pressures An design in a netwok has resulting in a huge buildup of pressure, beyond allowable levels. This causes the simuliation calculation to corrupt and breakdown. Because Ventsim uses somes of the results of previous simulations for current calculations (for example fan pressures are used to help calculate air density), this may corrupt future simulations as well

Resolution Allow Ventsim Visual™ to automatically reset the model. The model can also be manually reset from the Tools Menu. The cause of the pressure buildup should be investigated. It usually stems from overuse or restriction of fixed airflow, or too many high resistance (bulkheads) blocking off a working part of the model and restricting flow balanacing. Occasionally it may be due to airways not being connecting properly, restricting movement of air, which can be resolved with the Tools > Filter > Bind command.

32.2.3. Duplicate airway An airway with te same entry and exit location as another airway has been created.

Resolution Allow Ventsim Visual™ to delete the duplicate airway.

32.2.4. Fixed flow cannot be achieved An airway has a fixed flow placed in line with another fixed flow, resulting in a conflict between the two flows, or a fix flow is placed in a locaton where it cannot draw air.

Resolution Remove one of the fixed flows, or ensure a path between the flows exists to balanced the flow difference. Ensure there are no breaks in any airways leading to or from the fixed flow, through which airflow cannot travel.

32.2.5. Fix being over-restricted A fix flow encounters too much resistance to flow the required air quantity causing a massive buildup in pressure.

Resolution Check to ensure pathways before and after the fix are connected to the model or surface, and can freely flow air, and no blocked resistances are present in the pathways before or after the fix. Airways that are not exactly connected cannot carry airflow. While a no entry/exit warning will normally highlight these airways, if 'allow closed end' has been selected, then no warning will show, and the problem may be difficult to find. Try the wireframe mode with nodes displayed if this is a problem.

32.2.6. operating fan blocked A fan has been placed in an airway through which no air can flow.

Resolution As with 'fix stopped', check to ensure restricting blocked resistances are not present, and the airways before and after the fan can carry air.

32.2.7. convergence problem The model cannot find a resolution in the model airflow balance.

Resolution Ensure fans are not running stalled or negated, and no unusual pressures or flows exist within the model.

32.2.8. temperature outside allowable range Temperature is increasing or being reduced beyond the allowable range.

Resolution Investigate what is causing high / low temperatures (eg high heat or refirgeration loads, coupled with low airflows). Ensure airflow is adequate for heat addition or removal amounts. Reduce heat input if possible, or increase airflow.

32.2.9. heat estimation error encountered A general error in estimating thermal properties occurred. This normally occurs where air temperatures or pressures are welll outside of the expected range.

Resolution Investigate what is causing high / low temperatures (eg high heat or refirgeration loads, coupled with low airflows). Ensure airflow is adequate for heat addition or removal amounts. Reduce heat input if possible, or increase airflow.

32.2.10. temp estimation near rock surface An error estimate transfer of heat flux from rock strata surface to airflow. This may happen where an extremely low airflow exists, or temperature or moisture values in the air are unusually high or low. Where airflow is less than the error correction value in the air simulaton settings, Ventsim will not attempt to solve heat balance, and will simply assume the air temperature becomes the same as the virgin rock temperature.

Resolution Increase airflow through airway, or increase tolerance of massflow setting in the Settings menu, to ignore airways with low flow.

32.2.11. overpressure across resistance Pressure building up unacceptably over a high resistance airway, or a fan or fixed flow running into a high resistance airway. This error may occasionally show up when simulating Ventsim Classic 3.9 models with Ventsim Visual.

Resolution Investigate and remove the source of the high pressure (fan or fix) or remove the high resistance causing the buildup in pressure. Unlike Ventsim Classic 3, which ignore this error, this situation is unacceptable to Ventsim Visual, as it adversely affects air densities and heat buildup, and in nearly all cases is a result of user input error. Pressure above 15000 Pa are generaly used as a trigger for this error.

32.2.12. operating fan restricted by resistance A resistance has been placed in the same airway as a fan, and the fan is being unreasonably restricted. This is a common practise in Ventsim Classic 3.9 models to stop airflow through a fan. In Ventsim Visual, it can cause overpressure and heat buildup, and is therefore no longer permitted.

Resolution Turn the fan OFF instead from the EDIT form, of remove the fan. If the fan is turned OFF, click on SELF CLOSING if you want to ensure air does not leak back through the fan.

32.2.13. fix being over restricted Similar to overpressure across resistance, but the error code will target the airway with the fan or fix, not the resistance.

Resolution. Changing the fan or fix, or alternatively removing the high resistance will correct the problem.

32.2.14. unresolved pressure or flow Ventsim Visual™ cannot resolve of pressure or airflow volume during simulation

Resolution Ensure no unusually airways, fan pressure or pathways exist within the model model.

32.2.15. fan static P curve invalid, check fan No fan static pressure curve is available for the fan, but a static curve has been selected in

the Edit Box or the Settings Menu.

Resolution Enter a fan static pressure curve for the fan, or ;

change the Edit Box setting to a Fan Total Curve (FTP), or ;

change the Global Fan Pressure method in the Settings menu to Total Pressure Method.

32.2.16. fan total P curve invalid, check fan No fan total pressure curve (FTP) is available for the fan, but a total curve has been selected in the Edit Box or the Settings Menu.

Resolution Enter a fan total pressure curve for the fan or;

Change the Edit Box setting to a Fan Static Curve (FSP), or;

Change the Global Fan Pressure method in the Settings menu to Static Pressure Method.

32.2.1. Meshing error Ventsim Visual™ cannot create a workable mesh of airway loops (meshes) required for airflow and pressure balancing using the Hardy Cross method.

Resolution Ensure that there are not too many airways connected to the SURFACE. In addition ensure that airways are physically connected – use the TOOLS > FILTER option if necessary to allow Ventsim to ensure a connection.

Chapter

33

33 APPENDIX F – Shortcut Keys

A number of keyboard strokes exist to assist in rapid selection of commonly used functions. Most menu items have the shortcut key next to the menu item. Below is a general summary of common key strokes

CTRL N	**New File**
CTRL O	**Open File**
CTRL M	**Merge File**
CTRL I	**Inherit File Attributes**
CTRL S	**Save File**
CTRL F	**File Note**
CTRL C	**Clone Attributes**
CTRL V	**Apply Attributes**
CTRL L	**Lock On Target (Toggle)**
CTRL T	**Lock On Transparency (Toggle)**
CTRL Q	**Quick View**
LEFT Arrow	**Move to previous Quick View**
RIGHT Arrow	**Move to next Quick View**
HOME	**Fit All**
INSERT	**Insert Node**
PAGE UP	**Select / Move Up one elevation level (if defined)**
PAGE DOWN	**Select / Move Down one elevation level (if defined)**
END	**Show ALL elevation levels**
DEL	**Enter delete mode (select / fence airways to delete)**
CTRL Z	**UNDO**
CTRL Y	**REDO**
F1	**HELP**
F2	**Plan / Section Views (Toggle to cycle through views)**
F3	**FIND (Toggle to repeat last find command)**
F4	**FIND and HIGHLIGHT found airways**
F5	**Simulation Airflow**
F6	**Simulation Thermodynamic**
F7	**Hide / Show Zero Flow airways**
F8	**Hide / Show Excluded airways**
F9	**Transparencies on/off**
F12	**Save As**
T	**Show / Hide text data**
L	**Show / Hide limited data**
Z	**Zoom Mode**
D	**Draw or Add airway mode**
E	**Edit Mode**
S	**Select Mode**
M	**Move Mode**
C	**Copy Mode**
B	**Block Mode (for blocking / unblocking airways)**
R	**Reverse Mode (for reversing airways)**
Z	**Zoom Out**
P	**Perspective / Orthogonal Mode Toggle**
W	**Toggle between Wireframe and Solids**
G	**Display / Hide Grid**

N	**Display / Hide Nodes**
A	**Display / Hide Arrows**
I	**Display Hide Icons**



34 Appendix Table of Figures

Figure 4-1 Ventsim Visual™ Main Window 25
Figure 4-2 The Edit Plane, shown with the SHIFT key pressed 30
Figure 4-3 True Vertical Line showing top and bottom airways lining up 31
Figure 4-4 True Vertical Guide Line helps guide a shaft vertically into the airway below 31
Figure 4-5 Picture showing inclined airway being drawn down 32
Figure 4-6 Coordinate entry system 33
Figure 4-7 Example of copying a selected group of airways 35
Figure 5-1 Master File Options 38
Figure 5-2 File Security Options 40
Figure 5-3 An example of a Ventsim Visual™ Text File Loaded into Microsoft Excel 42
Figure 5-4 Import Option form showing DXF import options. 43
Figure 5-5 Export to DXF Options 45
Figure 5-6 Reference Graphics Manager 45
Figure 5-7 Automatic License Activation and Release 47
Figure 5-8 Clone Attributes 50
Figure 5-9 Find Airway Data 51
Figure 5-10 Example showing a ventilation fan recirculating air 56
Figure 5-11 Example of Summary Output with Description 60
Figure 5-12 Mine Summary Graphs 61
Figure 5-13 Spreadsheet view of model with selected data 64
Figure 5-14 Filtering Tools Combined 65
Figure 5-15 The simplify dialog box 65
Figure 5-16 Binding Tools 67
Figure 5-17 Duplicate Finding Tools 68
Figure 5-18 Filter Airways 69
Figure 5-19 Conversion Table 72
Figure 6-1 Example of limiting text display 76
Figure 7-1 Orthogonal Display 81
Figure 7-2 Perspective Display 81
Figure 7-3 Animation Speed Control 82
Figure 7-4 Manual airway drawing options 84
Figure 7-5 The Vent Duct Builder Dialog Box 84
Figure 7-6: Ramp Build Function 85
Figure 7-7 Multi Selection Options 86
Figure 7-8 Deletion options 87
Figure 7-9 An airway stopping 87
Figure 7-10 Contaminant placing options 89
Figure 7-11 Contaminant Options 91
Figure 8-1 Select a data category, followed by a data type 93
Figure 9-1 Edit Box Tabs 97
Figure 9-2 Airway Edit Box Form 100
Figure 9-3 Set airway names, coordinates and stages. 101
Figure 9-4 Set airway physical characteristics 101
Figure 9-5 Further Airway Options 103
Figure 9-6 Example of use of fresh / exhaust airway type colouring 105

Figure 9-7 Resistance, Friction and Shock Factors *105*
Figure 9-8 Edit Box Fan Information *108*
Figure 9-9 The Edit Box Heat Entry Tab (Advanced Version Only) *112*
Figure 9-10 Rock Condition entry for airways *115*
Figure 9-11 Edit Box Contaminant Input *117*
Figure 9-12 Airway Information Tab *119*
Figure 9-13 Heat Data *122*
Figure 9-14 Recording sheet for entering general airway information *123*
Figure 9-15 Attaching sensors to airways *124*
Figure 10-1 Model example before level selection *126*
Figure 10-2 Model example after level selection *126*
Figure 11-1 Preset Table Options *128*
Figure 12-1 Graphics Setting Options *141*
Figure 12-2 Graphics Setting Options *142*
Figure 12-3 Ventsim Visual™ Settings *144*
Figure 12-4 Simulation Contaminant Settings *147*
Figure 12-5 Simulation Environment Settings *149*
Figure 12-6 Simulation Heat Settings *156*
Figure 12-7 Ventsim Visual™ General Settings *159*
Figure 13-1 Airflow Calculator # 1 ..... *160*
Figure 13-2 Airflow Calculator # 2 ..... *161*
Figure 13-3 Diesel Heat Estimator *161*
Figure 13-4 Diesel Fuel Consumption Assistant *162*
Figure 13-5 Electric motor heat estimation *163*
Figure 13-6 Heat Assistant Screen *164*
Figure 15-1 Example of a Closed Model *172*
Figure 15-2 Example of an Open Model *172*
Figure 15-3 Imported DXF Lines *175*
Figure 15-4 Conversion of DXF lines to airways *176*
Figure 15-5 Example show the effect of the Simplify Function to reduce airway data *177*
Figure 15-6 Placing a fixed flow in an airway *180*
Figure 15-7 Example of import error after simulation resulting from misaligned ends or unjoined nodes *180*
Figure 15-8 Example showing ventilation duct into blind heading. *181*
Figure 16-1 Example of duct built *185*
Figure 16-2 Auxiliary ventilation of duct. *186*
Figure 16-3 Colours showing the relative internal pressure of the duct *186*
Figure 16-4 Multiple Ducts *187*
Figure 16-5 Partially changing the duct size *187*
Figure 16-6 Extending an auxiliary duct *188*
Figure 17-1 Example of contaminant sourcing narrowing down a smoke source. *192*
Figure 18-1 – Example of Blasting Gases at a monitor location *194*
Figure 18-2 : Placing a contaminant in an airway *195*
Figure 19-1 Inline Concentration (represented by the green icon) *200*
Figure 19-2 Example of Injected Gas *201*
Figure 19-3 Run the gas simulation option *203*
Figure 19-4 Change the text and colour to show gas concentrations *203*
Figure 20-1 Example of Heat in mine calculated by Ventsim after simulation *206*
Figure 20-2 Example of an inline cooler chilling ALL airflow *211*
Figure 20-3 Example showing same inline cooler chilling only 40% airflow *211*
Figure 21-1 Diesel Equipment with DPM emissions in Preset Values *215*
Figure 21-2 Diesel heat and DPM source placed in airway *216*
Figure 21-3 Example showing DPM simulation colouring through mine *216*
Figure 22-1 - Example above showing a single model divided into four (4) different stages. *217*
Figure 23-1 - Chart showing a complex buildup of Carbon Monoxide complicated by reversing and recirculating airflows *235*
Figure 26-1 : Financial Simulator Output showing life of mine airway costs *254*
Figure 26-2 Example of a Financial Simulation Table *255*

Figure 26-3 Global Optimisation *257*
Figure 26-4 High Cost Airways coloured to show clearly *258*
Figure 27-1 Set the starting edit location *262*
Figure 27-2 Enter the starting elevation of the drawing (edit) plane *262*
Figure 27-3 Construct an initial ramp decline *263*
Figure 27-4 : Draw horizontal airways from the ramp base *264*
Figure 27-5 Construct a shaft to the surface *264*
Figure 27-6 Draw multiple levels for the mine *265*
Figure 27-7 Edit the airway to set the airway size *266*
Figure 27-8 Add a fixed airflow to the airway *266*
Figure 27-9 Use the Edit – Info to view airway flow, pressure and power *267*
Figure 27-10 Colouring showing contamination spread time in seconds *267*
Figure 27-11 Initial imported DXF strings in Ventsim Visual *269*
Figure 27-12 The Level Elevation database *270*
Figure 27-13 Set airway layer names *270*
Figure 27-14 Initial selection of all decline airways *271*
Figure 27-15 Select and edit the decline airways *272*
Figure 27-16 Fresh and Exhaust Air Type colouring *272*
Figure 27-17 The final DXF import result showing the *273*
Figure 27-18 Resulting conversion with colour levels reset *274*
Figure 27-19 Airways coloured by airflow *276*
Figure 30-1 Customised Truck Picture *286*